

PROBE: FRONTIER CODING AGENTS FIND DIFFERENT BUGS THAN MAINTAINERS FIX

Marco Paina¹, Mark Niklas Müller¹, Niels Mündler-Sasahara², Martin Vechev²

¹ LogicStar.ai, ² ETH Zurich

{marco, mark}@logicstar.ai

 probebench.com  LogicStar/probe

ABSTRACT

Proactive bug discovery is an important software-engineering problem. Even though coding agents are already widely deployed in this domain, their capabilities remain understudied. In particular, the challenging task of finding all bugs that human maintainers would repair across an entire repository has not been studied yet. To close this gap, we introduce PROBE, a benchmark consisting of all 2,457 bugs fixed over the course of 18 months across 20 diverse GitHub repositories, together with a method for matching candidate findings to this partial reference set. We evaluate coding agents across frontier models and find they all achieve a recall of below 21% and a precision of less than 9% with respect to the reference set. While stronger models increase recall substantially from 8% to 17%, they do not improve precision. Surprisingly, despite the low precision, LLM and human evaluators still judge 85% of findings valid. Crucially, we find that found bug distributions are similar across agents but differ substantially from those of bugs fixed by maintainers. The practical relevance of bug discovery and the low recall of frontier models make this benchmark a valuable resource for both model users and developers.

1 INTRODUCTION

Coding agents have dramatically increased the pace at which code is being produced (LogicStar AI, 2025; GitHub, 2025), outpacing human review (He et al., 2026a; Xu et al., 2026). While coding agents have been shown to reliably fix bugs reported by humans (Jimenez et al., 2024; Deng et al., 2026), it is an open question whether they can also find such meaningful bugs autonomously, a capability receiving increasing commercial attention (OpenAI, 2026; Anthropic, 2026c; Cursor, 2026; cubic, 2026). Such a capability would ease the human burden of code review and application testing.

Prior work answers this question only incompletely, pointing the agent to a proposed patch or files known to contain a flaw (Zeng et al., 2026; Li et al., 2026), or focusing on security vulnerabilities (Wen et al., 2026; Guo et al., 2025; Li et al., 2025), often ones that can be reliably exploited (Zhang et al., 2025b; Shi et al., 2026a; Zhang et al., 2025a). Whether agents can find the bugs that maintainers would fix across a whole repository remains unexplored. Answering this question is hard, as the full set of bugs that a repository contains is unknown (Bird et al., 2009).

However, we observe that maintainers reveal which bugs matter to them by fixing them over time. We build PROBE on this signal (Figure 1): we snapshot 20 Python, JavaScript and TypeScript repositories at the start of 2025 and collect the 2,457 bugs present in the snapshot that maintainers fixed over the following 18 months. An LLM-based matcher scores findings against these bugs; on expert-labeled pairs of findings, it reaches 99% precision and 98% recall.

Asked to audit a whole repository, coding agents report only a handful of findings, recovering under 1% of the reference bugs. Prior bug finding agents (Mueller, 2025; Maaz et al., 2025) fare little better, achieving at most 3.2% recall. We therefore split each repository into small sets of files and audit each in a separate agent session, raising recall roughly tenfold.

Even with this harness, coding agents find few of the bugs maintainers fix: across ten models, the best configuration recovers only 20.8% of the reference bugs, and none exceeds 8.1% precision. Stronger models and higher reasoning effort raise recall mainly by reporting more findings (Pearson $r = 0.94$), while precision barely changes. Low precision does not mean that findings are incorrect.




Figure 1: Overview of PROBE. (1) We snapshot a repository at T_0 . (2a) We mine the maintainers’ commits in the reference window $T_0 \rightarrow T_1$, extract all bugs they fix, and keep those already present at T_0 as the reference set. (2b) The bug finder we are benchmarking audits the T_0 snapshot. (3) Reported bugs are matched against the reference set to compute recall and precision.

Since maintainers keep fixing snapshot bugs after the reference window, even a perfect bug finder would reach only an estimated 26–47% precision. Indeed, an independent panel of LLM judges, validated against a human grader, confirms 84% of the findings that do not match the reference set as real bugs. Thus, agent-found bugs are generally real, but different from those fixed by maintainers.

In addition, we find that all agents report similar bug types. It appears that their reported bugs are sampled from a distribution that differs substantially from that of maintainer-fixed bugs: agents over-report local correctness errors such as wrong arithmetic or comparisons (19% of agent findings vs. 10% of maintainer fixes), while maintainers more often fix incomplete input handling, such as a missing branch for a supported input variant (8% vs. 18%). This extends to individual bugs: within the same bug type, GPT-5.6 Luna runs overlap with each other a median of 6.3 times more than with maintainer fixes.

In conclusion, while agents find real bugs, they are mostly not the ones maintainers fix. Our benchmark PROBE makes this gap measurable.

Key Contributions Our three key contributions in this work are:

- PROBE, a benchmark of 2,457 maintainer-fixed bugs across 20 repositories for whole-repository bug finding, built by a validated pipeline applicable to any repository (§2).
- An evaluation of ten frontier models in a new multi-pass audit harness, with independent validation of findings beyond the reference set (§3 and §4).
- An analysis showing that agents agree with each other but not with maintainers (§4.2).

2 EVALUATING OPEN-ENDED BUG DISCOVERY

2.1 BENCHMARK CONSTRUCTION

Overview We provide an overview of our approach, illustrated in Figure 1. We collect a diverse set of open-source code repositories and take a snapshot at time T_0 (1st of January 2025). We then scrape all commits to the repository until T_1 (1st of July 2026); we call this time range the *reference window*. We analyze every commit during this period to extract fixed bugs. For every detected bug, we check whether it was already present at T_0 , and filter out bugs that were introduced in later commits. The remaining bugs form the *reference set*. This reference set is incomplete, as bugs still unfixed at T_1 are missing. Below, we provide more detail about each construction step and give all prompts for LLM-based steps in Appendix F.

Repository Curation We manually selected a total of 20 Python, JavaScript, and TypeScript repositories from diverse domains that are actively developed, do not depend on internet access, special hardware or third-party services, did not experience a major refactoring in the reference window, have at most 200k source lines of code at T_0 , and have a permissive license.

Environment Preparation We create historically faithful execution environments by using coding agents to set up Docker images for each repository, pinning the project dependencies to versions available at T_0 . We ensure that the repository test suite passes in this state and remove all historical revisions, tags and branches.

Reference Bug Collection Considering all commits, we aim to extract all bugs fixed during the reference window using the following six-step pipeline. We note that relying on explicit links to issues has been shown to lead to small and biased datasets (Bird et al., 2009). Unless otherwise specified, we use GPT-5.6 Terra (medium) for all steps requiring an LLM. Table 1 shows the number of commits and candidate bugs remaining after each stage.

Table 1: Commits and candidate bugs remaining after each stage of the bug collection pipeline. Δ is the change relative to the preceding stage.

Stage	Count	Δ
Commits	13,254	–
Bug-Fix Commits	4,296	–67.6%
Candidate Bugs	4,763	+10.9%
Anchored Candidates	3,345	–29.8%
Present Candidates	2,501	–25.2%
Deduplicated Bugs	2,457	–1.8%

1. **Identify Bug-Fix Commits.** We filter all commits on the main branch, treating merges as a single commit, using a combination of deterministic rules and LLM classification to identify bug-fix commits. First, we remove commits made by automated repository maintenance and edits that touch only generated or vendored files. Second, we use an LLM to classify whether the commit corrects any runtime behavior, based on the commit message, the patch, related user issues, and associated pull requests. We explicitly include commits that additionally contain non-bug-fixing changes.
2. **Extract Bugs.** From each bug-fix commit we extract all distinct *candidate bugs*, again using an LLM, splitting bugs that do not share a root cause. Each candidate bug contains a brief summary of the incorrect behavior and the key code hunks modified to resolve the bug.
3. **Anchor Code Changes.** Since we extract candidate bugs at the time of their fix T' ($T_0 < T'$), the affected code ranges need to be mapped back onto T_0 . To this end, we first trace file renames and then correct for lines added or removed between T_0 and T' . Lines that did not yet exist at T_0 are dropped. If no line survives, we try to relocate the block by its content or by its enclosing function name; if that fails too, the code was added or moved to a different file after T_0 and we remove the candidate bug.
4. **Check Bug Presence.** We verify whether a candidate bug was actually present at T_0 , using a coding agent with access to both the full revision history and the bug description. We additionally tell the agent whether AG-SZZ (Kim et al., 2006) traces the lines modified by the fix to commits already present at T_0 . If the agent establishes that the bug was absent at T_0 and only introduced by a later change, we exclude it. This also includes cases where inputs triggering the bug are not supported at T_0 . For this step, we use high reasoning effort.
5. **Synthesize Bug Reports.** We now synthesize a detailed bug report based on the original description of the incorrect behavior and the repository state at T_0 . The agent is instructed not to reference the fix in the report.
6. **Deduplicate Candidates.** Finally, we merge candidate bugs that describe the same defect, using our LLM-based bug matching, see §2.3, under a stricter criterion requiring a shared root cause.

2.2 BENCHMARK OVERVIEW

PROBE (Proactive Repository-wide Open-world Bug Evaluation) consists of 2,457 distinct bugs across 10 Python, 6 TypeScript, and 4 JavaScript repositories, covering diverse domains such as parsing, rendering, math, and workflow orchestration. We show core statistics in Table 2 and a per-repository breakdown in Figure 2 and Table 6. Every bug consists of a description of the incorrect behavior, a primary location in the snapshot at T_0 (line ranges, file, and repository), the surrounding code snippet, a severity and a suggested fix (more details in Appendix A.2).

Benchmark Validation We assess the quality of the reference set with a two-stage audit. First, we review all 2,457 reference bugs with a high-effort GPT-5.6 Terra agent with access to the repository history. It categorizes 209 bugs (8.5%) as incorrect (introduced after T_0 , no defect, not at indicated location, description contradicts code). Second, we manually label a stratified sample of 100 bugs, blind to the agent’s verdicts. This yields 12 rejected bugs, only weakly overlapping (6 bugs) with the 17 rejected by the agent. As agreement barely exceeds chance ($\kappa = 0.29$), we keep the whole set.

Table 2: Per-repository statistics of PROBE.

	Min	Mean	Max
# Files	17	223.4	657
# Lines (k)	2.1	57.0	122.9
# Tests	182	3,144.8	11,831
# Commits	75	662.7	3,465
# Bug-fixing commits	6	214.8	979
# Reference bugs	3	122.8	512




Figure 2: Reference bugs per repository.

Total Bug Pool Estimate We estimate the total number of bugs humans would eventually fix by modeling the rate at which T_0 bugs are fixed. We fit exponential, Weibull, and lognormal distributions and show the resulting fits in Figure 3. We observe a heavy tail with the lognormal distribution fitting the data best. Fitting the full data, we estimate between 5.2k and 5.9k bugs fixed within 5 years and between 7.2k and 9.4k within 10 years, see Table 9. As humans tend to discover more relevant bugs earlier, we assume bugs detected in the far future to be irrelevant. Given the observed 2,457 bugs, this implies a ceiling on precision of between 26% and 47% for a perfect bug finder that finds exactly the bugs humans would fix within 5 to 10 years. For a more detailed description of the model and the exact fitted parameters, see Appendix A.3.




Figure 3: Fix-position density observed (gray bars) and fitted based on the first half of each repository’s fix-commit sequence.

2.3 EVALUATION

Metrics We report recall, precision, and F1 score with respect to the reference set. Recall is the proportion of reference bugs that were matched by an agent finding. Precision is the proportion of findings that match reference bugs. We additionally report cost for one run in USD at API prices.

Bug Matching Reliably matching findings to reference bugs is essential for the validity of our evaluation. We thus propose the following two-step method, which considers all pairs of bugs using their description, code snippet, and line ranges, so a bug finder must provide at least this information. This approach costs about \$5–8 per 1,000 findings.

1. **Rule-based Filter.** We compute six similarity metrics per bug pair: line overlap, cosine similarities of an embedding of the description and an embedding additionally considering the code snippet, and inverse document frequency-weighted Jaccard similarities of the tokenized code snippet, identifiers in the code snippet and description, and called function identifiers. If any metric exceeds a threshold tuned to avoid false negatives with respect to the second stage, we retain the pair. For details on the metrics and thresholds, see Table 10.
2. **LLM-based Judge.** We instruct Gemini 3.5 Flash, given the description, line range, and code snippet for both bugs, to determine whether resolving the underlying root cause for either one of them would also resolve the other. If so, we count them as matching.

We validate this approach on 307 findings across 3 repositories with 67 expert-validated matches. Of the 17,177 within-repository pairs, 2.7% pass the rule-based filter, including all matches. All removed pairs were also rejected by the LLM judge in a validation experiment. Across 5 runs of the judge, precision averages 98.8% and recall 97.6%, with each run identifying 65 or 66 of the 67 matches and marking at most 1 additional pair as a match. For more details, see Appendix A.4.

Independent Bug Validation To assess precision beyond the incomplete reference set, we use a two-tiered panel of agents. If the first tier (GPT-5.6 Luna and Gemini 3.5 Flash) disagrees, we refer the finding to a second tier (Claude Opus 5 and GPT-5.6 Terra; GPT-5.6 Sol often refused to answer due to cybersecurity guardrails), reporting an inconclusive result if they disagree. All judges are instructed to produce a proof of concept demonstrating the described bug on a real user input, given the snapshot codebase and the bug report. We report validity rate as the proportion of confirmed findings, ignoring inconclusive results. See Appendix F.6.2 for the exact instructions.

3 BUG FINDING HARNESS

As we observe vanilla coding agents to achieve $< 1\%$ recall when asked to audit a whole repository (Table 5), we propose a harness boosting recall. To this end, we partition a repository’s files, where each partition is reviewed in a separate *pass* with access to the whole repository and a context document. Every model receives identical file partitions and context documents.

Preprocessing For every repository, we create two auxiliary documents, shared across all passes: i) a *context document* compiled by a Claude Opus 5 exploration agent (Appendix F.5.1), describing the project’s purpose, architecture, public API and supported inputs; ii) a function-level call graph of the non-test source files, built with Python’s `ast` module or the TypeScript compiler API.

File Partitioning We partition all non-test source files by complexity and size. We score every file by its number of cross-file callers and callees, its size, and its number of functions. The most complex files are assigned their own group, while the rest are grouped by directory, splitting groups that exceed a budget of 60k tokens. Across the 20 repositories, this yields between 5 and 90 passes each, with a total of 740 passes covering 4,468 files. See Appendix B for more details.

Prompt Construction The prompt is constructed from the audit instructions (Appendix F.5.2), the context document, the full target files, a call graph excerpt, and short snippets of callers and callees in other files. The agent is tasked to report each bug in JSON format using the same fields as the reference bugs (see Table 7) plus a confidence score. We remove findings violating the schema.

Execution and Isolation We run each pass with a timeout of three hours in a separate Docker container with historically faithful dependencies, but without revision history. Network access and the CLIs’ web search tools are disabled.

4 EXPERIMENTAL EVALUATION

Experimental Setup We evaluate ten models: GPT-5.6 Luna, Terra and Sol; GPT-5.4; Claude Sonnet 5 and Opus 5 (Appendix C.1); Gemini 3.5 Flash; GLM 5.3 Flash; DeepSeek V4.1 Flash; and Muse Spark 1.3. We run Anthropic, OpenAI, and Google models in their vendors’ coding-agent CLIs and the remaining models using Codex CLI. Unless otherwise specified, we use medium reasoning effort for the OpenAI, Anthropic and Google models and high effort for GLM 5.3 Flash, DeepSeek V4.1 Flash and Muse Spark 1.3, evaluate all models with our harness, and run each configuration once for cost reasons.

4.1 AGENTS RECOVER FEW MAINTAINER-FIXED BUGS

Historical Recall and Precision We compare different models in Table 3 (Appendix C.2) and observe that all agents recover only a small share of the historical bugs, with even the best run achieving less than 21% recall and at most 8.1% precision. While recall varies significantly across models, mostly determined by the total number of findings (Pearson $r = 0.94$), precision is much more consistent. Interestingly, some of the cheapest models (DeepSeek V4.1 Flash, GPT-5.6 Luna (xhigh), and GLM 5.3 Flash) exceed GPT-5.6 Sol (medium) in F1 score at less than a fifth of its cost.



Figure 4: F1 scores over API cost. GPT-5.6 Luna (blue) and Sol (orange) across reasoning efforts. Reruns are faint markers.

Reasoning Effort We evaluate GPT-5.6 Luna at low to xhigh reasoning effort, visualizing the resulting F1 score in Figure 4. We find that while precision stays constant, recall increases substantially from 5.3% to 17.3% as cost increases from \$8 to \$131. GPT-5.6 Luna (xhigh) thus strictly dominates GPT-5.6 Sol (medium) in terms of cost, recall, and precision. Evaluating GPT-5.6 Sol at low to high effort shows the same trend, with recall rising from 11.4% to 20.8% as cost rises from \$276 to \$1,185.

Table 3: Recall, precision, and F1 score w.r.t. the reference set, sorted by F1, with the effort sweeps of GPT-5.6 Sol and GPT-5.6 Luna last, from highest to lowest reasoning effort. Cells for Muse Spark 1.3 and GPT-5.6 Luna (medium) are means over 5 and 10 runs, respectively.

Model	Effort	Recall (%)	Precision (%)	F1 (%)	Findings	Cost
DeepSeek V4.1 Flash	high	15.2	8.1	10.5	5,019	\$73
GLM 5.3 Flash	high	15.8	7.0	9.7	6,029	\$120
GPT-5.4	medium	11.0	6.9	8.5	4,204	\$655
GPT-5.6 Terra	medium	9.1	7.6	8.3	3,093	\$224
Gemini 3.5 Flash	medium	9.8	6.4	7.8	3,867	\$493
Muse Spark 1.3	high	15.9	4.8	7.4	8,372	\$164
Claude Sonnet 5	medium	7.9	5.8	6.7	3,472	\$421
GPT-5.6 Sol	high	20.8	6.7	10.2	8,285	\$1,185
	medium	16.9	6.7	9.6	6,675	\$678
	low	11.4	7.5	9.0	3,903	\$276
GPT-5.6 Luna	xhigh	17.3	7.1	10.1	6,636	\$131
	high	13.0	6.9	9.0	5,017	\$55
	medium	7.6	7.0	7.3	2,774	\$15
	low	5.3	6.5	5.8	2,027	\$8

4.2 AGENTS FIND DIFFERENT BUGS THAN MAINTAINERS FIX

Most Unmatched Bugs Are Still Valid To test whether low precision w.r.t. the reference set means that most findings are not in fact bugs, we validate 100 findings each for nine models using our agent panel (Figure 5; details in Table 14). It confirms 96% of the findings that match the reference set and 84% of those that do not as correct. Three of the four models with the lowest precision (Claude Sonnet 5, Gemini 3.5 Flash and Muse Spark 1.3) also have significantly lower validity (64–73% vs. 89–95%). Manually grading 180 of these findings blind to the model and the panel’s verdict, we agree with the panel on 93% of the 131 findings that neither judged inconclusive ($\kappa = 0.77$; Appendix C.3). Low precision thus mostly reflects real bugs outside the reference set.




Figure 5: Bug validity assessed by the LLM panel over precision w.r.t. the reference set, with 95% confidence intervals. For GPT-5.6 Luna and Muse Spark 1.3, both axes use their first run.

However, since agents show no preference for earlier- or later-fixed bugs (Appendix C.4), extrapolating their precision of about 7% to our estimate of all T_0 bugs fixed within ten years (Table 9) yields a precision of only 21–27%. With 85% of findings considered valid, more than two-thirds of the valid bugs agents report would thus remain unfixed for at least a decade at the maintainers’ current pace.

Agents and Humans Find Different Bug Types To investigate this mismatch, we categorize all bugs found by agents and humans into 33 bug types (see Appendix D for how we build them and their full distributions) and compare their distributions. We observe in Figure 6 that all agents find bugs with relatively similar category distributions while the human distribution is quite different.




Figure 6: Jensen-Shannon distance of the bug-type distribution of each agent run to the other runs and of the human reference set to all runs.

Comparing the five bug types most over- and under-represented among agent findings relative to human ones (Table 4), we observe that agents tend to over-report local faults, such as wrong arithmetic or comparisons and unhandled degenerate values, while humans focus on incomplete handling of inputs and errors in the public API surface. We hypothesize that humans are more likely to find and fix bugs that cause a mismatch between described and implemented behavior or observable failures when running the code or using its public API, while coding agents are more likely to find logical bugs that cause subtly incorrect behavior. Categorizing what is needed to trigger incorrect

Table 4: Bug types most over- (top) and under-represented (bottom) among agent findings relative to the human reference set, by gap in percentage points (pp). Agent counts ($\bar{n}$) and shares are means over one run of each of the 14 configurations.

Category	Human		Agents		Gap (pp)	Ratio
	n	%	$\bar{n}$	%		
Wrong arithmetic or comparison expression	243	9.9	916	18.5	+8.6	1.86
Unhandled degenerate value	222	9.1	674	13.9	+4.8	1.53
Incorrect regular expression pattern	47	1.9	245	4.7	+2.8	2.47
Missing state reset or restoration	57	2.3	242	4.9	+2.6	2.11
Wrong data source read	57	2.3	224	4.5	+2.1	1.91
Missing branch for a supported input variant	439	18.0	400	7.7	-10.3	0.43
Missing dispatch or lookup table entry	124	5.1	38	0.7	-4.3	0.14
Incorrect public type declaration	111	4.5	57	1.1	-3.5	0.24
Unimplemented advertised feature	114	4.7	133	2.6	-2.0	0.56
Wrong dispatch or lookup table entry	102	4.2	130	2.6	-1.6	0.63

behaviors (Appendix D.4), we observe that humans find more bugs requiring specific environments (10.8% vs. 4.7% for agents) or visual inspection of outputs (3.8% vs. 0.7%), while agent findings more often need only a specific input (83.9% vs. 74.3% for humans).

Agents and Humans Find Different Bugs of the Same Type

This mismatch extends to findings within a category. Per bug type, we divide a run’s recall w.r.t. another run of the same agent by its recall w.r.t. the human reference set, pooling over all pairs of runs. If this normalized recall ratio is 1, the agent runs overlap with each other just as much as with the human reference set. If it is higher, they agree more with each other than with the human reference set. We observe in Figure 7 that across the 28 bug types with at least ten human and agent findings, the ratio has a minimum of 2.9 and a median of 6.3 for GPT-5.6 Luna.




Figure 7: Per-category overlap of repeated GPT-5.6 Luna runs compared to human-fixed bugs.

This agreement extends to other models. Analyzing the likelihood of another model finding a reference bug, conditioned on GPT-5.6 Luna finding it in exactly n of 9 runs (Figure 8), we see it rise from 5% for the bugs no run finds to 87% for the bugs all 9 find. In contrast, sampling bugs at the same recall uniformly at random per category would give 12–17%.




Figure 8: Share of reference bugs that other models find, conditioned on how many of 9 Luna runs find the bug. The dashed line picks bugs at random within each type; the orange line is a held-out tenth Luna run.

4.3 FURTHER ANALYSIS

Our Audit Harness and Prior Bug Finders

We ablate our bug finding harness using Claude Sonnet 5 and GPT-5.6 Luna in Table 5. *Vanilla* uses a single coding agent session of the native CLI with a basic prompt (see Appendix F.5.3). *Passes* keeps the 740 passes of our harness, but replaces our audit instructions, context document, file contents and call graph with a minimal prompt listing the pass’s target files (see Appendix F.5.4). The *Vanilla* setting reports < 100 total findings across 20 repositories, leading to a recall of < 1% while achieving strong precision. Adding the multi-pass structure but not the full context leads to both a recall and precision between the full harness and the single prompt, at a lower F1 score and higher cost compared to our harness. Comparing against two prior LLM-based bug finders, we observe Hound (Mueller, 2025), a security audit agent, achieving less than half our recall at a lower precision and 8.6× the cost, and agentic-pbt

Table 5: Comparison of our bug finding harness against a single prompt (Vanilla), the same pass decomposition but with a minimal prompt (Passes), and prior methods: Hound (Mueller, 2025) and agentic-pbt (Maaz et al., 2025). Recall, precision and F1 are in %.

Dataset	Model	Method	Recall (%)	Precision (%)	F1 (%)	Findings	Cost
Full	Claude Sonnet 5	Vanilla	0.6	17.4	1.2	86	\$94
		Passes	5.3	8.0	6.4	1,656	\$487
		Full harness (ours)	7.9	5.8	6.7	3,472	\$421
	GPT-5.6 Luna	Vanilla	0.9	32.3	1.7	65	\$1
		Passes	5.8	8.3	6.8	1,826	\$18
		Hound	3.2	5.0	3.9	1,371	\$129
		Full harness (ours)	7.6	7.0	7.3	2,774	\$15
	Python Only	agentic-pbt (medium)	0.9	15.5	1.7	97	\$4
		agentic-pbt (high)	0.9	8.9	1.6	180	\$9
		Full harness (ours)	6.1	6.7	6.4	1,412	\$7

(Maaz et al., 2025), which employs property-based testing and only supports Python, achieving $< 1\%$ recall at good precision.

Ensembling Multiple Runs Across reruns of Muse Spark 1.3 (5) and GPT-5.6 Luna (10), the standard deviations of recall (0.66 and 0.48 pp) and precision (0.20 and 0.32 pp, respectively) are relatively small. However, on average only 63% and 57% of one run’s findings are also reported by another run. Thus, ensembling runs by reporting only findings that repeat at least n times across runs allows us to trade off recall and precision as illustrated in Figure 9. For example, the union of all Muse Spark 1.3 runs achieves a recall of 26.7% and the intersection of all GPT-5.6 Luna runs achieves a precision of 10.5%, both exceeding the best single-run performance. This shows that findings with a higher report probability are more likely to match human findings. We explore this further in Appendix E where we show that the bug finding process is well modeled by a stable-beta process, characterized by a stable core of high-probability findings and an infinite pool of rare findings.




Figure 9: Historical precision and recall for findings reported in at least n of 10 (Luna) or 5 (Muse Spark) runs, from $n = 1$ (union) to all runs (intersection). Faint curves use only the first two or five runs.

Time Preferences in Matched Bugs We show in Appendix C.4 that there is no detectable preference for agents finding earlier- or later-fixed bugs across models (Holm-adjusted p -values ≥ 0.20). As the reference window contains the knowledge cut-offs of all tested models that publish one (Table 17), we find no evidence of contamination for them; for GLM 5.3 Flash, Muse Spark 1.3 and DeepSeek V4.1 Flash, released after T_1 without a published cut-off, the test cannot rule it out.

5 RELATED WORK

Repository-Level Maintenance A plethora of prior work has studied autonomous bug resolution (Jimenez et al., 2024; Deng et al., 2026; Yang et al., 2025). Much less has investigated code maintenance tasks, such as refactoring (Thillen et al., 2026; Shi et al., 2026b), test generation (Mündler et al., 2024) or code optimization (Press et al., 2025; He et al., 2026b). To our knowledge, no prior benchmark evaluates general repository-wide bug discovery.

Restricted Bug Detection Prior work on autonomous bug detection focuses on investigating specific files or patches: SWR-Bench (Zeng et al., 2026) provides agents with a pull request and asks them to generate review comments on the issues that require changes, including software bugs. Active-SWE (Li et al., 2026) mines historical bugs and measures whether agents can detect and

resolve concrete bugs when provided with the affected files. In contrast, our work tasks agents to report all defects across an entire repository.

Repository-Level Vulnerability Detection Cybench (Zhang et al., 2025b) requires agents to autonomously discover and exploit software vulnerabilities, but is limited to artificially constructed targets. CyberGym-E2E (Shi et al., 2026a) measures vulnerability detection, exploitation and patching on historical OSS-Fuzz vulnerabilities in open-source projects. BountyBench (Zhang et al., 2025a) is based on real-world open-source projects with associated bug bounties. In contrast, our work considers general software bugs beyond security vulnerabilities.

Bug Detection Methods Guo et al. (2025) propose a repository-level auditing agent that follows data flow to detect null-pointer dereferences, memory leaks and use-after-free bugs. Lin et al. (2026) focus on defensive coding patterns and find instances with similar context but lacking defenses. Wen et al. (2026) evaluate repository-level vulnerability detection that retrieves vulnerability-related dependencies from call graphs. Li et al. (2025) propose to combine LLMs with static analysis reports to discover security vulnerabilities. None of these methods targets the setting of general software bugs we study.

6 LIMITATIONS

Maintainer fixes as the reference The reference set contains only bugs fixed within 18 months, and an unfixed bug is not necessarily unimportant: maintainers may be unaware of it or lack the capacity to fix it. However, we estimate how many snapshot bugs maintainers would fix within 5 to 10 years, which caps precision at 26–47% (§2.2). Our conclusions do not hinge on the exact value, as even the tightest ceiling is three times the best observed precision. Recall, in contrast, does not depend on when a bug was fixed (Appendix C.4) and thus likely carries over to bugs fixed later. Further, if capacity alone limited fixes, unfixed bugs would resemble fixed ones in type; instead, agent findings differ systematically from maintainer fixes (§4.2), so the reference set reflects maintainers’ priorities rather than a random sample of bugs.

Benchmark scope PROBE covers 20 repositories from diverse domains in the three most used languages on GitHub (GitHub, 2025). However, these languages share certain properties that prevent specific types of bugs, e.g., they are all memory-safe and thus exclude memory-safety bugs. Moreover, our curation excluded codebases beyond 200k lines. As our pipeline applies to any repository with a commit history and needs no manual bug labeling, we believe natural extensions to additional languages and repositories are interesting items for future work.

Bug finding methods Other harnesses could yield different results. Ours is identical across models, isolating model differences, and outperforms both single-session agents and prior methods (Table 5); as each pass can access the whole repository, agents are not restricted to local reasoning. However, maintainer-fixed bugs more often need a specific environment, a person inspecting the output, or particular timing to surface (Appendix D.4), while the evaluated agents primarily inspect code. Methods that exercise software as its users do could find bugs closer to those maintainers fix, an exciting direction for future work.

7 CONCLUSION

We introduced PROBE, the first benchmark for whole-repository bug discovery that uses the bugs maintainers fix as its reference. Across ten models, coding agents recover few of these bugs at low precision, achieving a maximum recall of 20.8%. Stronger models and higher reasoning effort mostly yield more findings rather than better ones. Yet most findings are real bugs, as an independent panel of LLM judges confirms. We investigate this and find that they just differ systematically from the bugs maintainers fix: LLM-found bugs disproportionately involve local faults, such as wrong arithmetic or comparisons and unhandled degenerate values, while human-fixed bugs more often concern incomplete input handling and errors in the public API surface. We believe that finding the bugs that matter to humans is a key frontier for scaling automated software engineering, and that PROBE makes progress toward it measurable.

REFERENCES

- Anthropic. Claude Opus 5, 2026a. URL <https://platform.claude.com/docs/en/models/opus-5/overview>. Accessed 2026-09-25.
- Anthropic. Claude Sonnet 5, 2026b. URL <https://platform.claude.com/docs/en/models/sonnet-5/overview>. Accessed 2026-09-25.
- Anthropic. Project Glasswing: Securing critical software for the AI era, 2026c. URL <https://www.anthropic.com/glasswing>. Accessed 2026-09-25.
- Marco Battiston, Stefano Favaro, Daniel M. Roy, and Yee Whye Teh. A characterization of product-form exchangeable feature probability functions. *The Annals of Applied Probability*, 28(3): 1423–1448, 2018. doi: 10.1214/17-AAP1333.
- Christian Bird, Adrian Bachmann, Eirik Aune, John Duffy, Abraham Bernstein, Vladimir Filkov, and Premkumar Devanbu. Fair and balanced? Bias in bug-fix datasets. In *Proceedings of the 7th Joint Meeting of the European Software Engineering Conference and the ACM SIGSOFT Symposium on The Foundations of Software Engineering, ESEC/FSE '09*, pp. 121–130, New York, NY, USA, 2009. Association for Computing Machinery. ISBN 9781605580012. doi: 10.1145/1595696.1595716. URL <https://doi.org/10.1145/1595696.1595716>.
- Tamara Broderick, Michael I. Jordan, and Jim Pitman. Beta processes, stick-breaking and power laws. *Bayesian Analysis*, 7(2):439–476, 2012. doi: 10.1214/12-BA715.
- cubic. AI codebase scans for bugs and vulnerabilities, 2026. URL <https://www.cubic.dev/codebase-scans>. Accessed 2026-09-25.
- Cursor. Bugbot, 2026. URL <https://cursor.com/bugbot>. Accessed 2026-09-25.
- DeepSeek. Change Log, 2026. URL <https://api-docs.deepseek.com/updates/>. Accessed 2026-09-25.
- Xiang Deng, Jeff Da, Edwin Pan, Yannis Yiming He, Charles Ide, Kanak Garg, Niklas Lauffer, Andrew Park, Chetan Rane, Karmini Sampath, Maya Krishnan, Srivatsa Kundurthy, Sean M. Hendryx, Zifan Wang, Chen Bo Calvin Zhang, Noah Jacobson, Bing Liu, and Brad Kenstler. SWE-Bench Pro: Can AI agents solve long-horizon software engineering tasks? In *ICML*, 2026.
- GitHub. Octoverse: A new developer joins GitHub every second as AI leads TypeScript to #1, 2025. URL <https://github.blog/news-insights/octoverse/octoverse-a-new-developer-joins-github-every-second-as-ai-leads-typescript-to-1/>. Accessed 2026-09-25.
- Google. What’s new in Gemini 3.5 Flash, 2026. URL <https://ai.google.dev/gemini-api/docs/whats-new-gemini-3.5>. Accessed 2026-09-25.
- Jinyao Guo, Chengpeng Wang, Xiangzhe Xu, Zian Su, and Xiangyu Zhang. RepoAudit: An autonomous LLM-agent for repository-level code auditing. In *ICML*, 2025.
- Hao He, Shyam Agarwal, Yegor Denisov-Blanch, Pavel Azaletskiy, Sanmi Koyejo, and Bogdan Vasilescu. AI writes faster than humans can review: A longitudinal study of an enterprise 2x mandate, 2026a. URL <https://arxiv.org/abs/2607.01904>.
- Xinyi He, Qian Liu, Mingzhe Du, Lin Yan, Zhijie Fan, Yiming Huang, Yin Zheng, Zejian Yuan, and Zejun Ma. SWE-Perf: Can language models optimize code performance on real-world repositories? In *ICML*, 2026b.
- J. L. Hodges, Jr. The significance probability of the Smirnov two-sample test. *Arkiv för Matematik*, 3(5):469–486, 1958. doi: 10.1007/BF02589501.
- Sture Holm. A simple sequentially rejective multiple test procedure. *Scandinavian Journal of Statistics*, 6(2):65–70, 1979. URL <https://www.jstor.org/stable/4615733>.
- Carlos E. Jimenez, John Yang, Alexander Wettig, Shunyu Yao, Kexin Pei, Ofir Press, and Karthik R. Narasimhan. SWE-bench: Can Language Models Resolve Real-world GitHub Issues? In *ICLR*, 2024. URL <https://openreview.net/forum?id=VTF8yNQm66>.

- Sunghun Kim, Thomas Zimmermann, Kai Pan, and E. James Whitehead, Jr. Automatic identification of bug-introducing changes. In *21st IEEE/ACM International Conference on Automated Software Engineering (ASE'06)*, pp. 81–90, 2006. doi: 10.1109/ASE.2006.23.
- Haobin Li, Ping Deng, Weizhong Qian, Liang Jiang, Zhenyu Huang, Mouxing Yang, and Xi Peng. Active-SWE: Benchmarking coding agents for proactive bug fixing without issue reports, 2026. URL <https://arxiv.org/abs/2608.04682>.
- Ziyang Li, Saikat Dutta, and Mayur Naik. IRIS: LLM-assisted static analysis for detecting security vulnerabilities. In *ICLR*, 2025. URL <https://arxiv.org/abs/2405.17238>.
- Miaoqian Lin, Kai Chen, and Hao Chen. BugAuditor: Detecting bugs via inconsistent defensive code auditing. In *35th USENIX Security Symposium (USENIX Security 26)*, pp. 4011–4030, Baltimore, MD, August 2026. USENIX Association. ISBN 978-1-939133-58-8. URL <https://www.usenix.org/conference/usenixsecurity26/presentation/lin-miaoqian>.
- LogicStar AI. Agents in the Wild, 2025. URL <https://insights.logicstar.ai/>. Accessed 2026-09-25.
- Muhammad Maaz, Liam DeVoe, Zac Hatfield-Dodds, and Nicholas Carlini. Agentic Property-Based Testing: Finding Bugs Across the Python Ecosystem. In *NeurIPS 2025 Fourth Workshop on Deep Learning for Code*, 2025. URL <https://arxiv.org/abs/2510.09907>.
- Meta. Introducing Muse Spark 1.3, 2026. URL <https://research.meta.ai/blog/introducing-muse-spark-1-3>. Accessed 2026-09-25.
- Bernhard Mueller. Hound: Relation-First Knowledge Graphs for Complex-System Reasoning in Security Audits. *arXiv preprint arXiv:2510.09633*, 2025. URL <https://arxiv.org/abs/2510.09633>.
- Niels Mündler, Mark Niklas Müller, Jingxuan He, and Martin Vechev. SWT-Bench: Testing and Validating Real-world Bug-fixes with Code Agents. In *NeurIPS*, 2024. URL http://papers.nips.cc/paper_files/paper/2024/hash/94f093b41fc2666376fb1f667fe282f3-Abstract-Conference.html.
- OpenAI. Codex Security: now in research preview, 2026. URL <https://openai.com/index/codex-security-now-in-research-preview/>. Accessed 2026-09-26.
- OpenAI. GPT-5.4 Model, 2026a. URL <https://developers.openai.com/api/docs/models/gpt-5.4>. Accessed 2026-09-25.
- OpenAI. GPT-5.6 Luna Model, 2026b. URL <https://developers.openai.com/api/docs/models/gpt-5.6-luna>. Accessed 2026-09-25.
- OpenAI. GPT-5.6 Sol Model, 2026c. URL <https://developers.openai.com/api/docs/models/gpt-5.6-sol>. Accessed 2026-09-25.
- OpenAI. GPT-5.6 Terra Model, 2026d. URL <https://developers.openai.com/api/docs/models/gpt-5.6-terra>. Accessed 2026-09-25.
- Belinda Phipson and Gordon K. Smyth. Permutation p-values should never be zero: Calculating exact p-values when permutations are randomly drawn. *Statistical Applications in Genetics and Molecular Biology*, 9(1):Article 39, 2010. doi: 10.2202/1544-6115.1585.
- Ori Press, Brandon Amos, Haoyu Zhao, Yikai Wu, Samuel Ainsworth, Dominik Krupke, Patrick Kidger, Touqir Sajed, Bartolomeo Stellato, Jisun Park, Nathanael Bosch, Eli Meril, Albert Steppi, Arman Zharmagambetov, Fangzhao Zhang, David Pérez-Piñeiro, Alberto Mercurio, Ni Zhan, Talor Abramovich, Kilian Lieret, Hanlin Zhang, Shirley Huang, Matthias Bethge, and Ofir Press. AlgoTune: Can language models speed up general-purpose numerical programs? In *NeurIPS Datasets and Benchmarks Track*, 2025.

- Tianneng Shi, Robin Rheem, Dongwei Jiang, Mona Wang, Francisco De La Riega, Zhun Wang, Jingzhi Jiang, Alexander Cheung, Sean Tai, Jonah Cha, Jianhong Tu, Gabriel Han, Chenguang Wang, Jingxuan He, Wenbo Guo, and Dawn Song. CyberGym-E2E: Scalable real-world benchmark for AI agents’ end-to-end cybersecurity capabilities. In *ICML*, 2026a. URL <https://arxiv.org/abs/2606.04460>.
- Yuling Shi, Jinghan Xu, Kelin Fu, Wenhao Zeng, Yingwei Ma, Shilin He, Lei Zhang, Yue Liu, Zelin Zhao, Terry Yue Zhuo, Jialun Cao, Siyu Ye, Tianyu Liu, Kai Cai, Shing-Chi Cheung, and Xiaodong Gu. SWE-Bench ProMax: Benchmarking agents on large-scale multilingual code refactoring. In *Conference on Language Modeling*, 2026b.
- Yee Whye Teh and Dilan Görür. Indian buffet processes with power-law behavior. In *Advances in Neural Information Processing Systems*, volume 22, pp. 1838–1846, 2009. URL https://papers.nips.cc/paper_files/paper/2009/file/f1b6f2857fb6d44dd73c7041e0aa0f19-Paper.pdf.
- Romain Thibaux and Michael I. Jordan. Hierarchical beta processes and the Indian buffet process. In *Proceedings of the Eleventh International Conference on Artificial Intelligence and Statistics*, volume 2 of *Proceedings of Machine Learning Research*, pp. 564–571, 2007. URL <https://proceedings.mlr.press/v2/thibaux07a.html>.
- Alex Thillen, Niels Mündler, Veselin Raychev, and Martin Vechev. CodeTaste: Can LLMs Generate Human-Level Code Refactorings? In *ICML*, 2026. URL <https://arxiv.org/abs/2603.04177>.
- Xin-Cheng Wen, Xinchun Wang, Yujia Chen, Ruida Hu, David Lo, and Cuiyun Gao. From function to repository: Towards repository-level evaluation of software vulnerability detection. *IEEE Transactions on Software Engineering*, 52(4):1315–1331, 2026. doi: 10.1109/TSE.2026.3662145.
- Feiyang Xu, Poonacha K. Medappa, Murat M. Tunc, Martijn Vroegindewij, and Jan C. Fransoo. AI-assisted programming decreases the productivity of experienced developers by increasing the technical debt and maintenance burden, 2026. URL <https://arxiv.org/abs/2510.10165>.
- John Yang, Carlos E. Jimenez, Alex Zhang, Kilian Lieret, Joyce Yang, Xindi Wu, Ori Press, Niklas Muennighoff, Gabriel Synnaeve, Karthik Narasimhan, Diyi Yang, Sida Wang, and Ofir Press. SWE-bench Multimodal: Do AI systems generalize to visual software domains? In *ICLR*, 2025.
- Z.ai. New Released, 2026. URL <https://docs.z.ai/release-notes/new-released>. Accessed 2026-09-25.
- Zhengran Zeng, Ruikai Shi, Keke Han, Yixin Li, Kaicheng Sun, Yidong Wang, Zhuohao Yu, Rui Xie, Wei Ye, and Shikun Zhang. SWR-Bench: Assessing LLM performance in real-world code review comment generation. *Proceedings of the ACM on Software Engineering*, 3(FSE):3093–3115, 2026. doi: 10.1145/3808144.
- Andy K. Zhang, Joey Ji, Celeste Menders, Riya Dulepet, Thomas Qin, Ron Y. Wang, Junrong Wu, Kyleen Liao, Jiliang Li, Jinghan Hu, et al. BountyBench: Dollar Impact of AI Agent Attackers and Defenders on Real-World Cybersecurity Systems. In *NeurIPS Datasets and Benchmarks Track*, 2025a. URL <https://arxiv.org/abs/2505.15216>.
- Andy K. Zhang, Neil Perry, Riya Dulepet, Joey Ji, Celeste Menders, Justin Lin, Eliot Jones, Gashon Hussein, Samantha Liu, Donovan Jasper, Pura Peetathawatchai, Ari Glenn, Vikram Sivashankar, Daniel Zamoshchin, Leo Glikbarg, Derek Askaryar, Haoxiang Yang, Aolin Zhang, Rishi Alluri, Nathan Tran, Rinnara Sangpisit, Kenny Oseleononmen, Dan Boneh, Daniel Ho, and Percy Liang. Cybench: A framework for evaluating cybersecurity capabilities and risks of language models. In *ICLR*, 2025b.

A BENCHMARK DETAILS

A.1 THE REPOSITORIES

Table 6 lists the 20 repositories of PROBE by their GitHub names, grouped by language and sorted by reference bugs; elsewhere we refer to them by repository name alone.

Table 6: The 20 repositories of PROBE. Files and kLOC count the audited non-test source files (Appendix B), and Passes the audit passes they are split into (§3). Tests counts the tests that pass at the snapshot in our Docker image (for echarts, its unit tests only). Commits and Fix com. (bug-fixing commits) are counted over the 18-month reference window, and Bugs are the reference bugs they yield.

Repository	Domain	Files	Passes	kLOC	Tests	Commits	Fix com.	Bugs
tobymao/sqlglot	SQL parsing	70	16	49.9	646	2,848	979	512
prefecthq/prefect	Workflow orchestration	420	70	119.5	11,831	3,465	910	429
py-pdf/pypdf	PDF manipulation	52	14	35.7	562	562	190	165
kozea/weasyprint	HTML/CSS rendering	65	19	30.5	3,053	315	196	115
fonttools/fonttools	Font tooling	308	69	122.1	4,372	318	108	113
networkx/networkx	Graph algorithms	283	44	112.5	5,646	481	93	84
opshin/opshin	Smart-contract compiler	49	12	10.8	411	213	63	51
pygments/pygments	Syntax highlighting	330	47	122.9	5,122	165	46	41
hgrecco/pint	Units and quantities	73	15	16.4	2,170	88	34	28
python-jsonschema/jsonschema	Schema validation	23	5	4.9	7,675	167	6	6
<i>Python (10)</i>		1,673	311	625.1	41,488	8,622	2,625	1,544
honojs/hono	Web framework	167	35	19.9	3,268	431	181	144
apache/echarts	Charting	550	90	120.2	182	110	58	46
harttle/liquidjs	Template engine	120	32	5.9	1,416	103	33	32
remeda/remeda	Functional utilities	309	8	26.3	1,935	231	41	30
panva/jose	Cryptography	111	23	8.7	282	248	17	3
msgpack/msgpack-javascript	Serialization	17	5	2.1	316	75	8	3
<i>TypeScript (6)</i>		1,274	193	183.2	7,399	1,198	338	258
sveltejs/svelte	UI compiler	328	64	49.2	5,698	1,414	618	248
mozilla/pdf.js	PDF rendering	178	37	115.4	948	1,345	535	247
openlayers/openlayers	Map rendering	358	84	108.3	2,163	549	148	121
josedjong/mathjs	Mathematics	657	51	59.4	5,200	126	32	39
<i>JavaScript (4)</i>		1,521	236	332.3	14,009	3,434	1,333	655
Total (20)		4,468	740	1,140.6	62,896	13,254	4,296	2,457

A.2 BUG STRUCTURE

Every bug consists of the fields in Table 7: a title and description of the incorrect behavior, a primary location in the snapshot at T_0 , the surrounding code, a severity and a suggested fix. In our main text we summarize repo, file, line_start/end as primary code location, and title, description as description.

Table 7: Fields of a reference bug record.

Field	Description
repo	GitHub repository.
file	Primary bug location file.
line_start/end	Primary bug location line numbers.
title	Short bug title.
description	What is wrong, its trigger and consequence.
severity	Impact, from low to critical.
suggested_fix	Short description of the fix.
code_snippet	Code around the bug location.

A.3 ESTIMATING THE TOTAL BUG POOL

Population and Observation Window We fit the 17 repositories with at least 25 reference bugs, i.e., all except jsonschema, jose, and msgpack-javascript. Over the reference window, January 2025




Figure 10: Calendar density of mined bug-fixing commits. Top: the share of all 4,265 commits in each month; the dashed line is uniform activity over 18 months. Bottom: monthly shares normalized separately within each repository (each row sums to 100%). Fixing activity varies across repositories and over time.

through June 2026, they hold 2,445 of the 2,457 reference bugs and 4,265 of the 4,296 bug-fixing commits of Table 6. We model when each reference bug is fixed, measuring time in bug-fixing commits rather than days: a repository’s clock advances by one with every bug-fixing commit, including commits that fix only bugs introduced after T_0 .

Bug-Fixing Commits as the Clock In calendar time, a falling fix rate can reflect either depletion of the bugs present at T_0 or fewer bug-fixing commits. Fixing activity varies substantially (Figure 10): pooled monthly counts range from 175 to 378 (a factor of 2.16), and individual repositories have quiet months and concentrated bursts. Measuring time in bug-fixing commits factors out this varying activity.

Conditional Fix-Position Model Let N_j be the number of bug-fixing commits in repository j ’s window, k_j its number of reference bugs, and x_{ij} the position of bug i ’s fix in that sequence. Commits are ordered along the first-parent chain and assigned positions $0.5, 1.5, \dots, N_j - 0.5$; bugs fixed by the same commit share its position. For a distribution of fix positions with CDF F_θ and density f_θ (three candidate families, defined below), we only observe bugs fixed within the window, so the likelihood conditions on $x_{ij} < N_j$:

$$p_\theta(x_{ij} \mid x_{ij} < N_j) = \frac{f_\theta(x_{ij})}{F_\theta(N_j)}, \quad \ell(\theta) = \sum_j \left[\sum_{i=1}^{k_j} \log f_\theta(x_{ij}) - k_j \log F_\theta(N_j) \right]. \quad (1)$$

The parameters θ are shared across repositories. Each repository’s unknown number of T_0 bugs cancels under this conditioning, so the fit uses only how front-loaded the observed fixes are. We use the continuous densities as an approximation on the half-integer commit positions.

The three families are parameterized as

$$F_{\text{exp}}(x) = 1 - \exp(-\beta x), \quad \beta > 0, \quad (2)$$

$$F_{\text{Wei}}(x) = 1 - \exp[-(x/\lambda)^a], \quad a, \lambda > 0, \quad (3)$$

$$F_{\text{LN}}(x) = \Phi\left(\frac{\log x - \mu}{\sigma}\right), \quad \sigma > 0, \quad (4)$$

where Φ is the standard normal CDF and $\log$ is the natural logarithm. The exponential assumes a constant fixing hazard per remaining bug per bug-fixing commit. The Weibull allows that hazard to decrease ($a < 1$) or increase ($a > 1$), and the lognormal allows a much longer tail. Here x and λ are measured in bug-fixing commits and β in inverse bug-fixing commits. Table 8 reports the fitted parameters.

Table 8: Fitted parameters of the three fix-position families. Full-window estimates use all 2,445 bugs; first-half estimates use 1,396.

Family	Parameter	Full window	First half
Exponential	β	0.00112	0.00190
Weibull	a	0.926	0.933
	λ	1,264	763
Lognormal	μ	15.6	15.5
	σ	3.77	3.82

First-Half Fit and Held-Out Diagnostic For repository j , let $c_j = \text{round}(N_j/2)$. We estimate parameters from positions $x_{ij} < c_j$ using the same likelihood with truncation at c_j . The remaining positions are held out; no late positions enter this fit. Figure 3 pools repositories on the normalized position $u = x/N_j$, in 20 equal-width bins, and compares them with the predicted density

$$q_\theta(u) = \frac{1}{K} \sum_j k_j \frac{N_j f_\theta(u N_j)}{F_\theta(N_j)}, \quad K = \sum_j k_j = 2,445. \quad (5)$$

Because the weights k_j are the observed full-window counts, this tests when bugs are fixed, not how many there are. The expected number of held-out bugs is $\sum_j k_j [1 - F_\theta(c_j)/F_\theta(N_j)]$. Against 1,049 observed late bugs, the estimates are 928 (exponential), 957 (Weibull), and 1,008 (lognormal), underpredictions of 11.6%, 8.8%, and 3.9%. No formal confidence band is shown: bugs fixed by the same commit can be dependent, and the family parameters are estimated from the data.

Extrapolation and Limits For a horizon of y years, we assume the observed fixing pace continues and set $H_j(y) = N_j(12y/18)$. The estimated number of bugs present at T_0 and fixed by that horizon is $\sum_j k_j F_\theta(H_j(y))/F_\theta(N_j)$; the eventually-fixed estimate is $\sum_j k_j / F_\theta(N_j)$ (the ∞ column of Table 9).

Table 9: Estimated number of T_0 bugs fixed within different horizons.

	5 years	10 years	∞
Exponential	5,195	7,197	13,030
Weibull	5,326	7,471	15,089
Lognormal	5,884	9,389	747,859

The large disagreement in eventual totals reflects assumptions about the unobserved tail, despite relatively similar fits inside the window. The conditional likelihood depends only on the curve’s shape inside the window: a curve that ends with the window fits equally well and implies no further fixes, while a longer tail implies more. The observed 2,445 bugs are therefore a lower bound, but the data give no finite upper bound on the number of bugs present at T_0 . Never-fixed bugs are invisible, and incomplete mining or a declining probability of mapping a later fix back to T_0 can distort the observed density. The holdout tests the timing of detected fixes and cannot measure this missing population.

A.4 BUG MATCHING AND DEDUPLICATION

Bug matching (§2.3) has three uses: matching an agent’s findings to the reference set, merging duplicate reference bugs in Step 6 of the benchmark construction, and merging repeated runs into one set of distinct findings.

Similarity Filter A pair goes to the judge if any of the six signals of Table 10 reaches its threshold. We chose the thresholds to send as few pairs as possible to the judge while keeping all 217 duplicates it confirmed among 3,770 finding–reference pairs from ten repositories. Since one signal suffices, this is a weighted set-cover problem. On held-out pairs between agent findings and those of an independent bug-finding tool on all 20 repositories, the thresholds keep 472 of 474 duplicates.

Table 10: The six pairwise similarity signals that pre-filter finding pairs before the LLM duplicate judge.

Signal	Inputs	Tokens / model	Score	Threshold
line overlap	file, line_start, line_end	line ranges in the same file	Jaccard	0.02
full-text embedding	title, description, first 1,000 characters of code_snippet	all-MiniLM-L6-v2	cosine	0.65
description embedding	title, description	all-MiniLM-L6-v2	cosine	0.57
snippet tokens	code_snippet	words ^a of ≥ 2 characters	IDF-weighted Jaccard ^c	0.60
identifiers	description, code_snippet	words ^a of ≥ 3 characters	IDF-weighted Jaccard ^c	0.10
API calls	code_snippet	called names ^b	IDF-weighted Jaccard ^c	0.22

^a The distinct matches of the regex `[a-z_]\w*` (a letter or underscore followed by letters, digits or underscores) in the lowercased text, minus a stopword list of Python keywords and common Python and TypeScript builtins.

^b The distinct lowercased bare or dotted names directly followed by `'(`, with a leading `self.`, `cls.` or `this.` removed and common builtins such as `len` or `console.log` dropped; bare names need ≥ 5 characters.

^c The summed weight of the tokens two findings share, divided by that of all their tokens. A token’s weight is $\log \frac{n+1}{df+1} + 1$, from an IDF (inverse document frequency) table built once per run over the n findings on both sides of the comparison, df of which contain the token.

LLM Judge Gemini 3.5 Flash at medium thinking effort judges one pair per call and sees only the two reports, never the signal values (Appendix F.4.1). On 452 pairs from hono, Claude Opus 5 with access to the full repository agrees with the judge on 98.9% of pairs ($\kappa = 0.932$); on the five pairs where they disagree, a human sided with the judge.

Three Uses To score a run, every finding is paired with every reference bug, and matching is many-to-many: recall counts the reference bugs matched by at least one finding, precision the findings that match at least one reference bug. Step 6 pairs reference bugs that share a file and uses a stricter prompt that requires a shared root cause (Appendix F.2.5). Confirmed pairs are merged as connected components, keeping the earliest fix, which removes 44 bugs. Repeated runs are merged one at a time: the findings of each new run are paired with the merged set and with each other, with a finding’s suggested fix appended to its description, and confirmed pairs are again merged as connected components. Merging the ten GPT-5.6 Luna runs reduces 27,737 findings to 7,472 and judges 180,287 pairs for \$1,007.

Validation The corpus of §2.3 holds a subset of findings from several earlier discovery runs on opshin, prefect, and weasyprint. Its pairs join two findings rather than a finding and a reference bug, but go through the same filter and prompt as scoring. The identifier threshold was partly tuned on these repositories. Because matches are not transitive, we score individual pairs rather than clusters. The first run judges all 17,177 pairs with the filter off: it confirms none of the 16,708 pairs the filter removes and reaches 98.5% precision and 98.5% recall. Each later run judges only the filtered pairs and agrees with the first on at least 99.8% of them ($\kappa \geq 0.991$). All errors fall on three pairs where it is debatable whether one fix resolves both. The five runs cost \$94.

B PASS PLANNING

A deterministic planner partitions each repository’s audited files into the passes of §3. It uses no LLM, only the static call graph, file sizes and the directory tree, and its parameters are the same for all repositories, so a snapshot always yields the same plan.

Audited Files The call graph covers every non-test source file of the snapshot. The planner skips 197 generated database migration files in prefect and audits the remaining 4,468 files.

File Score Each file f receives the score

$$s(f) = 3c(f) + 0.05l(f) + 0.5n(f),$$

where $c(f)$ counts the distinct functions in other files that call into f or that f calls, $l(f)$ is the file’s line count and $n(f)$ the number of functions it defines. Cross-file connectivity dominates: one call partner in another file weighs as much as 60 lines.

Individual Passes Files are ranked by score, with ties broken by path. A file gets a pass of its own if its score is at least 15% of the repository’s top score, but at most 15% of a repository’s audited files do so, and at least one always does. The score threshold decides in 11 repositories and the count limit in 9.

Directory Batches The remaining files are grouped by top-level directory. We estimate a group’s size as the characters of its line-numbered source divided by 3.5. A group above 60k tokens is split by subdirectory, below the deepest directory its files share, and each part is split again while it stays over budget. Files in a single directory are sorted by line count and cut into two halves instead. A batch left with a single file becomes an individual pass. Batches hold a median of 7 files, from 2 to 246. In total, 331 files get an individual pass by score, 28 as single-file batches, and 381 directory batches hold the other 4,109, for 740 passes.

Call-Graph Context An individual pass includes snippets of at most 40 callers and 40 callees in other files, and a batch at most 25 of each. Calls between files of the same batch are left out, since both files are already in the prompt. When the limit binds, functions referenced by more of the pass’s files come first, then longer snippets.

C ADDITIONAL RESULTS

C.1 RESULTS ON THE FIVE-REPOSITORY SUBSET

To limit cost, Claude Opus 5 audits only five repositories, covering both Python and JavaScript/TypeScript: hono, networkx, pdf.js, pypdf and weasyprint, with 755 reference bugs. Table 11 restricts every configuration to these five repositories, so that Claude Opus 5 can be compared with the others like for like. Claude Opus 5 reaches 21.2% recall at 10.0% precision, level with GPT-5.6 Sol (medium) and more than twice the recall of Claude Sonnet 5. The other configurations rank roughly as they do on all repositories.

C.2 RECALL AND PRECISION PER REPOSITORY

Tables 12 and 13 break the recall and precision of Table 3 down by repository, with the repositories grouped by language as in Table 6.

Repository Variation Comparing recall across repositories (see Table 12), we observe large differences that bug count does not explain (Spearman $\rho = -0.27$ between a repository’s reference bugs and its mean recall). Averaged over agents, recall per repository ranges from about 3% on sqlglot to over 40% on liquidjs and jsonschema, and the configurations rank the repositories consistently (Kendall’s $W = 0.75$). Notably, recall is substantially higher for TypeScript (25.4%) than for Python (10.8%) or JavaScript (12.0%). Precision also varies widely, from 0.6% on jose to 22.9% on pypdf (see Table 13), with an even more consistent ranking ($W = 0.92$).

Table 11: Recall, precision and F1 against the reference set on the five repositories Claude Opus 5 audited (755 reference bugs), for every configuration of Table 3, in its order. Cells for Muse Spark 1.3 and GPT-5.6 Luna (medium) are means over 5 and 10 runs, respectively, and cost covers the five repositories.

Model	Effort	Recall (%)	Precision (%)	F1 (%)	Findings	Cost
DeepSeek V4.1 Flash	high	17.5	11.7	14.0	1,172	\$15
GLM 5.3 Flash	high	18.7	10.4	13.3	1,428	\$25
GPT-5.4	medium	12.5	10.3	11.3	942	\$138
GPT-5.6 Terra	medium	10.6	10.9	10.7	761	\$46
Gemini 3.5 Flash	medium	10.7	9.8	10.2	867	\$104
Muse Spark 1.3	high	20.6	8.0	11.6	1,921	\$35
Claude Sonnet 5	medium	9.5	9.7	9.6	762	\$96
Claude Opus 5	medium	21.2	10.0	13.6	1,707	\$353
GPT-5.6 Sol	high	24.0	9.6	13.7	1,976	\$249
	medium	20.9	10.0	13.6	1,694	\$130
	low	14.3	11.1	12.5	970	\$61
GPT-5.6 Luna	xhigh	20.1	10.5	13.8	1,575	\$27
	high	15.5	10.1	12.2	1,211	\$11
	medium	10.0	11.0	10.5	691	\$3
	low	7.7	11.7	9.3	488	\$2

C.3 VALIDITY OF FINDINGS

Table 14 gives the panel’s verdicts behind each point of Figure 5. The findings are sampled in proportion to each run’s findings per repository and judged under opaque identifiers; validating them cost \$772 (\$0.86 per finding). Table 15 compares one author’s blind verdicts with the panel’s on the 180 findings of the validity sample graded by both (§4.2). The agreement and κ reported there leave out the findings the author was unsure about and those the panel left inconclusive (Abstained in Tables 14 and 15) because both of its tiers split.

C.4 CONTAMINATION

We test whether agents preferentially match bugs fixed earlier or later in the reference window. Within each repository, we order the reference bugs by fix time and normalize their ranks to $[0, 1]$. Under the null hypothesis, the m_j matched bugs of repository j are a uniformly random subset of its reference bugs. With $F_j(r)$ the empirical rank CDF of repository j and $M = \sum_j m_j$, the expected CDF of matched ranks is $F_0(r) = M^{-1} \sum_j m_j F_j(r)$, and we measure the deviation with the Kolmogorov–Smirnov statistic (Hodges, 1958)

$$D = \sup_r \left| \hat{F}_{\text{matched}}(r) - F_0(r) \right|, \quad (6)$$

where $\hat{F}_{\text{matched}}$ is the empirical CDF of matched ranks. We estimate p from 100,000 permutations of the match labels within repositories, $p = (b + 1)/(100,000 + 1)$, where b counts the permutations with a D at least as large as observed (Phipson & Smyth, 2010), and apply Holm’s correction across all runs (Holm, 1979).

Only DeepSeek V4.1 Flash has an unadjusted $p < 0.05$ ($p = 0.008$, $D = 0.076$; Table 16), from an excess of matches among earlier-fixed bugs. After Holm correction its p is 0.204 and all others are 1, so we find no evidence that agents favor earlier- or later-fixed bugs.

The fix-rank test can only reveal contamination for a model whose training data contains some but not all reference fixes, i.e., whose knowledge cut-off lies inside the reference window. Table 17 lists the cut-offs the vendors publish. All seven published cut-offs lie inside the window, ranging from January 2025 for Gemini 3.5 Flash, the window’s first month, to May 2026 for Claude Opus 5. GLM 5.3 Flash, Muse Spark 1.3 and DeepSeek V4.1 Flash have no published cut-off and were released after T_1 , so their training data may cover the entire window.

Table 12: Recall (%) against the reference set per repository, for every configuration of Table 3 and Claude Opus 5. The shaded italic rows pool the bugs of one language. For configurations run several times, each cell is the mean over the runs. The shaded Mean column averages the configurations of Table 3, counting each repeated configuration once and excluding Claude Opus 5. Bold marks each row’s best configuration.

Repository	Bugs	DeepSeek V4.1 Flash (high)	GLM 5.3 Flash (high)	GPT-5.4 (medium)	GPT-5.6 Terra (medium)	Gemini 3.5 Flash (medium)	Muse Spark 1.3 (high, 5 runs)	Claude Sonnet 5 (medium)	GPT-5.6 Sol (high)	GPT-5.6 Sol (medium)	GPT-5.6 Sol (low)	GPT-5.6 Luna (xhigh)	GPT-5.6 Luna (high)	GPT-5.6 Luna (medium, 10 runs)	GPT-5.6 Luna (low)	Claude Opus 5 (medium)	<i>Mean</i>
sqlglot	512	3.9	4.5	2.0	1.8	1.6	3.2	0.8	8.2	3.3	2.7	5.5	3.1	1.1	0.8	-	3.0
prefect	429	12.6	13.5	10.5	6.8	11.4	15.2	8.2	17.9	13.5	8.9	16.3	12.4	6.4	5.1	-	11.3
pypdf	165	17.0	22.4	9.1	8.5	11.5	27.8	12.7	24.2	23.6	16.4	21.2	14.5	11.4	10.3	30.9	16.5
weasyprint	115	10.4	10.4	7.0	6.1	6.1	9.7	4.3	16.5	13.9	6.1	15.7	7.0	4.3	1.7	9.6	8.5
fonttools	113	28.3	27.4	19.5	20.4	17.7	29.0	15.9	31.9	30.1	23.9	28.3	22.1	14.6	8.8	-	22.7
networkx	84	28.6	32.1	19.0	15.5	20.2	27.6	13.1	35.7	32.1	26.2	31.0	23.8	13.1	9.5	32.1	23.4
opshin	51	27.5	27.5	15.7	13.7	9.8	24.3	11.8	35.3	21.6	13.7	33.3	23.5	10.2	7.8	-	19.7
pygments	41	19.5	12.2	7.3	7.3	7.3	14.1	12.2	17.1	17.1	12.2	14.6	12.2	8.0	4.9	-	11.9
pint	28	10.7	7.1	7.1	7.1	7.1	10.0	7.1	10.7	10.7	10.7	3.6	3.6	0.4	0.0	-	6.9
jjsonschema	6	83.3	66.7	66.7	50.0	50.0	33.3	50.0	66.7	66.7	66.7	50.0	16.7	33.3	33.3	-	52.4
<i>Python</i>	1,544	13.0	13.8	8.6	7.1	8.6	14.1	7.1	17.9	14.0	10.0	15.3	10.7	6.1	4.6	-	10.8
hono	144	34.0	29.9	26.4	22.9	19.4	39.0	18.1	48.6	39.6	25.7	38.2	37.5	21.4	15.3	36.8	29.7
echarts	46	17.4	28.3	6.5	13.0	13.0	10.0	8.7	28.3	21.7	15.2	19.6	17.4	7.2	2.2	-	14.9
liquidjs	32	53.1	37.5	37.5	40.6	25.0	46.2	28.1	53.1	50.0	37.5	65.6	46.9	33.4	18.8	-	41.0
remeda	30	6.7	3.3	10.0	3.3	3.3	10.7	3.3	10.0	10.0	10.0	10.0	3.3	3.3	3.3	-	6.5
jose	3	0.0	0.0	0.0	33.3	0.0	13.3	33.3	33.3	0.0	0.0	33.3	0.0	3.3	0.0	-	10.7
msgpack-javascript	3	33.3	33.3	0.0	33.3	33.3	33.3	33.3	33.3	33.3	0.0	0.0	33.3	3.3	0.0	-	21.7
<i>TypeScript</i>	258	29.8	27.1	21.7	21.3	17.1	31.1	16.3	40.7	33.7	22.9	34.5	30.6	17.8	11.6	-	25.4
svelte	248	16.5	19.8	12.5	10.5	12.5	16.6	6.9	23.4	22.6	11.7	17.3	14.1	8.4	3.6	-	14.0
pdf.js	247	7.7	8.9	6.9	5.3	4.0	7.7	3.6	8.9	7.7	6.1	7.3	4.5	4.0	3.6	7.3	6.2
openlayers	121	19.8	20.7	20.7	12.4	14.0	18.7	9.9	32.2	19.8	14.0	22.3	16.5	9.9	5.8	-	16.9
mathjs	39	30.8	23.1	20.5	10.3	12.8	26.2	10.3	30.8	33.3	12.8	28.2	25.6	10.3	7.7	-	20.2
<i>JavaScript</i>	655	14.7	16.0	12.4	8.9	9.6	14.2	6.4	20.0	17.1	10.1	15.1	11.6	7.2	4.3	-	12.0
<i>All</i>	2,457	15.2	15.8	11.0	9.1	9.8	15.9	7.9	20.8	16.9	11.4	17.3	13.0	7.6	5.3	-	12.6

Table 13: Precision (%) against the reference set per repository, for every configuration of Table 3 and Claude Opus 5. The shaded italic rows pool the findings of one language. For configurations run several times, each cell is the mean over the runs. The shaded Mean column averages the configurations of Table 3, counting each repeated configuration once and excluding Claude Opus 5. Bold marks each row’s best configuration.

Repository	DeepSeek V4.1 Flash (high)	GLM 5.3 Flash (high)	GPT-5.4 (medium)	GPT-5.6 Terra (medium)	Gemini 3.5 Flash (medium)	Muse Spark 1.3 (high, 5 runs)	Claude Sonnet 5 (medium)	GPT-5.6 Sol (high)	GPT-5.6 Sol (medium)	GPT-5.6 Sol (low)	GPT-5.6 Luna (xhigh)	GPT-5.6 Luna (high)	GPT-5.6 Luna (medium, 10 runs)	GPT-5.6 Luna (low)	Claude Opus 5 (medium)	Mean
sqlglot	15.3	12.9	8.3	11.7	9.2	7.2	4.7	13.1	7.9	14.6	11.9	13.4	8.6	8.9	–	10.6
prefect	10.2	8.5	10.3	8.2	10.1	6.4	7.7	9.4	7.8	9.1	9.2	8.9	8.2	8.7	–	8.8
pypdf	25.2	23.5	18.8	20.3	22.1	21.4	24.4	18.1	22.2	26.2	19.2	18.6	25.7	34.7	24.8	22.9
weasyprint	6.3	5.8	6.7	7.4	6.9	4.7	4.6	5.8	6.4	6.0	8.7	6.6	5.8	3.6	4.6	6.1
fonttools	7.1	5.6	6.1	7.6	5.6	3.9	4.9	5.0	6.0	7.8	5.4	5.6	6.2	4.5	–	5.8
networkx	6.9	6.0	4.9	4.6	6.4	3.8	5.4	4.8	4.8	6.5	5.3	5.0	4.7	4.6	5.3	5.3
opshin	15.2	13.4	11.8	17.1	8.9	10.5	8.7	15.5	12.0	10.9	19.4	16.9	13.0	11.8	–	13.2
pygments	1.5	0.9	1.2	1.1	1.1	0.9	2.2	0.8	1.0	1.5	1.0	1.1	1.4	1.4	–	1.2
pint	2.0	1.2	2.2	2.6	2.0	1.3	2.3	1.4	2.1	3.5	0.6	0.9	0.2	0.0	–	1.6
jsonschema	20.0	14.3	12.5	15.8	17.6	4.9	15.8	7.5	9.4	19.0	8.3	4.8	13.6	18.2	–	13.0
<i>Python</i>	7.8	6.9	6.8	7.0	7.3	5.1	6.5	6.5	6.2	8.0	7.0	6.7	6.7	6.9	–	6.8
hono	21.1	18.3	21.0	23.8	18.1	16.9	17.7	21.1	21.5	20.2	20.3	22.3	22.9	23.4	17.0	20.6
echarts	1.8	2.2	0.9	1.9	1.3	0.5	1.1	1.5	1.6	1.7	1.7	1.6	1.1	0.5	–	1.4
liquidjs	13.5	12.8	11.4	19.6	10.9	8.3	9.3	11.8	13.3	15.0	15.9	13.9	14.7	13.3	–	13.1
remeda	3.1	1.4	3.3	2.0	3.0	3.0	3.0	2.0	2.3	3.3	1.9	1.3	2.5	3.4	–	2.5
jose	0.0	0.0	0.0	2.7	0.0	0.3	2.0	2.0	0.0	0.0	1.5	0.0	0.2	0.0	–	0.6
msgpack-javascript	4.2	3.4	0.0	4.8	8.7	2.9	6.2	2.5	3.2	0.0	0.0	3.7	0.7	0.0	–	2.9
<i>TypeScript</i>	8.7	6.7	6.4	9.4	6.2	5.0	6.0	7.2	7.8	7.6	8.1	8.2	8.0	7.1	–	7.3
svelte	13.9	14.6	13.2	15.4	12.2	8.3	8.9	11.7	15.0	15.0	12.0	12.8	15.8	10.7	–	12.8
pdf.js	7.7	7.4	8.0	8.1	3.9	3.7	4.7	5.9	5.3	6.6	5.7	4.2	5.9	6.9	5.2	6.0
openlayers	7.4	5.3	6.5	5.5	4.1	3.0	3.2	6.2	4.4	4.7	5.4	5.0	5.3	4.3	–	5.0
mathjs	4.1	3.7	3.0	2.1	1.9	2.4	2.4	3.3	3.5	2.4	3.6	3.6	2.4	2.1	–	2.9
<i>JavaScript</i>	8.2	7.5	7.4	7.2	5.3	4.1	4.5	6.7	6.8	6.5	6.6	6.2	6.6	5.2	–	6.3
<i>All</i>	8.1	7.0	6.9	7.6	6.4	4.8	5.8	6.7	6.7	7.5	7.1	6.9	7.0	6.5	–	6.8

Table 14: The panel’s verdicts on the 100 sampled findings of one run per configuration. Validity is the confirmed share of the decided verdicts, with its 95% Clopper–Pearson interval. For GPT-5.6 Luna (medium) and Muse Spark 1.3, the run is the first of their repeats. Bold marks the most confirmed and fewest rejected findings and the highest validity.

Model	Effort	Confirmed	Rejected	Abstained	Validity (%)	95% CI
GPT-5.4	medium	94	5	1	95	[89, 98]
GPT-5.6 Sol	medium	92	5	3	95	[88, 98]
DeepSeek V4.1 Flash	high	93	6	1	94	[87, 98]
GPT-5.6 Terra	medium	89	7	4	93	[86, 97]
GPT-5.6 Luna	medium	85	10	5	89	[81, 95]
GLM 5.3 Flash	high	84	10	6	89	[81, 95]
Gemini 3.5 Flash	medium	67	25	8	73	[63, 82]
Muse Spark 1.3	high	65	27	8	71	[60, 80]
Claude Sonnet 5	medium	62	35	3	64	[54, 73]

Table 15: The author’s blind verdict (rows) against the panel’s (columns) on the 180 findings of the validity sample graded by both.

Author	Panel			Total
	Confirmed	Rejected	Abstained	
Confirmed	103	0	0	103
Rejected	9	19	6	34
Unsure	35	5	3	43
Total	147	24	9	180

Table 16: Fix-rank permutation tests for every run, grouped as in Table 3; Run numbers the repeated runs of GPT-5.6 Luna (medium) and Muse Spark 1.3. Column p is unadjusted; p_{Holm} adjusts for all 27 tests. Bold denotes $p < 0.05$ in each column; no result remains significant after Holm correction.

Model	Effort	Run	Matched	D	p	p_{Holm}
DeepSeek V4.1 Flash	high		373	0.076	0.008	0.204
GLM 5.3 Flash	high		388	0.042	0.329	1.000
GPT-5.4	medium		270	0.039	0.692	1.000
GPT-5.6 Terra	medium		223	0.044	0.677	1.000
Gemini 3.5 Flash	medium		240	0.067	0.157	1.000
Muse Spark 1.3	high	1	387	0.044	0.282	1.000
		2	385	0.032	0.668	1.000
		3	373	0.029	0.784	1.000
		4	391	0.037	0.466	1.000
		5	417	0.046	0.181	1.000
Claude Sonnet 5	medium		194	0.059	0.409	1.000
GPT-5.6 Sol	high		512	0.034	0.359	1.000
	medium		415	0.036	0.476	1.000
	low		279	0.052	0.309	1.000
GPT-5.6 Luna	xhigh		424	0.038	0.385	1.000
	high		320	0.030	0.856	1.000
	medium	1	181	0.057	0.489	1.000
		2	200	0.055	0.458	1.000
		3	209	0.047	0.631	1.000
		4	189	0.050	0.637	1.000
	low	5	193	0.047	0.697	1.000
		6	179	0.059	0.444	1.000
		7	183	0.050	0.649	1.000
		8	168	0.075	0.221	1.000
		9	195	0.033	0.956	1.000
		10	181	0.049	0.686	1.000
	low		129	0.064	0.584	1.000

Table 17: Knowledge cut-offs of the evaluated models as published by their vendors. For the three models without a published cut-off, we give their release date instead.

Model	Knowledge cut-off	Source
Gemini 3.5 Flash	January 2025	Google (2026)
GPT-5.4	31 August 2025	OpenAI (2026a)
Claude Sonnet 5	January 2026	Anthropic (2026b)
GPT-5.6 Luna, Terra, Sol	16 February 2026	OpenAI (2026b;c;d)
Claude Opus 5	May 2026	Anthropic (2026a)
GLM 5.3 Flash	not published (released 26 August 2026)	Z.ai (2026)
Muse Spark 1.3	not published (released 2 September 2026)	Meta (2026)
DeepSeek V4.1 Flash	not published (released 10 September 2026)	DeepSeek (2026)

D BUG-TYPE TAXONOMY

D.1 CONSTRUCTION

We induce the bug types of §4.2 from a corpus of 5,416 bugs: the 2,444 human-fixed bugs of the reference set (13 of the 2,457 merge with another through a shared agent finding) and 3,205 findings of an earlier GPT-5.4 audit of the same snapshots that every LLM validator confirmed, 233 of which match a human-fixed bug and are counted once. Drawing on both sources keeps the categories from fitting only one of the two distributions we compare. Claude Opus 5 proposes 38 categories, within a requested range of 25–40, that classify bugs by root cause rather than symptom, from the titles and descriptions of 2,546 bugs sampled across repositories and sources (Appendix F.7.1). Claude Sonnet 5 then assigns every corpus bug one category and one trigger level, in batches of 50 bugs identified only by opaque keys (Appendix F.7.3). Finally, Claude Opus 5 merges the categories holding fewer than 50 bugs into a neighbor unless they are conceptually irreducible (Appendix F.7.2), leaving 33. The findings of every configuration are assigned with the same prompt against these frozen categories.

D.2 CATEGORIES

Table 18 lists the 33 categories, grouped into six families that Claude Opus 5 drew from the names and definitions alone. In the prompts, each definition also names the neighboring category a borderline bug belongs to instead; we omit these clauses here.

Table 18: The 33 bug types and their definitions, grouped by family (continued in Table 19).

Category	Definition
<i>Missing case coverage</i>	
Missing branch for a supported input variant	Inline conditional logic handles some supported kinds, syntaxes or shapes of input but omits another equally supported variant, so it is processed by the wrong path.
Missing rejection of invalid input	Malformed, out-of-range, duplicated or otherwise unsupported input is silently accepted and processed instead of being validated and refused at the boundary.
Unhandled degenerate value	Code fails to special case a boundary value that is legal input, such as an empty collection, zero, a single element, or an absent or null field, and then indexes, divides or dereferences it.
Unimplemented advertised feature	A documented option, method, mode or format is exposed but its behaviour is absent or a stub, so the request is silently ignored or handled by an unrelated path.
Missing dispatch or lookup table entry	A registry, mapping, keyword list, transform table or alias set lacks an entry for a supported case, so lookup falls through to a generic or absent handler.
Truthiness test instead of presence test	A falsy but meaningful value such as zero, an empty string, false or an empty collection is treated as absent because the code tests truthiness rather than explicit nullness or membership.
Missing initialisation or default	A variable, field or option is read on a path where it was never assigned, or a required default is not supplied when constructing an object or record.
<i>Incorrect expressions and computation</i>	
Wrong arithmetic or comparison expression	A formula, offset, sign, bound or relational operator is written incorrectly so the computed result or decision is wrong, including off-by-one indexes and inverted conditions.
Incorrect regular expression pattern	A pattern is too narrow, too broad, missing an escape, or ambiguous enough to backtrack pathologically, so it fails to match or over-matches legal text.
Numeric precision or width mistake	Values are truncated, rounded, packed into too few bits, signed instead of unsigned, or accumulated in a lower precision type than required.
Wrong ordering of matching rules	Alternatives, cases or rules are tried in an order that lets a general rule shadow a more specific one, or lets a later specialised rule become unreachable.
<i>Wrong reference or declared contract</i>	
Wrong dispatch or lookup table entry	An entry exists in a table, constant set or definition list but carries a misspelled key, wrong target, wrong unit or otherwise incorrect value.
Wrong data source read	Logic reads from a plausible but incorrect field, collection, snapshot or alternative source of the same information, such as raw instead of normalised values or one member instead of the aggregate.
Incorrect public type declaration	A type annotation, generic constraint, overload or interface describes the runtime contract incorrectly, rejecting valid calls or widening inferred results.
Missing parameter propagation	A caller fails to forward available context such as a dialect, projection, encoding, signal, index or option to a callee that needs it, so the callee applies defaults.
Wrong argument at a call site	A call passes swapped, mismatched or plainly incorrect arguments, including a wrong literal, a wrong receiver, or arguments in the wrong positions.
Incorrect name or scope resolution	Identifiers, aliases, qualifiers or bindings are resolved against the wrong scope, namespace or declaration, including leaked or shadowed compiler bindings and wrongly qualified references.

Table 19: The 33 bug types and their definitions, grouped by family (continued from Table 18).

Category	Definition
<i>State, shared data and lifecycle</i>	
Missing state reset or restoration	Flags, counters, cursors, module globals or cached bookkeeping are left over from a previous operation or are not restored when an operation exits, including exceptional exits without a finally.
Colliding key construction	A keyed store is built unsafely, either because the identifier used for caching, indexing, deduplication or grouping lacks a delimiter or a distinguishing component so distinct items collide, or because a plain object or inherited property lookup is used as the container so keys such as <code>__proto__</code> or constructor corrupt or leak results.
Mutation of shared input data	Code mutates data that others alias, either by modifying an argument, option object, cached entry or otherwise shared structure instead of copying it, or by modifying or re-consuming a live view or single pass iterator while it is being traversed, so unrelated callers see changed data or items are skipped, duplicated or lost.
Missing cache invalidation	A change to underlying inputs is not propagated to dependents, either because a memoised or cached value is never invalidated or because a dependency, subscription or change notification needed by an observer, effect or rendering pipeline is never registered or emitted, so later reads observe stale data.
Missing resource release	Listeners, subscriptions, timers, buffers, sockets, processes or graphics objects are created but never unregistered, cancelled, closed or deleted, so they accumulate or fire after teardown.
<i>Control flow, concurrency and failure</i>	
Wrong sequencing of operations	Steps run in the wrong order relative to each other, for example reading state before it is normalised, emitting output before required setup, or mutating a structure before a dependent computation.
Swallowed or mislabelled error	An exception is caught and discarded, replaced by a misleading type or message, raised without being thrown, or signalled by an assertion rather than a proper error, so callers cannot react correctly.
Unguarded failure-prone call	A call that can fail transiently or on malformed data is made with no surrounding handling, retry or fallback, so the failure propagates and aborts otherwise recoverable work.
Missing synchronisation or atomicity	Concurrent tasks, threads, processes or requests interleave without a lock, lease, deterministic lock order or single atomic statement, causing races, duplicate effects or deadlocks.
Missing cycle or depth guard	A traversal or loop lacks a working termination guard, whether a recursive or reference following walk without a visited set or depth limit, or an iterative loop whose index never advances or whose exit condition can never be satisfied.
Incorrect asynchronous control flow	Asynchronous work is misdriven, for example a promise or coroutine is not awaited, a blocking call runs on an event loop, a callback resolves early or out of order, or a pending promise is never settled.
<i>Non-functional and environment</i>	
Missing output escaping	Text is emitted into a sink without the sanitising that sink requires, either structural or untrusted content interpolated into HTML, SQL, XML, CSS, URLs, regexes, headers or generated code without escaping, or credentials, tokens and other confidential values placed into messages, logs, URLs or persisted state without redaction.
Missing consumption limit	Attacker-influenced or unbounded sizes are allocated, decompressed, queued or buffered without a cap, permitting exhaustion of memory, disk or queue capacity.
Redundant or superlinear work	Correct results are produced but with avoidable repeated scanning, rebuilding, re-fetching or quadratic accumulation that degrades latency.
Missing or weak credential check	Authentication or authorisation is absent, incomplete, bypassable, or performed with a comparison whose timing reveals the secret, or an integrity check whose result is ignored.
Build or packaging misconfiguration	Project metadata, packaging rules, dependency declarations, tooling flags or generated asset configuration are wrong, so builds, installs or environments break independently of program logic.

D.3 BUG-TYPE DISTRIBUTION

Table 20 extends Table 4 to all categories. For each of the ten categories shown there, the human share lies outside the range spanned by the individual runs, so no single configuration drives the gap.

Table 20: Bug-type distribution of the human reference set and of coding agent findings, for all categories, sorted by gap. Agent counts ($\bar{n}$) and shares are means over one run of each of the 14 configurations; Range gives the lowest and highest share of a single run. Gap is the agent share minus the human share in percentage points; Ratio is the agent share over the human share.

Category	Human		Agents			Gap (pp)	Ratio
	n	%	$\bar{n}$	%	Range		
Wrong arithmetic or comparison expression	243	9.9	916	18.5	16.9–20.8	+8.6	1.86
Unhandled degenerate value	222	9.1	674	13.9	10.7–19.6	+4.8	1.53
Incorrect regular expression pattern	47	1.9	245	4.7	3.1–5.7	+2.8	2.47
Missing state reset or restoration	57	2.3	242	4.9	3.5–5.9	+2.6	2.11
Wrong data source read	57	2.3	224	4.5	3.3–5.8	+2.1	1.91
Colliding key construction	24	1.0	139	2.8	1.7–3.6	+1.9	2.90
Truthiness test instead of presence test	26	1.1	126	2.6	1.7–3.8	+1.6	2.49
Mutation of shared input data	27	1.1	128	2.6	2.0–3.6	+1.5	2.39
Wrong ordering of matching rules	4	0.2	66	1.3	0.5–1.9	+1.1	7.92
Swallowed or mislabelled error	41	1.7	129	2.6	1.4–4.9	+0.9	1.55
Missing rejection of invalid input	225	9.2	492	10.1	6.4–13.7	+0.9	1.09
Missing resource release	26	1.1	51	1.1	0.7–1.8	0.0	1.01
Missing cycle or depth guard	33	1.4	63	1.3	0.7–1.7	−0.1	0.95
Incorrect asynchronous control flow	17	0.7	28	0.6	0.4–0.7	−0.1	0.85
Numeric precision or width mistake	34	1.4	62	1.2	0.7–1.6	−0.2	0.89
Wrong argument at a call site	34	1.4	50	1.1	0.7–1.4	−0.3	0.77
Incorrect name or scope resolution	17	0.7	17	0.4	0.1–0.9	−0.3	0.53
Missing or weak credential check	15	0.6	13	0.3	0.2–0.4	−0.3	0.46
Missing cache invalidation	32	1.3	48	1.0	0.6–1.2	−0.4	0.73
Build or packaging misconfiguration	13	0.5	8	0.2	0.0–0.4	−0.4	0.29
Redundant or superlinear work	19	0.8	20	0.4	0.0–1.1	−0.4	0.50
Missing synchronisation or atomicity	35	1.4	49	1.0	0.4–1.6	−0.4	0.71
Wrong sequencing of operations	88	3.6	157	3.0	1.9–4.0	−0.6	0.84
Unguarded failure-prone call	47	1.9	66	1.3	0.7–2.5	−0.6	0.70
Missing output escaping	39	1.6	49	1.0	0.3–1.5	−0.6	0.63
Missing initialisation or default	51	2.1	70	1.4	1.1–2.5	−0.6	0.69
Missing consumption limit	30	1.2	24	0.5	0.2–0.6	−0.8	0.37
Missing parameter propagation	48	2.0	35	0.7	0.5–1.1	−1.2	0.37
Wrong dispatch or lookup table entry	102	4.2	130	2.6	2.0–3.7	−1.6	0.63
Unimplemented advertised feature	114	4.7	133	2.6	1.6–3.9	−2.0	0.56
Incorrect public type declaration	111	4.5	57	1.1	0.6–1.5	−3.5	0.24
Missing dispatch or lookup table entry	124	5.1	38	0.7	0.3–1.4	−4.3	0.14
Missing branch for a supported input variant	439	18.0	400	7.7	4.4–9.6	−10.3	0.43
No listed category fits	3	0.1	7	0.1	0.0–0.5	0.0	1.14
All bugs	2,444	100.0	4,954	100.0			

D.4 TRIGGER

Alongside its category, every bug is assigned a trigger level, answering what is needed to observe the failure (Table 21). Agent findings concentrate further on bugs that need only a specific input. Human-fixed bugs more often need a specific environment, a person inspecting the output, or timing, concurrency or load, and on each of these levels every agent run falls below the human share.

Table 21: Trigger levels of the human reference set and of coding agent findings. Agent shares are means over one run of each of the 14 configurations; Range gives the lowest and highest share of a single run.

Level	Needed to observe the failure	Human		Agents	
		n	%	%	Range
Ordinary use	Any execution of the affected path with common inputs fails or gives a wrong result.	105	4.3	6.1	4.6–7.8
A specific input	A particular value, shape or edge case is needed, such as an empty or absent value, an unusual variant, malformed data or a boundary.	1,815	74.3	83.9	79.2–86.3
A specific environment	A particular platform, runtime or dependency version, locale, toolchain or type checker is needed.	265	10.8	4.7	3.7–6.3
Interaction or inspection	The failure shows only in rendered output, a user interface or a document, or through a user’s sequence of actions, and a person has to look at it.	92	3.8	0.7	0.3–1.0
Timing, concurrency or load	Concurrent execution, a particular ordering of asynchronous events, a long-running process or large inputs are needed.	167	6.8	4.6	3.2–6.3

E A MODEL OF REPEATED BUG DISCOVERY

Repeated runs of one configuration report partly different findings (§4.3). We model a configuration’s findings as the features of a stable-beta process, fit it to the repeated runs of Muse Spark 1.3 and GPT-5.6 Luna, and derive what it implies for the union of many runs.

E.1 MODEL

Setting A defect is a *bug* if a maintainer would fix it when presented with the defect and an available fix. Let $\mathcal{U}$ denote these bugs in a fixed repository state and $\mathcal{H} \subseteq \mathcal{U}$ the historical reference set. An agent’s reachable findings $\mathcal{R}_A$ include both bugs and false positives, $\Phi_A = \mathcal{R}_A \setminus \mathcal{U}$ (Figure 11).

Findings as Features Each deduplicated finding (Appendix A.4) is a feature, and each run records whether that feature was reported. For a fixed agent, configuration, budget, and repository state, write

$$B = \sum_{k=1}^{\infty} p_k \delta_{\theta_k}, \quad z_{ik} \mid B \sim \text{Bernoulli}(p_k), \quad \mathcal{F}_i = \{\theta_k : z_{ik} = 1\}. \quad (7)$$

Here θ_k identifies a finding, p_k is its per-run reporting probability, and δ_{θ_k} places unit mass at its identity. Conditional on B , the indicators are independent across runs and findings. The probabilities do not sum to one: a run can report multiple findings. This beta–Bernoulli construction provides a prior over binary feature matrices (Thibaux & Jordan, 2007).

The Three Parameters We model bug findings with a *three-parameter beta process*, also called the stable-beta process (Teh & Görür, 2009). The stable-beta process has mass $\alpha > 0$, concentration $c > -\sigma$, and discount $0 \leq \sigma < 1$. Its atoms (p_k, θ_k) form a Poisson point process with intensity

$$\nu(dp, d\theta) = C p^{-1-\sigma} (1-p)^{c+\sigma-1} dp G(d\theta), \quad C = \frac{\alpha \Gamma(c+1)}{\Gamma(1-\sigma) \Gamma(c+\sigma)}, \quad (8)$$

where G is a nonatomic probability measure over findings. The intensity is an expected atom count, not a normalized probability density.

The parameters have direct operational interpretations. Integrating p against the intensity gives $\mathbb{E}[|\mathcal{F}_i|] = \alpha$. Integrating p^2 gives

$$\mathbb{E}[|\mathcal{F}_1 \cap \mathcal{F}_2|] = \alpha \frac{1-\sigma}{c+1}. \quad (9)$$




Figure 11: The historical reference set $\mathcal{H}$ lies within the bug universe $\mathcal{U}$. The agent’s reachable findings $\mathcal{R}_A$ overlap both and extend to false positives Φ_A . Shading indicates per-run reporting probability, from a frequently rediscovered core to rare findings.




Figure 12: Observed and modeled distinct findings reported in exactly j of 10 GPT-5.6 Luna runs (log scale). Only the stable-beta process reproduces both the many singletons and the stable core of findings.

Thus larger c reduces expected pairwise sharing at fixed α, σ . The discount controls the accumulation of low-probability findings through the factor $p^{-1-\sigma}$. Setting $\sigma = 0$ recovers the ordinary beta process. Although there are infinitely many latent features, each run contains finitely many almost surely; marginally its size is $\text{Poisson}(\alpha)$ (Broderick et al., 2012).

E.2 FIT TO REPEATED RUNS

Parameter Estimation Parameters can be estimated from the frequency spectrum $M_{r,j}$, the number of findings reported in exactly j of r runs. Poisson thinning gives independent counts

$$M_{r,j} \sim \text{Poisson}(\mu_{r,j}), \quad \mu_{r,j} = \binom{r}{j} C B(j - \sigma, r - j + c + \sigma), \quad j = 1, \dots, r, \quad (10)$$

where $B(a, b)$ is the beta function. Their product likelihood supports fitting without enumerating unseen findings. All predictive equations above condition on fixed parameters.

Compared Models We fit the frequency spectrum of Muse Spark 1.3 (5 runs) and GPT-5.6 Luna (10 runs). Findings are deduplicated across runs, which gives $M_{r,j}$ for all reported findings, whether or not they match a historical bug. We compare the stable-beta process with two models of a finite pool. In the *binomial* model every finding has the same reporting probability q . In the *Beta-binomial* model reporting probabilities are drawn from $\text{Beta}(a, b)$, with $a, b \in [0.01, 50]$.

Findings that no run reported are not observed, so every model is fitted by maximum likelihood on the spectrum conditional on $j \geq 1$.

Results Table 22 reports Pearson’s χ^2 over the r bins, its p -value, and the sample-size-free $\sqrt{\chi^2/N}$ with N the number of distinct findings. The stable-beta process is the only model that is not rejected ($p = 0.36$ and $p = 0.064$). In contrast to a binomial or Beta-binomial bug discovery process, this captures both the frequent rediscovery of a stable core and continued discovery of rare findings we observe, see Figure 12.

Table 23 gives the fitted parameters. The two configurations have similar discounts, $\hat{\sigma} = 0.26$ and $\hat{\sigma} = 0.29$. The mass estimates, 7,772 and 2,644, agree with the mean number of deduplicated findings per run, 7,770 and 2,636, although the fit does not impose this. The Beta-binomial ends at its lower bound $a = 0.01$: its likelihood keeps increasing as $a \rightarrow 0$, where it approaches the stable-beta process at $\sigma = 0$, and the data ask for $\sigma > 0$. Its pool size is then set by the bound, not by the data, and is thus omitted. The binomial model implies a pool only slightly larger than the observed union, which the continued arrival of new findings contradicts: runs six to ten of GPT-5.6 Luna raise the union from 5,689 to 7,472 findings.

Table 22: Goodness of fit to the number of distinct findings reported in exactly j of r runs, conditional on $j \geq 1$. k is the number of fitted parameters and N the number of distinct findings.

Model	k	χ^2	df	p	$\sqrt{\chi^2/N}$
<i>Muse Spark 1.3, high: 5 runs, 15,233 distinct findings</i>					
Binomial	1	22,197.0	3	$< 10^{-99}$	1.207
Beta-binomial	2	318.0	2	8.9×10^{-70}	0.144
Stable-beta process	2	2.1	2	0.357	0.012
<i>GPT-5.6 Luna, medium: 10 runs, 7,472 distinct findings</i>					
Binomial	1	1.7×10^6	8	$< 10^{-99}$	14.908
Beta-binomial	2	401.8	7	9.6×10^{-83}	0.232
Stable-beta process	2	13.3	7	0.064	0.042

Table 23: Fitted parameters of the models in Table 22 and the pool size each implies. † marks a parameter at its bound; the pool size of that Beta-binomial is set by the bound and omitted. The latent pool of the stable-beta process is infinite.

Model	Parameters	Pool size
<i>Muse Spark 1.3, high: 5 runs, 15,233 distinct findings</i>		
Binomial	$q = 0.493$	15,761
Beta-binomial	$a = 0.010^\dagger, b = 0.612$	—
Stable-beta process	$\alpha = 7,772, c = 0.172, \sigma = 0.263$	∞
<i>GPT-5.6 Luna, medium: 10 runs, 7,472 distinct findings</i>		
Binomial	$q = 0.348$	7,577
Beta-binomial	$a = 0.010^\dagger, b = 0.827$	—
Stable-beta process	$\alpha = 2,644, c = 0.254, \sigma = 0.287$	∞

E.3 UNBOUNDED DISCOVERY AND FALSE POSITIVES

An Unbounded Pool of Findings The so-called discount parameter σ of the stable-beta process determines whether the model predicts a finite or unbounded finding pool; a negative σ gives the generalized finite beta–Bernoulli model (Battiston et al., 2018). For the fitted positive σ (Appendix E.2), the expected number of distinct findings grows unbounded as r^σ .

A Lower Bound on False Positives Let $\mathcal{S}_r = \bigcup_{i=1}^r \mathcal{F}_i$, $K_r = |\mathcal{S}_r|$, and $U = |\mathcal{U}| < \infty$. With findings deduplicated by defect identity, at most U members of $\mathcal{S}_r$ can be real bugs. For $K_r > 0$, the false-positive fraction of the accumulated distinct findings therefore satisfies

$$\frac{|\mathcal{S}_r \setminus \mathcal{U}|}{K_r} \geq \max\left\{0, 1 - \frac{U}{K_r}\right\}. \quad (11)$$

If $K_r \rightarrow \infty$, this fraction tends to one. This is a consequence of unbounded discovery and a finite bug universe, not of historical non-matches being false positives. A numerical lower bound at a finite budget requires an upper bound on U ; the incomplete reference set supplies only a lower bound. The result concerns the deduplicated union, not the false-positive fraction of an individual run, which can repeatedly report real bugs.

As a fixed repository contains only finitely many bugs, unbounded growth in distinct findings implies accumulating false positives. Retaining only findings reported in at least n runs thus isolates findings of increasingly higher minimum reporting probability, trading recall for precision as n increases (Figure 9).

F PROMPTS

This section prints PROBE’s prompts, grouped by the stage of §2 and §3 or the experiment of §4 they belong to.

A value substituted into a prompt at run time is set in *italics* and named rather than shown, so what is printed is the template and not one instance of it. Where a stage constrains its output, the harness appends the JSON schema of that output to the instructions.

F.1 ENVIRONMENT PREPARATION

F.1.1 SNAPSHOT ENVIRONMENT (PYTHON)

CODING AGENT Environment preparation for a Python repository. The agent writes the snapshot image and its fully pinned requirements, repins every package released after T_0 down to the last release before it, and must get the repository’s own test suite to run to completion. It is a brief for a coding agent working in the benchmark repository; <owner>, <repo> and <commit> stand for the repository being set up and its snapshot commit.

Prompt

```
# Snapshot environment setup --- Python repo `<repo>`

You are setting up a reproducible Docker test environment for the benchmark repo **`<repo>`** (a Python
repo already added as a git submodule under `repos/<owner>/<repo>/<commit>`, pinned at the
2025-01-01 snapshot commit).

## Goal

Produce a Docker image whose test suite runs to completion via **`environment/run_tests.py`**, with
every package version pinned to what was installable on the snapshot cutoff (this snapshot's entry
in `configs/environment/snapshot_config.json`). Nothing installed may be a version released after
the cutoff.

## Deliverables

1. `dockerfiles/<owner>/<repo>/<commit>/Dockerfile.base` --- the base image (build deps + pinned Python
env + editable install of `<repo>` + the test-runner CMD). `<commit>` is the 12-char short SHA of
the snapshot pin; the submodule checkout sits at `repos/<owner>/<repo>/<commit>`.
2. `dockerfiles/<owner>/<repo>/<commit>/requirements.txt` --- the **fully pinned** (`name==version`)
environment: runtime + test dependencies, all transitive deps included.
3. `dockerfiles/<owner>/<repo>/<commit>/build-constraints.txt` --- the repo's `[build-system]` requires`
and their transitive deps, pinned the same way; skip it for a repo with no `pyproject.toml`, which
pip builds unisolated (cf. prefect, sqlglot). Without it pip resolves the build backend fresh from
PyPI on every build, pulling post-cutoff packages into the snapshot.
4. A `<repo>` entry in `repos/repos.json` **if one does not already exist** --- `run_tests.py` requires
it. Match the existing entries' shape: `github_full_name` (lowercased `owner/name`), `snapshot_sha`
(the full snapshot commit), `language` (`python`), and `src_path` (in-repo source root, e.g.
`/<repo>`).

## Study these first (do not skip)

- `dockerfiles/opshin/opshin/<commit>/Dockerfile.base` + `requirements.txt` --- the simplest reference
(plain setup tools, top-level `tests/`).
- `dockerfiles/kozea/weasyprint/<commit>/Dockerfile.base` + `requirements.txt` --- reference for a repo
that needs extra **system libraries** (`apt-get install ...`) beyond `gcc`/`git`.
- `dockerfiles/prefecthq/prefect/<commit>/Dockerfile.base` + `requirements.txt` --- reference for a large
suite with pytest ini/marker/ignore tweaks in the CMD.
- `docker_scripts/run_sharded.sh` --- the in-container pytest runner every Python repo uses. It shards
`<tests_dir>` by top-level test file (`test_*.py` and `*_test.py`) / immediate subdir, runs each in
a fresh pytest process, and prints the final `=== TOTAL: N failed, N passed, N skipped, ... ===` line
that `run_tests.py` looks for. **Reuse it**;; do not invent a new runner.
- `environment/run_tests.py` --- how the suite is built and run (`build_base` → run the image's CMD,
capture stdout to `findings/<owner>/<repo>/<commit>/test_results.txt`, echo the TOTAL line).
- `environment/pin_to_snapshot.py` --- read its module docstring. It queries the PyPI JSON API for every
`name==version` pin in `dockerfiles/<owner>/<repo>/<commit>/requirements.txt` and repins anything
released after the cutoff down to the highest non-prerelease, non-yanked version at/before the
cutoff. Use it (see workflow).

## Dockerfile pattern (adapt, don't blindly copy)

Follow the shared skeleton from the reference Dockerfiles exactly for these parts, changing only the
`$OWNER/$REPO/$COMMIT` segments:

```dockerfile
FROM python:3.10.16-slim # see "Python version" below
```

```

RUN apt-get update && apt-get install -y \
 gcc \
 git \
 && rm -rf /var/lib/apt/lists/* # add repo-specific system libs here (cf. weasyprint)

WORKDIR /app
COPY dockerfiles/$OWNER/$REPO/$COMMIT/requirements.txt . # snapshot dockerfiles dir, mirrored by the
 checkout below
RUN pip install --no-cache-dir -r requirements.txt

COPY repos/$OWNER/$REPO/$COMMIT .
RUN rm .git

COPY dockerfiles/$OWNER/$REPO/$COMMIT/build-constraints.txt /tmp/build-constraints.txt
RUN PIP_CONSTRAINT=/tmp/build-constraints.txt pip install --no-cache-dir --no-deps -e .

COPY docker_scripts/run_sharded.sh /app/run_sharded.sh

COPY docker_scripts/init_snapshot_repo.sh /tmp/init_snapshot_repo.sh
RUN bash /tmp/init_snapshot_repo.sh /app

TOTAL: <paste the observed green TOTAL line here once you have it>
CMD ["timeout", "-k", "30", "10800", \
 "bash", "/app/run_sharded.sh", "<tests_dir>", \
 "-v", "--timeout=60", "--timeout-method=thread", "--tb=short", "-m", "not service"]
...

No image may ship the repo's upstream git history. Its `origin/*` refs are dated to clone time, so
an agent could read the post-snapshot fixes the benchmark measures against. `RUN rm .git` drops the
submodule gitlink, and `init_snapshot_repo.sh` --- last, after every install and build step, so the
tree is committed clean --- leaves a single-commit repo with no remotes, tags or parents.

That removes the tags a version-deriving build backend reads. If the repo uses `setuptools_scm`,
`hatch-vcs` or another SCM source, hand it the version the pin would have produced (`git describe
--tags` in the snapshot checkout), build-scoped so nothing persists into the container:

```dockerfile
RUN SETUPTOOLS_SCM_PRETEND_VERSION_FOR_<DIST>=<version> \
    PIP_CONSTRAINT=/tmp/build-constraints.txt \
    pip install --no-cache-dir --no-deps -e .
...

Use the unscoped `SETUPTOOLS_SCM_PRETEND_VERSION` under `hatch-vcs` (cf. jsonschema): it calls
setuptools_scm without a dist name, so the `_FOR_<DIST>` form is never read.

A repo with no `pyproject.toml` builds without pip's isolation, so `PIP_CONSTRAINT` does not reach its
`setup_requires`: add `--no-build-isolation` and pin those packages in `requirements.txt` instead
(cf. sqlglot).

## Choosing the pieces per repo (this is where repos differ)

- **Python version.** Prefer `python:3.10.16-slim` to match the other repos (9 of 10 use it). But check
the repo's `requires-python` (in `pyproject.toml`/`setup.cfg`) --- if it demands newer (e.g.
`>=3.11`), pick the lowest compatible pinned slim tag (networkx uses `python:3.11.11-slim` for
exactly this reason) and say why in your summary. Always pin the full `x.y.z` version --- a floating
minor tag re-resolves past the cutoff on a future rebuild.
- **System libraries.** If `pip install` or the tests fail on a missing shared library / native build,
add the needed `apt-get` packages (weasyprint is the template).
- **`<tests_dir>` for the CMD.** `run_sharded.sh` shards a directory. Find where this repo's tests
actually live: a top-level `tests/` (like opshin/weasyprint) or `Tests/` (fonttools), or inside the
package (`networkx/` --- the package itself, `pint/testsuite`, `jsonschema/tests`). Pass that path. If
tests are scattered per-subpackage with no single dir, prefer running against the installed package
(`pytest --pyargs $REPO ...`) instead --- but confirm `run_sharded.sh` can express that; if not, raise
it with me rather than hacking around it.
- **Marker / ignore flags.** Keep `-m "not service"` as the others do --- unless the repo defines its own
marker taxonomy for non-reproducible tests, in which case use it (pypdf: `-m "not enable_socket and
not samples"`). Add `--ignore=...` for test files that need network/external services or are otherwise
not reproducible in the sandbox (cf. prefect). Add pytest plugins the suite needs (e.g.
`pytest-timeout`) to `requirements.txt`.
- **Project adopts / odd tests.** If the repo's own `adopts` fight the harness, strip just the
offending flags with `--override-ini=adopts=...` and document why in a comment above the CMD (prefect
drops a mypy-stub flag with `-rfEs`; fonttools drops `--doctest-modules/--pyargs` with `-ra`).
`--deselect` individual tests that only pass under upstream's single-process ordering (cf.
jsonschema's comment), set `ENV` vars the suite expects (jsonschema's
`JSON_SCHEMA_TEST_SUITE=/app/json`), and skip benchmark plugins (`--benchmark-skip`, cf. pint).

## Workflow

1. **Add/verify the `repos.json` entry** (deliverable 4) so `run_tests.py` can resolve the repo.
2. **Assemble a fully-pinned `requirements.txt`** Install the repo plus its test extras in a throwaway
env and `pip freeze`, or read its `pyproject.toml`/`setup.cfg` test/dev extras and pin them --- the
end state is a complete `name==version` list (runtime + test + transitive), like the reference
files.

```

```

3. **Resolve `build-constraints.txt`** from the repo's `[build-system] requires` (pip's
  `setuptools`/`wheel` default when the table is absent): `printf '<req\n...' | uv pip compile -
  --exclude-newer <cutoff> --python-version <x.y> --no-header --no-annotate`. Then build with `pip
  install -v` and read the log: a backend may add build requirements dynamically that the closure
  misses (hatchling pulls `editables`), and anything installed outside the constraint set needs its
  own pin.
4. **Snapshot-pin:** run `uv run python environment/pin_to_snapshot.py $REPO` (dry run) to see which
  pins were released after the cutoff, then `--apply` to repin them. Resolve any `manual_review`
  entries by hand. Re-run until it reports no changes, then repeat with `--file build-constraints`.
5. **Build + run:** `uv run python environment/run_tests.py $REPO`. Iterate on the Dockerfile /
  requirements.txt until the suite is green (`0 failed, 0 errors`). Some pre-existing
  `skipped`/`xfailed` are fine; unexpected failures usually mean a wrong pin, a missing system lib, or
  a test needing a service you should `--ignore`.
6. **Record the result:** once green, paste the exact `=== TOTAL: ... ===` line into the `# TOTAL:`
  comment above the CMD (as the reference Dockerfiles do).

### If the full suite takes more than ~10 minutes

Do **not** run the whole thing yourself. Build the image and verify with a **representative subset** ---
run `run_sharded.sh` against one or two shards inside the container, or a handful of `-k`-selected
tests --- to confirm the environment is sound (imports work, deps resolve, tests execute and pass).
Configure the CMD to run the **full** suite regardless, note in your summary that you validated on a
subset only, and I will run the complete suite myself.

## Report back

Summarize: Python version chosen (and why if not 3.10), any system libs added, the `<tests_dir>` and any
`--ignore`/marker flags, anything `pin_to_snapshot.py` needed manual resolution for, the `TOTAL`
line (or the subset you validated + why the full run was deferred), and anything you were unsure
about.

```

F.1.2 SNAPSHOT ENVIRONMENT (TYPESCRIPT/JAVASCRIPT)

CODING AGENT Environment preparation for a TypeScript or JavaScript repository, the counter-
part of Appendix F.1.1. Dependencies are pinned to what the repository's lockfile resolved at the
snapshot commit. It is a brief for a coding agent working in the benchmark repository; `<owner>`,
`<repo>` and `<commit>` stand for the repository being set up and its snapshot commit.

Prompt

```

# Snapshot environment setup --- TypeScript/JavaScript repo `<repo>`

You are setting up a reproducible Docker test environment for the benchmark repo **<repo>** (a
TypeScript/JavaScript repo already added as a git submodule under `repos/<owner>/<repo>/<commit>`,
pinned at the 2025-01-01 snapshot commit).

## Goal

Produce a Docker image whose test suite runs to completion via **environment/run_tests.py**, with
every package version pinned to what the repo resolved at the snapshot commit. Nothing installed may
be a version released after the cutoff (this snapshot's entry in
`configs/environment/snapshot_config.json`).

## Deliverables

1. `dockerfiles/<owner>/<repo>/<commit>/Dockerfile.base` --- the base image (Node + package install from
the committed lockfile + build if needed + the test-runner CMD). `<commit>` is the 12-char short SHA
of the snapshot pin; these repos have no snapshot `requirements.txt`, so the base's `COPY` lines
all read from the `repos/<owner>/<repo>/<commit>` checkout (for a workspace monorepo like svelte,
see **Workspace layout** below).
2. A `<repo>` entry in `repos/repos.json` **if one does not already exist** --- `run_tests.py` requires
it. Match the existing entries' shape: `github_full_name` (lowercased `owner/name`), `snapshot_sha`
(the full snapshot commit), `language` (`"typescript"` or `"javascript"`, matching the repo's
primary language), and `src_path` (in-repo source root, e.g. `/src`; for a workspace monorepo, the
package under test, e.g. `/packages/svelte/src`).

There is **no `requirements.txt`** for these repos, and **pin_to_snapshot.py** does not apply (it is
PyPI-only). Pinning is achieved by installing from the repo's **committed lockfile** with a frozen
install (see below) --- that lockfile, at the snapshot commit, already encodes exactly the versions
that were resolved on the snapshot date.

## Study these first (do not skip)

- `dockerfiles/honojs/hono/<commit>/Dockerfile.base` --- the reference TS setup: pinned node, install from
the frozen lockfile (bun), `bun run build`, then run three vitest configs via
`run_vitest_tests.sh`.
- `dockerfiles/sveltejs/svelte/<commit>/Dockerfile.base` --- reference for a pnpm workspace monorepo:
corepack-pinned pnpm, whole-repo copy before the frozen install, and a COPYed custom
`vitest.no-browser.config.js` (in the same dockerfiles dir) that excludes the browser suite and

```

```

    raises timeouts.
- `dockerfiles/mozilla/pdf.js/<commit>/Dockerfile.base` --- reference for a build-harness repo: pinned
  node with the cutoff rationale spelled out, `ENV` test vars, a `gulp lib-legacy` build, then jasmine
  via `run_jasmine_tests.sh`.
- `docker_scripts/run_vitest_tests.sh` --- hono's in-container runner. It runs one or more vitest configs
  and emits the final `=== TOTAL: N failed, N passed, N skipped (S suites run, F failed) ===` line
  that `run_tests.py` looks for.
- `docker_scripts/run_sharded.sh` --- the Python runner; read it only to see the exact shape of the
  `=== TOTAL: ... ===` contract, in case your repo's test runner isn't vitest and you need a small
  wrapper that emits the same line.
- `environment/run_tests.py` --- how the suite is built and run (`build_base` → run the image's CMD,
  capture stdout to `findings/<owner>/<repo>/<commit>/test_results.txt`, echo the TOTAL line). Note:
  if no `=== TOTAL: ...` line is present it warns but still saves output --- aim to emit the line anyway
  for consistency with the other repos.

## Dockerfile pattern (adapt --- these repos differ more than the Python ones)

hono uses npm; your repo most likely uses npm with a committed `package-lock.json` (check!). Use
the package manager the repo's lockfile implies, and always do a frozen / clean install so
nothing re-resolves to a newer version:

- `package-lock.json` → `npm ci`
- `yarn.lock` → `yarn install --frozen-lockfile`
- `pnpm-lock.yaml` → `pnpm install --frozen-lockfile`
- `bun.lockb` / the textual `bun.lock` → `bun install --frozen-lockfile` (hono)

Skeleton (adapt the `$OWNER/$REPO/$COMMIT` segments, the package manager, the build step, and the test
CMD):

```dockerfile
FROM node:20.18.1-slim # exact pin, newest of the line at/before the cutoff --- see "Node
version" below

RUN apt-get update && apt-get install -y \
 git \
 && rm -rf /var/lib/apt/lists/* # add curl/unzip/build tooling only if the install needs it

WORKDIR /app

Copy just the manifest + lockfile first so the install layer caches independently of source.
COPY repos/$OWNER/$REPO/$COMMIT/package.json repos/$OWNER/$REPO/$COMMIT/package-lock.json ./
RUN npm ci

COPY repos/$OWNER/$REPO/$COMMIT .
RUN rm .git

RUN npm run build # only if tests need built output; many runners execute TS/JS test
files directly

COPY docker_scripts/run_vitest_tests.sh /app/run_vitest_tests.sh # copy the wrapper matching this
repo's runner (vitest/jest/mocha/ava/jasmine)

COPY docker_scripts/init_snapshot_repo.sh /tmp/init_snapshot_repo.sh
RUN bash /tmp/init_snapshot_repo.sh /app

TOTAL: <paste the observed green TOTAL line here once you have it>
CMD ["timeout", "-k", "30", "10800", \
 "bash", "/app/run_vitest_tests.sh", ""] # adapt to the actual runner --- see below
...

No image may ship the repo's upstream git history. Its `origin/*` refs are dated to clone time, so
an agent could read the post-snapshot fixes the benchmark measures against. `RUN rm .git` drops the
submodule gitlink, and `init_snapshot_repo.sh` --- last, after the install and any build step, so the
tree is committed clean --- leaves a single-commit repo with no remotes, tags or parents. A build step
that derives a version or build number from git history falls back to its no-repo default; say so
in your summary if the repo does that.

Choosing the pieces per repo (this is where repos differ)

- **Node version.** Pick the major line from the repo's `.nvmrc` / `package.json` `engines.node` (prefer
Node 20 unless the repo needs newer; if `.nvmrc` pins a non-LTS current release, use the nearest
LTS that satisfies `engines`), then pin the newest release of that line at/before the cutoff ---
currently `node:18.20.5-slim` / `node:20.18.1-slim` / `node:22.12.0-slim`; verify against
`https://nodejs.org/dist/index.json`. Never use a floating tag (`node:20-slim`): it re-resolves past
the cutoff on a future rebuild --- that drift shipped a newer ICU whose Unicode tables broke 32
pdf.js specs. State your choice and why.
- **Package manager.** Driven by the committed lockfile (see list above). If the repo has no
lockfile, a frozen install is impossible and fresh resolution would pull post-cutoff versions ---
stop and raise this with me rather than guessing pins.
- **Build step.** Some repos build before testing (hono: `bun run build`), others run tests directly
(ava / jest / mocha / vitest execute `.ts`/`.js` test files without a prior build). Include `npm run
build` only if the tests actually need built artifacts; skip it otherwise. Watch for heavy
`prepare`/`prepublish` scripts that `npm ci` may trigger --- you may need `npm ci --ignore-scripts`
plus an explicit lighter build.

```

```

- **Test runner + the TOTAL line.** The runner varies by repo (check `package.json` `scripts.test`).
 Reuse the matching in-container wrapper --- each emits the same `=== TOTAL: N failed, N passed, N
 skipped ... ===` line `run_tests.py` looks for, and each hard-fails if it cannot parse the runner's
 summary:
- **vitest** → `run_vitest_tests.sh` (pass the config path(s), `` for the default config): hono runs
 three configs, remeda the default, svelte a custom no-browser config.
- **jest** → `run_jest_tests.sh` (echarts: `--config test/ut/jest.config.cjs`; liquidjs: default
 config).
- **mocha** → `run_mocha_tests.sh` <spec ...> (mathjs: `test/unit-tests`; openlayers: `--recursive
 test/node --timeout 60000`; msgpack-javascript: `test/**/*.test.ts`).
- **ava** → `run_ava_tests.sh` (jose).
- **jasmine** → `run_jasmine_tests.sh` (pdf.js: `--config=test/unit/clitests.json`, standalone once
 the Dockerfile has run the `gulp lib-legacy` build).
- **anything else** → no wrapper yet; write a small `docker_scripts/run_<runner>_tests.sh` modelled on
 the above (run the suite so a failure doesn't mask counts, parse the summary, print the TOTAL
 line). If awkward, raise it with me first.
- **Workspace layout.** Most repos are flat, but some are workspace monorepos --- svelte is a **pnpm
 workspace** (`pnpm-workspace.yaml` + `pnpm-lock.yaml` at the root, target package under
 `packages/svelte`). Provision the repo-pinned pnpm via corepack, run the **frozen install at the
 root, and COPY the **whole repo before installing when a workspace member's lifecycle script
 needs its own source (svelte's playgrounds/sandbox `prepare` does --- manifests-only layer caching
 doesn't survive that). Run the target package's tests from the root and point `src_path` at the
 package source (`/packages/svelte/src`).
- **System libraries.** Add `apt-get` packages only if the install/tests need them (native addon builds,
 headless-browser test deps, etc.). Many top-level `test` scripts chain extra steps --- lint,
 coverage, or browser/rendering suites (mathjs `test` runs lint; openlayers `test` runs karma +
 rendering). Bypass the npm script and invoke the unit suite directly through the wrapper (mathjs:
 mocha on `test/unit-tests`; openlayers: mocha `--recursive test/node`) so the TOTAL reflects the
 real suite, and flag any sub-suites you skip and why (browser/rendering can't run headless here ---
 svelte excludes its Chromium suite via a custom vitest config). The build VM is throttled: raising
 in-suite timeouts is an accepted pattern (openlayers mocha `--timeout 60000`; svelte's 30s vitest
 timeouts), the outer CMD `timeout` still caps total wall-time.

Workflow

1. **Add/verify the `repos.json` entry** (deliverable 2) so `run_tests.py` can resolve the repo.
2. **Write `Dockerfile.base`** using the frozen install for this repo's package manager and the correct
 runner CMD.
3. **Build + run:** `uv run python environment/run_tests.py $REPO`. Iterate until the suite is green (`0
 failed`). Some pre-existing `skipped`/`todo` are fine.
4. **Verify pins:** confirm the install was frozen (no lockfile drift, no fresh resolution). If you had
 to touch the lockfile, that's a red flag --- investigate rather than commit a regenerated lockfile.
5. **Record the result:** paste the exact `=== TOTAL: ... ===` line into the `# TOTAL:` comment above the
 CMD.

If the full suite takes more than ~10 minutes

Do **not** run the whole thing yourself. Build the image and verify with a **representative subset**
(run one test file / a focused test filter inside the container) to confirm the environment is
sound. Configure the CMD to run the **full** suite regardless, note that you validated on a subset
only, and I will run the complete suite myself.

Report back

Summarize: Node version chosen (and why if not 20), package manager + install command, whether a build
step was needed, the test runner and how you emit the TOTAL line (reused vitest wrapper vs. new
script), any suites skipped (e.g. browser-only) and why, the `TOTAL` line (or the subset you
validated + why the full run was deferred), and anything you were unsure about.

```

## F.2 BENCHMARK CONSTRUCTION

### F.2.1 BUG-FIX COMMIT CLASSIFIER

**GPT-5.6 Terra** Classifier of Step 1 of benchmark construction: whether a commit corrects previously buggy runtime behavior.

#### System

You are classifying a single git commit as either a **\*\*bug fix\*\*** or **\*\*not a bug fix\*\*** (feature, refactor, docs, test, dependency bump, formatting, build, etc.).

A bug fix means the commit changes code so that a previously-buggy behavior is corrected --- a regression repaired, an incorrect output made correct, a crash prevented, a missing input validation added, a race resolved, a leak plugged, an off-by-one or comparison error corrected, a security flaw closed.

**\*\*Do NOT classify as bug fix:\*\***

- New features or enhancements (even if labeled "improve" or "handle X").
- Pure refactors that preserve behavior (but see the mixed-commit rule below).
- Documentation, test additions, comments, formatting.
- Dependency upgrades, version bumps, or lockfile/manifest changes --- even when the upstream release

```

fixes a bug or CVE. A bug fixed in a dependency is a bug in that dependency, not in this repository;
only changes to this repository's own code count. (Exception: vendored third-party source patched
directly in this repository's tree is an in-repo fix and does count.)
- Build/CI/tooling changes.
- Reverts (any commit whose subject starts with `Revert` --- reject outright).

Mixed commits: Classify on whether any part of the commit corrects a real, previously-buggy
behavior --- not on what dominates the change. A commit is a bug fix even when the bulk of it is an
unrelated refactor, feature, cleanup, or formatting, as long as it also repairs a genuine bug. Do
not reject a real fix just because it is a small hunk buried in a large diff. Set `confidence` to
reflect how sure you are that a real bug was fixed (a clearly buried but unmistakable fix can still
be `high`).

Edge cases:
- "Handle edge case X" that wasn't previously broken → not a bug fix.
- "Fix typo in error message" → bug fix only if the typo materially broke behavior; otherwise reject.
- "Make X more robust" → only if there is a specific symptom being fixed.

You will be given the commit message, the linked issue body and linked PR body (when GitHub resolved a
closing issue/PR --- otherwise both will read `(none)`), a file-change stat (`file | +N -N` lines),
and a diff excerpt. Very large diffs are truncated --- the middle is elided and replaced with a
`...[diff truncated: N of M chars elided]...` marker, leaving the head and tail visible. When you see
that marker, base the verdict on the visible head and tail hunks plus the commit message, the linked
bodies, and the stat.

Return ONLY a JSON object matching the generated JSON Schema appended to this prompt. Its field
descriptions are part of the output contract.

Few-shot examples

Example A --- subject: `tests: add regression test for #1421`, diff touches `tests/` only.
```json
{"is_bug_fix": false, "confidence": "high",
 "rationale": "Test-only commit; no production code changes.",
 "bug_kind_hint": ""}
```

Example B --- subject: `bump cryptography to 42.0.4 to pick up CVE-2024-XXXX`, diff updates a single
pinned dependency.
```json
{"is_bug_fix": false, "confidence": "high",
 "rationale": "Dependency version bump; the CVE lives in the upstream library, not in this repository's
code.",
 "bug_kind_hint": ""}
```

Example C --- subject: `Refactor _parse to use match statement`, diff is a behavior-preserving
rewrite.
```json
{"is_bug_fix": false, "confidence": "high",
 "rationale": "Pure refactor; control-flow rewritten without changing observable behavior.",
 "bug_kind_hint": ""}
```

Example D --- subject: `Refactor request parsing; also fix header-length off-by-one`, diff is a large
behavior-preserving rewrite that also corrects a real boundary bug.
```json
{"is_bug_fix": true, "confidence": "medium",
 "rationale": "Mostly a refactor, but it also repairs a genuine off-by-one in header-length handling, so
it counts as a bug fix.",
 "bug_kind_hint": "off-by-one"}
```

```

## User

Commit SHA: *commit SHA*  
Subject: *commit subject*

Body:  
*commit message body*

Linked issue body:  
*linked issue body, or (none)*

Linked PR body:  
*linked pull request body, or (none)*

File-change stat:  
*file-change stat*

Diff:  
*the commit diff, head-and-tail truncated to the configured budget*

## F.2.2 BUG EXTRACTOR

**GPT-5.6 Terra** Bug extractor of Step 2: it turns one bug-fixing commit into zero or more candidate bugs, one per distinct root cause.

### System

You are splitting a bug-fix commit into one or more **logical bugs**.

A logical bug means a distinct underlying defect in the pre-fix code. Do not split by symptom, affected entry point, failing test, or user-visible behavior. Multiple symptoms caused by the same root cause are one bug.

The commit is purported to fix at least one bug. Some commits bundle multiple unrelated fixes, and some get mislabeled by the upstream classifier. Your job is to:

1. Decide whether this commit really fixes a bug at all.
2. If yes, identify whether it fixes one distinct root-cause bug or several distinct root-cause bugs.
3. Emit one record per logical bug.
4. For each bug, pinpoint the **parent-side** line range that contains the buggy code: the lines the fix removes or modifies. For a hunk that only **adds** lines (a missing check or guard the fix inserts), the parent has no buggy line to point at --- set `parent_lines` to the insertion point `[A, A]`, where `A` is the parent line the new code follows (the last context line shown immediately before the `+` run; use `[1, 1]` when the insertion precedes the first line). Reserve `[0, 0]` for a bug you genuinely cannot localize to any hunk.

**Be CONSERVATIVE** about splitting. Default to one bug per commit.

Only split when it is obvious that the commit fixes two or more distinct bugs: separate root causes, separate broken invariants, unrelated correctness issues, or independent code paths that do not share the same fix rationale.

Do not split merely because one bug has multiple symptoms.

Examples:

- A URL parsing bug causes both the CLI and the backend server to crash on certain URLs. This is one bug: the root cause is the URL parsing defect. Do not create separate records for the CLI crash and server crash.
- A commit fixes URL parsing and also fixes input sanitization. These are two bugs if the fixes address independent defects.

**One logical bug, even if it spans files:**

- Caller/callee mismatch: the caller passes the wrong shape and the callee misinterprets it. List both files, with the file where the wrong behavior originates first.
- Shared helper repaired in one place that fixes several call sites.
- One root cause that manifests through several entry points, commands, APIs, or user-visible failures.
- A primary source file plus its test file (`tests/...` or `*.test.py`). **Omit** the test file from `files` --- the test only verifies the fix, it is not part of the buggy code.

**Split into multiple bugs only** when:

- The commit message itself lists distinct bugs, and the diff supports that they are separate root causes.
- Different files address visibly unrelated defects, such as a parser bug and an unrelated auth bug bundled in one commit.
- Hunks touch unrelated functions whose only commonality is being in the same module.
- The fixes correct independent wrong assumptions, checks, invariants, or data-handling paths.

**Reject the commit entirely** (emit `"bugs": []`) when the diff is not actually fixing a bug:

- Pure refactor, rename, formatting, or style change.
- Documentation, comments, or type hints with no behavioral change.
- Test-only edits where the fix is not in this commit.
- Performance improvement with no correctness impact.
- Dependency or configuration bump with no code-behavior change.
- Adding new functionality without correcting prior behavior.

Inputs you will see: the commit message, including subject and body; the linked issue body, if any; the linked PR body, if any; and the unified diff. Return **ONLY** a JSON object:

Follow the generated JSON Schema appended to this prompt. Its field descriptions are part of the output contract.

```
```json
{
  "bugs": [
    {
      "summary": "One-sentence description of what is wrong (snapshot-fresh, present tense --- not 'was wrong').",
      "files": ["path/to/primary_file.py", "path/to/secondary_file.py"],
      "hunks": [
        {
          "file": "path/to/primary_file.py",
          "parent_lines": [142, 156]
        }
      ],
      "bug_kind_hint": "off-by-one in loop bound"
    }
  ]
}
```

```

    }
  }
}
...

```

If the bug is truly cross-cutting (no single file dominates and multiple files share the wrong behavior), use a single record with `files`` listing every affected path and `hunks`` containing one entry per file. Do not invent splits.

User

Commit subject: *commit subject*

Commit body:
commit message body

Linked issue body:
linked issue body, or (none)

Linked PR body:
linked pull request body, or (none)

Diff:
the fix diff, head-and-tail truncated to the configured budget

F.2.3 BUG PRESENCE CHECK

GPT-5.6 Terra

Presence check of Step 4, run at high reasoning effort. The agent works in a read-only checkout at the snapshot with the later history available, and drops a candidate bug only when it can establish that the snapshot was not already wrong.

System

****Output format --- read this first.**** Your response MUST be exactly one JSON object matching the generated JSON Schema appended to this prompt --- its field descriptions are part of the output contract. No prose, no preamble, no markdown fences, no explanation outside the JSON. The very first character of your response must be `{`. The very last character must be `}`. Put all reasoning inside the `reasoning`` field. Any text outside the JSON object is a protocol violation.

You are deciding one candidate in a benchmark of historical bugs. A commit fixed something; the benchmark pins the code at an earlier ****snapshot**** revision and claims the bug was already there. Your job is to rule on that claim: ****was this a real bug at the snapshot revision (`keep\_A` or `keep\_B`), or was it not (`drop\_C` or `drop\_not\_present`)?****

Nobody has judged this candidate before you. There is no earlier verdict to agree with or overturn, and no queue clause telling you what to look at. You have the repository, you run the checks below on every candidate, and your citations decide.

Your working directory

You are running ****read-only**** in a checkout of this repository, pinned at the snapshot revision: ``HEAD`` is the snapshot. Do not attempt to write anything --- a command that wants to write the index will fail.

Read-only bounds what you may change, not what you may run. Besides the git commands below, ****you may run the snapshot's own code****: import a module and call it, enumerate a registry, or run the fix's own reproducer against the snapshot. A reproducer that passes at the snapshot is direct evidence the defect is not there, and a wrong result you produce yourself is the strongest realizability answer available. Cite what you ran as ``execution``, with the command as the locator and its output as the quote.

The object store also holds history ****after**** the snapshot, including the fix commit itself and the branch it landed on. That is the point of running you here: questions of the form "did this exist yet at the snapshot?" are decidable, and you must decide them by running git, not by inference.

The commands that answer most candidates:

```

- `git show <fix_sha>` --- the fix diff. `git show <fix_sha> --stat` first if it is large.
- `git show HEAD:<path>` --- the file as it stood at the snapshot. Use `git grep -n <name> HEAD -- <path>` to find a line.
- `git log -S '<token>' --oneline HEAD..<fix_sha> -- <path>` --- commits **after** the snapshot that added or removed that token. A hit here is a candidate for the commit that introduced the repaired precondition.
- `git log -S '<token>' --oneline HEAD -- <path>` --- the same search **before** the snapshot. A hit here means the token was already in play.
- `git merge-base --is-ancestor <sha> HEAD && echo ANCESTOR || echo NOT-ANCESTOR` --- the decisive

```

temporal test. Run it on the commit you identified and report both the command and its answer.

- ``git grep -n <name> HEAD`` --- every site of an identifier at the snapshot, across the repo. This is how you refute a claim that something is absent.

The prompt below gives you the candidate's pinned line ranges, the splitter's summary, the fix commit message, the linked issue and PR bodies, machine-generated mapping notes and deterministic provenance signals. It does **not** give you a symbol scan or an embedded diff: run ``git grep`` and ``git show`` yourself, which is better evidence than either --- line-level, uncapped, and taken from the snapshot rather than from a file state months later.

The two errors this stage exists to catch

The dominant failure is **temporal**: the fix repairs code, a parameter, an option, a compatibility target or a call path that arrived **after** the snapshot. The fix's diff looks like a real bug fix --- because it is one, against the **later** code. The candidate is still wrong, because the defect could not happen at the snapshot.

The second failure runs the other way: a real, triggerable defect is **killed** by an absence claim built from a partial window. The code called missing is in the file, a few hundred lines outside the pinned range. One ``git grep`` settles that too.

Both are decidable here. Neither is decidable by reading the excerpt.

Required checks

Run every check below and add at least one ``citations`` entry naming it in that entry's ``check`` field. A required check with no citation of its own, or one whose citation is a paraphrase instead of a command's output, invalidates the verdict. Name the check that settled it in ``decisive_check``; it must be one you cited.

- **fix_diff** --- read ``git show <fix_sha>``. Cite the hunk that carries the repair.
- **fix_shape** --- read ``git show <fix_sha> --stat``, then answer four questions about the change itself. Does it add a test, or did it have to **rewrite** an existing one's assertions? Does it touch documentation or a declared support surface? Does the linked issue carry a label affirming a defect? Does it leave equivalent call sites untouched? Cite the stat line, the test hunk, or the absence of one. This check asks what the author treated as required; it never says what is at the snapshot.
- **snapshot_file** --- read the candidate's file at the snapshot around the pinned line ranges, and wider if the ranges look like a hull. Cite a numbered line that bears on the claim. If the file does not exist at the snapshot, that itself is the citation.
- **temporal_ancestry** --- identify the commit that introduced the precondition the fix repairs, then run ``git merge-base --is-ancestor`` on it against the snapshot. Cite the commit (as ``introducing_commit``) and the ancestry answer (as ``ancestry``), and repeat both in the top-level ``introducing_commit`` and ``ancestry_answer`` fields whenever you run this check, whether or not it decides the resolution. If no such commit exists --- the precondition was always there --- say so and cite the pre-snapshot ``git log -S`` that shows it.
- **symbol_sites** --- ``git grep -n`` at the snapshot every identifier that is load-bearing for the defective path. Cite ``path:line`` and say whether the hit is a definition, a use, or a comment. A name that genuinely returns nothing is the strongest evidence of absence there is; report that as the citation. Imports, typing aliases and helpers the fix itself introduces are expected to be absent and prove nothing.
- **upstream_text** --- read the commit message and the linked issue and PR bodies given below, and quote the sentence that bears on the change. Read them for **leads** to chase in the checkout, above all a claim that some later PR or commit caused the problem. The sentence itself settles nothing: ``upstream_text`` may corroborate a resolution and may never be its ``decisive_check``.

The four resolutions

- **keep_A** --- the defect exists at the snapshot, is triggerable by an input or call path that exists at the snapshot, and a competent reviewer reading the snapshot code could identify it as wrong.
- **keep_B** --- the same, except recognizing it needs outside context: a runtime's quirk, a documented support commitment, a spec corner, a real nonconforming sample. B is a real bug; C is not.
- **drop_C** --- the snapshot behavior was not a bug.
- **drop_not_present** --- the defective code, control flow or data path the fix rewrites did not exist at the snapshot at all.

What decides it: keep freely, drop only on a cited ground

There is no prior verdict here, so nothing decides a candidate by default except the evidence you gather. The two directions do not carry the same burden.

A keep needs the realizability answer every verdict carries. Answer it in ``snapshot_misbehavior`` before you choose a resolution: would the pre-fix code crash or produce a wrong result on a realizable input at the snapshot? Realizable means the triggering input or call path exists **at** the snapshot --- place it there with ``git grep`` or ``git show HEAD:<path>``, never from the fix diff. Name the concrete crash or wrong result and the path that reaches it. A ``keep_A`` or ``keep_B`` that names one is a confident keep; one that cannot is a keep you should mark low-confidence and explain, never a drop you cannot ground.

A drop must name one of exactly four grounds in ``drop_ground``, and cite evidence that establishes it. Each ground is a fact about the snapshot code, and you must state it as one. How the commit or its PR describes itself is never a ground.

- **precondition_postdates** --- ``drop_C``. The trigger the fix repairs arrived after the snapshot.

Establish it with an `ancestry` citation answering `NOT-ANCESTOR` on the commit that introduced the precondition, or with a `symbol\_site` citation showing the load-bearing name absent repo-wide at `HEAD`. An `ancestry\_answer` of `ANCESTOR` removes this ground outright --- the precondition was already there, and you must then judge the defect on its merits.

- **deliberate_rejection** → `drop.C`. The snapshot rejects the input on purpose, through validation you can point at, and the fix relaxes it for broken producers. Establish it with a `snapshot\_line` citation of that validation. A crash the snapshot performs **unintentionally** on malformed input is a robustness defect, not a deliberate rejection.
- **capability_absent** → `drop.C`. The fix adds a capability, a compatibility target or a support surface the snapshot never had, and its absence broke nothing the snapshot itself promised. Establish it with a `snapshot\_line` or `symbol\_site` citation --- of the project's own declared surface (its build target, its runtime or platform configuration, its documented commitments, **its own committed tests**), or of equivalent call sites the fix left untouched. Code that is correct against everything the project declares it supports is not defective because some environment outside that surface cannot run it.
- **code_absent** → `drop.not\_present`. The code, control flow or data path the fix rewrites is not at the snapshot: the snapshot has a different implementation, already contains the check the fix adds, or lacks the code the fix modifies. Establish it with a `symbol\_site` or `snapshot\_line` citation. Prefer this over `precondition\_postdates` when the code itself is missing, not merely the requirement.

If you cannot name and cite a ground, keep. That is not deference to anyone --- it is the burden of proof. A keep that turns out wrong leaves one bad record in a benchmark that reports its contamination; an unproven drop removes a real bug for good.

Every ground above is settled by locating something, or by failing to locate it: a commit's ancestry, a validation site, a declared support surface, an absent symbol. **There is deliberately no ground for "this changes no observable behavior".** That claim rests on judging two code paths equivalent, which no command can settle, and a reader who believes it is often reading only part of what the change repairs. So if the change looks like pure hygiene to you and none of the four grounds fits, the answer is `keep.A` or `keep.B`, not a drop. Say in `snapshot\_misbehavior` that you could not establish a concrete misbehavior, answer with low confidence, and name the drop you considered in `runner\_up\_resolution`. Reporting an uncertain keep costs the benchmark one flagged record; the drop you cannot establish costs it a real bug.

Five standing rules

- The bug summary is a claim, not a finding.** An earlier automated step wrote it by reading the **fix commit**, so it describes this candidate as a defect before anyone judged whether it was one, and its wording carries the fixer's framing. Verify that the defect it describes is the defect at the pinned ranges: a commit often repairs several things, and the summary can name a different one than the ranges hold. And when the summary names more than one defect, account for every one of them before you drop --- ruling out one and ignoring the rest is not a ground.
- The pinned ranges are a pointer, and sometimes a wrong one.** When they hold code the summary describes, judge that code. When they hold nothing it describes, that is not absence: a defect a few hundred lines outside them is the commonest way a real bug is killed here. `git grep` the defect the summary names across the whole snapshot, and if it is present and triggerable there, that is a keep --- say in `reasoning` that the ranges pointed elsewhere.
- The fix diff is not evidence about what is at the snapshot.** It is taken against a parent revision months later. Its context lines routinely contain parameters, options, branches and helpers the snapshot lacks, and a realizability argument built out of them is the single most common way this benchmark leaks a non-bug. Code you have seen only in the fix diff is post-snapshot code until you place it at the snapshot with `git grep` or `git show HEAD:<path>`. Its tests and reproducers run against the later code and place no input at the snapshot.
- The fix diff is evidence about what the project treated as required.** What the author changed, what the author left alone, and which tests the author had to touch are facts about the fix, and they bear on whether the snapshot behavior was **wrong** rather than on whether it was **there**. That is the **fix_shape** check. Use the diff for that question and never for the other one.
- A real crash or wrong result stays a keep however the change was packaged.** A `STY:`, `MAINT:`, `ROB:` or "gracefully handle" framing, a maintenance label, a typing sweep, a release merge --- none of these demote a defect that produces a crash or a wrong answer on input the snapshot accepts. Neither does the opposite packaging: a `feat:` or `ENH:` prefix, an "adds support for" body, a version-milestone note or a release-notes line. A commit can add a capability and repair a defect at once, and which one this candidate names is a question about the snapshot code, not about the commit's own words.
- Absence must be proven, never inferred from the pinned ranges.** The ranges are a partial view; most of the file is never named. Shifted line numbers, renamed identifiers and reorganised surroundings are not absence --- a variant spelling of the same defect is the same defect. Only a repo-wide `git grep` that returns nothing for a load-bearing name supports **code_absent**.

Reading the deterministic provenance signals

Each is a prior; none decides on its own, and none is a **drop_ground**.

- **fix arrived via a merge commit**: about a quarter of true records arrive via merges --- a merge alone means nothing. It becomes evidence in combination: a release or **next**-branch merge subject plus a feature-shaped diff and no bug-affirming issue is the release-merge pattern, and it points you at **temporal_ancestry**.
- **commit-subject type prefix**: upstream's own label (`BUG:`, `ROB:`, `ENH:`, `STY:`, `DEV:`, `MAINT:`).

```

    Most `ROB:` commits repair genuine crash-on-malformed-input defects; some relax deliberate
    validation. The prefix picks which check to run, never the answer.
- `SZZ introducer status`: `ancestral` --- the blamed lines existed at the snapshot. `none_ancestral` ---
    the blamed commits are not ancestors of the snapshot, which *suggests* post-snapshot origin but does
    not prove it, since a pre-snapshot commit merged late is non-ancestral without postdating. Either
    way, run `temporal_ancestry` and let git answer. `no_introducers` --- no signal: added-only and
    formatting-only fixes blame nothing.
- `linked issue labels` / `linked PR labels`: upstream's own framing, verbatim. "Not bug", wontfix,
    enhancement and feature framing all point at a check; none of them is a ground. Labels can be sparse
    or stale. Read the label text rather than any bug-affirming flag derived from it: that flag is a
    substring match, so a label reading "not bug" sets it.

## How to weigh what you find

- An ancestry answer is the strongest evidence available to you. `NOT-ANCESTOR` on the commit that
    introduced the repaired precondition establishes `precondition_postdates` unless something else
    places the precondition at the snapshot; `ANCESTOR` removes the temporal explanation entirely.
- A `git grep` hit at the snapshot refutes an absence claim outright, and the kind of hit matters: a
    definition or a use places the code there, a match inside a comment or a string does not.
- Upstream text may corroborate a code-level finding; it never decides one. If you cannot state the
    resolution as a fact about the snapshot code, the upstream wording has not given you one.
- What the fix left alone is evidence. A commit that repairs one site while leaving equivalent sites
    untouched is usually accommodating one caller rather than repairing a defect the project recognises;
    `git grep` the same construct across the snapshot and say what you found. The mirror holds too: a
    fix that changes every site of a construct is repairing the construct.
- **A test in the snapshot tree is part of the snapshot's declared surface.** A snapshot test that
    asserts the behavior the fix changes is a `snapshot_line` citation, and it establishes
    `capability_absent` or `deliberate_rejection`: the project had pinned that behavior, so changing it
    is a decision rather than a repair. It runs the other way too --- a fixture committed at the snapshot
    that the snapshot code mishandles places a realizable input there without touching the fix diff, and
    that is a keep.
- A fix that had to **rewrite an existing test's assertions** is the sharpest form of the same evidence:
    the behavior it changed was codified. A fix that only **adds** a test pinning corrected behavior of
    a function that already exists shows the opposite. A fix that keeps the old default and adds an
    opt-in beside it, or adds a new entry point beside an untouched old one, is adding a capability. A
    fix carrying its own backward-compatibility guard is telling you the patch is a no-op on the
    snapshot-era target.
- Where the checks genuinely do not settle it, say so in `reasoning`, answer with low confidence, and
    name the close rival in `runner_up_resolution`. Do not manufacture a reading.

## Examples (synthetic --- the shas, paths and names below belong to no real repository)

**Example 1** --- a fix corrects a bounds comparison inside a per-chunk quota accounting path.
```json
{
 "citations": [
 {
 "check": "fix_diff", "kind": "fix_diff", "locator": "git show 7c3f19ab -- pkg/archive/chunker.py",
 "quote": "- if used > chunk_quota:\n+ if used >= chunk_quota:"
 },
 {
 "check": "fix_shape", "kind": "fix_diff", "locator": "git show 7c3f19ab --stat", "quote": "
 pkg/archive/chunker.py | 2 +- \n tests/test_chunker.py | 41 +++++"
 },
 {
 "check": "snapshot_file", "kind": "snapshot_line", "locator": "pkg/archive/chunker.py:88", "quote": "
 while remaining:"
 },
 {
 "check": "symbol_sites", "kind": "symbol_site", "locator": "git grep -n chunk_quota HEAD", "quote": "
 (no output)"
 },
 {
 "check": "temporal_ancestry", "kind": "introducing_commit", "locator": "git log -S 'chunk_quota'
 --oneline HEAD..7c3f19ab -- pkg/archive/chunker.py", "quote": "e28d4f60 add per-chunk quota
 accounting"
 },
 {
 "check": "temporal_ancestry", "kind": "ancestry", "locator": "git merge-base --is-ancestor e28d4f60
 HEAD", "quote": "NOT-ANCESTOR"
 },
 {
 "check": "upstream_text", "kind": "upstream_text", "locator": "PR body", "quote": "follow-up to the
 quota work landed last month"
 }
],
 "resolution": "drop_C",
 "drop_ground": "precondition_postdates",
 "decisive_check": "temporal_ancestry",
 "introducing_commit": "e28d4f60",
 "ancestry_answer": "NOT-ANCESTOR",
 "snapshot_misbehavior": "None. The quota the off-by-one governs does not exist at the snapshot --- the
 name has no occurrence anywhere in the tree --- so no input reaches the comparison.",
 "decisive_evidence": "e28d4f60, which introduced the quota accounting the fix repairs, is not an
 ancestor of the snapshot",
 "runner_up_resolution": "drop_not_present",
 "confidence": "high",
 "reasoning": "The repaired branch belongs to quota accounting added after the snapshot, and the
 snapshot tree has no occurrence of the name at all, so the defect had no way to trigger there."
}
```

**Example 2** --- a fix flips `return LoadFailure(...)` to `raise LoadFailure(...)` deep inside a large
annotation sweep; the pinned range covers only the file's imports.
```json
{
 "citations": [
 {
 "check": "fix_diff", "kind": "fix_diff", "locator": "git show 93b1c07e -- lib/manifest/loader.py",
 "quote": "- return ManifestError(path)\n+ raise ManifestError(path)"
 },
 {
 "check": "symbol_sites", "kind": "symbol_site", "locator": "git grep -n load_manifest HEAD --
 lib/manifest/loader.py", "quote": "742:def load_manifest(self, path):"
 },
 {
 "check": "fix_shape", "kind": "fix_diff", "locator": "git show 93b1c07e --stat", "quote": "34 files

```

```

 changed, 902 insertions(+), 871 deletions(-); no test file touched"},
{"check": "snapshot_file", "kind": "snapshot_line", "locator": "lib/manifest/loader.py:751", "quote":
 "
 return ManifestError(path)",
{"check": "snapshot_file", "kind": "execution", "locator": "python -c \"import lib.manifest.loader as
m; print(type(m.load_manifest(None, 'truncated.mf')))\", "quote": "<class
'lib.manifest.loader.ManifestError'>"},
{"check": "temporal_ancestry", "kind": "ancestry", "locator": "git merge-base --is-ancestor a4f28d15
HEAD", "quote": "ANCESTOR"},
{"check": "upstream_text", "kind": "upstream_text", "locator": "commit message", "quote": "STY:
 annotate the loader module"}],
"resolution": "keep_A",
"drop_ground": null,
"decisive_check": "snapshot_file",
"introducing_commit": "a4f28d15",
"ancestry_answer": "ANCESTOR",
"snapshot_misbehavior": "Loading a truncated manifest through the public path returns the error object
 instead of raising it, so the caller treats the failure as a value and carries on with a half-loaded
 manifest.",
"decisive_evidence": "lib/manifest/loader.py:751 at the snapshot returns the exception object instead
 of raising it, inside the function defined at 742",
"runner_up_resolution": null,
"confidence": "high",
"reasoning": "The function the fix rewrites exists at the snapshot at line 742, far outside the pinned
 range, and at 751 it returns the error rather than raising it, so the caller's failure is silently
 swallowed. The sweep packaging does not change that."}

...

Example 3 --- a fix makes a reader tolerate a repeated header field the format forbids.
```json
{"citations": [
{"check": "fix_diff", "kind": "fix_diff", "locator": "git show 05e9b3ca -- src/headers.py", "quote":
    "-
        raise HeaderError(...)\\n+
        continue"},
{"check": "snapshot_file", "kind": "snapshot_line", "locator": "src/headers.py:4417", "quote": "
        raise HeaderError(f\"repeated field at {pos}\\")"},
{"check": "fix_shape", "kind": "fix_diff", "locator": "git show 05e9b3ca -- src/headers_test.py",
    "quote": "-
        assert_raises(HeaderError, parse, doubled)\\n+
        assert parse(doubled).fields == 1"},
{"check": "symbol_sites", "kind": "symbol_site", "locator": "git grep -n HeaderError HEAD --
    src/headers.py", "quote": "4417:
        raise HeaderError(f\"repeated field at {pos}\\")"},
{"check": "temporal_ancestry", "kind": "ancestry", "locator": "git merge-base --is-ancestor d71a6e84
    HEAD", "quote": "ANCESTOR"},
{"check": "upstream_text", "kind": "upstream_text", "locator": "issue body", "quote": "our writer
    emits the field twice; please accept these files"}],
"resolution": "drop_C",
"drop_ground": "deliberate_rejection",
"decisive_check": "snapshot_file",
"introducing_commit": "d71a6e84",
"ancestry_answer": "ANCESTOR",
"snapshot_misbehavior": "None. src/headers.py:4417 raises deliberately on a repeated field, which the
    format forbids; the snapshot rejects the input on purpose rather than mishandling it.",
"decisive_evidence": "src/headers.py:4417 at the snapshot raises deliberately, through validation of a
    rule the format states",
"runner_up_resolution": "keep_B",
"confidence": "high",
"reasoning": "The snapshot rejects the input through explicit validation of a stated rule, and the fix
    relaxes it for a nonconforming writer, which is a leniency change rather than a defect repair. The
    ancestry answer rules out the temporal reading."}

...

**Example 4** --- a fix rewrites one call to avoid a language builtin so an embedded runtime can load the
    module.
```json
{"citations": [
{"check": "fix_diff", "kind": "fix_diff", "locator": "git show 1a9f47c2 -- src/shaping/shaper.ts",
 "quote": "-
 const tail = runs.findLast(isVisible)\\n+
 const tail =
 runs.slice().reverse().find(isVisible)"},
{"check": "snapshot_file", "kind": "snapshot_line", "locator": "src/shaping/shaper.ts:214", "quote":
 "
 const tail = runs.findLast(isVisible)"},
{"check": "snapshot_file", "kind": "snapshot_line", "locator": "tsconfig.json:4", "quote": "
 \"target\": \"ES2023\""},
{"check": "fix_shape", "kind": "fix_diff", "locator": "git show 1a9f47c2 --stat", "quote": "
 src/shaping/shaper.ts | 2 +-\\n 1 file changed, 1 insertion(+), 1 deletion(-)"},
{"check": "symbol_sites", "kind": "symbol_site", "locator": "git grep -n findLast HEAD -- src",
 "quote": "src/shaping/shaper.ts:214\\nsrc/layout/lines.ts:88\\nsrc/layout/lines.ts:132"},
{"check": "temporal_ancestry", "kind": "ancestry", "locator": "git merge-base --is-ancestor 6b8e05d3
 HEAD", "quote": "ANCESTOR"},
{"check": "upstream_text", "kind": "upstream_text", "locator": "PR body", "quote": "our embedded
 runtime has no findLast, so I patched it locally"}],
"resolution": "drop_C",
"drop_ground": "capability_absent",
"decisive_check": "snapshot_file",
"introducing_commit": "6b8e05d3",
"ancestry_answer": "ANCESTOR",
"snapshot_misbehavior": "None on any runtime the project declares. The call is correct against the
 declared target, and only an embedded runtime outside that surface lacks the builtin.",

```

```

"decisive_evidence": "tsconfig.json:4 at the snapshot declares the target the call is valid against,
and the fix left two equivalent call sites in src/layout/lines.ts untouched",
"runner_up_resolution": "keep_B",
"confidence": "high",
"reasoning": "The snapshot call is valid against the project's own declared target, and the fix changed
one site while leaving two identical uses in place, so it accommodates one runtime outside the
declared surface rather than repairing a defect the project recognises."}
...

```

Now run the required checks, then emit the JSON object. Do not write any text before the opening `{`. Do not write any text after the closing `}`. Do not wrap the JSON in a code fence.

### User

Bug summary (from splitter): *the splitter's one-line summary of the candidate bug*  
 Snapshot file: *snapshot file*

Working directory: a checkout of *repository* pinned at the snapshot; HEAD is *snapshot commit*.  
 Fix commit: *fix commit*  
 Fix commit's first parent (the diff base): *first parent of the fix commit*

Pinned candidate ranges (snapshot coordinates):  
*one line per pinned candidate range, in snapshot coordinates*

Candidate locations (numbered snapshot source, one block per candidate):  
 ...  
*numbered snapshot source, one block per candidate location*  
 ...

Fix commit message:  
*fix commit message*

Linked issue body:  
*linked issue body, or (none)*

Linked PR body:  
*linked pull request body, or (none)*

Mapping notes:  
*one line per mapping note, or (none)*

Deterministic provenance signals (machine-derived priors, not verdicts):  
 - fix arrived via a merge commit: *yes or no*  
 - commit-subject type prefix: *commit-subject type prefix, or (none)*  
 - SZZ introducer status: *the SZZ introducer status line*  
 - linked issue labels: *linked issue labels, or (none)*  
 - linked PR labels: *linked pull request labels, or (none)*

## F.2.4 BUG REPORT SYNTHESIZER

**GPT-5.6 Terra** Report synthesizer of Step 5. It writes the snapshot-time bug report of a surviving candidate bug against the snapshot code, without citing the fix.

### System

You are writing a **bug finding record** from a fix commit. The record must describe the bug **as it exists at a specific code snapshot**, using present-tense language --- not as a historical fix.

You will be given:

- The bug summary from the splitter step.
- A numbered list of **candidate locations** --- grounded line ranges the fix touched --- each shown as ``[index] path:start-end`` followed by the snapshot source with absolute line numbers.
- The unified diff of the fix (showing what changed).
- The commit message, linked issue body, and linked PR body, if available.

Write the record as if you discovered the bug fresh by reading the snapshot code. The audience is a security/code reviewer auditing the snapshot.

First decide **where** the bug is: set ``primary_candidate_index`` to the index of the single candidate whose lines a reviewer would point to as the defect site. Ignore candidates that are unrelated refactors, renames, or reformatting bundled into the same commit. Return ``0`` when only one candidate is listed. Then write the ``title`` and ``description`` about that candidate's lines.

**Omission bugs.** When the fix diff is purely additive (it only inserts lines --- a guard, check, or branch --- with no ``-`` deletions in the relevant hunk), the defect is the **absence** of that code at the snapshot. The candidate lines show the region where the missing check belongs, not a defective

```

visible statement. Write the `title` and `description` as an omission --- "missing X check in Y before
Z" --- describing what is not there and the consequence, rather than pointing at a correct-looking
line as if it were wrong.

Hard rules:

- Title and description must be present tense and describe the bug as currently present in the snippet.
- Do not reference the fix at all in `title` or `description`. Phrases like "was fixed by", "the patch",
 "the commit", "previously", "before this change" are forbidden in those two fields.
- Cite identifiers and line numbers from the snapshot snippet, not from the diff.
- The only field where you may reference the fix is `suggested_fix` --- there it is acceptable (and
 useful) to say "replace `xs[i]` with `xs[i % len(xs)]`" etc.

Examples

Title --- bad (past tense, references fix):
> "Fixed off-by-one when iterating range bounds in `compile_loop`"

Title --- good (present tense, names bug + locus):
> "Off-by-one in `compile_loop` skips the final element of `bounds`"

Description --- bad (narrates the patch):
> "The original code subtracted 1 from the length, which was wrong. The commit changes it to use the
 full length, fixing the iteration."

Description --- good (snapshot-fresh):
> "`compile_loop` iterates `range(len(bounds) - 1)` at line 142, which omits the final element of
 `bounds`. When a caller passes a non-empty list, the last item is silently dropped. Triggered on
 every call with `len(bounds) >= 1`."

Return ONLY a JSON object matching the generated JSON Schema appended to this prompt. Its field
descriptions are part of the output contract.

```

### User

```

Bug summary (from splitter): the splitter's one-line summary of the candidate bug
Snapshot file: snapshot file

Candidate locations (numbered snapshot source, one block per candidate):
...
numbered snapshot source, one block per candidate location
...

Fix commit message:
fix commit message

Linked issue body:
linked issue body, or (none)

Linked PR body:
linked pull request body, or (none)

Fix diff:
the fix diff

```

## F.2.5 DEDUPLICATION JUDGE

**Gemini 3.5 Flash** Deduplication judge of Step 6. It carries the same record block as the matcher judge of Appendix F.4.1, under a stricter rule: the two records must describe one root-cause defect rather than merely admit one fix, and identical snippets and coincident line ranges count as weak evidence because a snippet is grown to its enclosing function.

### Prompt

```

You are reviewing two historical bug records mined from the commit history of the same repository
snapshot. Each was reconstructed from a nearby post-snapshot fix commit. Decide whether the two
records describe the same underlying root-cause defect.

Two records are duplicates only if they are the same flaw --- a single fix resolves both because they
are one and the same defect, not merely because the two are related, adjacent, or one region
contains the other. Two genuinely different defects that happen to live in the same function are NOT
duplicates.

Important cautions when weighing the evidence:
- The code snippets are grown to the enclosing function or class, so two distinct defects in the same
 function can carry byte-identical snippets. Do not treat snippet overlap as evidence of duplication.
- Line ranges are approximate and can coincide for the same reason. Weigh the titles and descriptions ---
 the described mechanism, trigger, and faulty behaviour --- over snippet or line-range overlap.

```

```

- When the two descriptions point at different mechanisms or different lines of the same function, treat
 them as distinct defects.

=== BUG A ===
ID: id of A
Title: title of A
File: file of A: first line of A- last line of A
Description:
description of A

Code snippet:
...
code snippet of A
...

=== BUG B ===
ID: id of B
Title: title of B
File: file of B: first line of B- last line of B
Description:
description of B

Code snippet:
...
code snippet of B
...

First, briefly reason through the evidence: compare the described defects, their triggers, and the
faulty behaviour, treating identical snippets and coincident line ranges as weak signals. Then
output your conclusion as a single fenced JSON block matching the JSON Schema appended below; its
field descriptions are part of the output contract.

```

### F.3 BENCHMARK VALIDATION

#### F.3.1 FALSE-POSITIVE AUDITOR

**GPT-5.6 Terra** False-positive auditor of the benchmark validation, run at high reasoning effort over every shipped reference bug. It works read-only in a checkout pinned at the snapshot, with the later history reachable, and may drop a record only on a ground it establishes with a citation of an accepted kind; the fix's commit message, issue and pull-request text are inadmissible as citations.

#### System

```

Output format --- read this first. Your response MUST be exactly one JSON object matching the
generated JSON Schema appended to this prompt --- its field descriptions are part of the output
contract. No prose, no preamble, no markdown fences, no explanation outside the JSON. The very first
character of your response must be `{`. The very last character must be `}`. Put all reasoning
inside the `reasoning` field. Any text outside the JSON object is a protocol violation.

You are auditing one record of a benchmark of historical bugs for false positives. A later commit
fixed something; the benchmark pins the code at an earlier snapshot revision and ships a record
claiming that a defect was already there, at a named file and line range, described by a title and a
description. Your job is adversarial: find and cite a ground on which the record is wrong. If
no ground survives your checks, say so --- `ground: none` --- and give the realizability answer that
makes it a real bug.

You are not the gate that admitted this record and you do not know what it concluded. Nobody's verdict
is in front of you. You have the repository, you run every check below, and your citations decide.

Your working directory

You are running read-only in a checkout of this repository, pinned at the snapshot revision: `HEAD`
is the snapshot. Do not attempt to write anything.

Read-only bounds what you may change, not what you may run. Besides git, you may run the snapshot's
own code: import a module and call it, or run the fix's own reproducer against the snapshot. A
reproducer that passes at the snapshot is direct evidence the defect is not there; a wrong result
you produce yourself is the strongest realizability answer available. Cite what you ran as
`execution`, with the command as the locator and its output as the quote.

The object store also holds history after the snapshot, including the fix commit. Questions of the
form "did this exist yet at the snapshot?" are decidable, and you decide them by running git, not by
inference.

Read the fix as a diff, never as a commit. Commit messages, pull-request text and issue text are the
fixer's framing, and they are not evidence about the snapshot. Use these forms and no other:

```

```

- `git diff <fix_sha>^ <fix_sha> -- <path>` --- the fix diff for one file; `git diff --stat <fix_sha>^
 <fix_sha>` for its shape.
- `git show HEAD:<path>` --- the file as it stood at the snapshot; `git grep -n <name> HEAD -- <path>` to
 find a line.
- `git log -S '<token>' --format='%h %ad' --date=short HEAD..<fix_sha> -- <path>` --- commits **after**
 the snapshot that added or removed that token; the same with `HEAD` alone for **before** the
 snapshot. Always pass --format; never read a subject or body.
- `git merge-base --is-ancestor <sha> HEAD && echo ANCESTOR || echo NOT-ANCESTOR` --- the decisive
 temporal test.
- `git grep -n -w <name> HEAD` --- every site of an identifier at the snapshot, repo-wide.

`git show <sha>` without a path, `git log` without --format, and any citation of kind 'upstream_text'
invalidate the verdict.

Required checks

Run every check below and add at least one 'citations' entry naming it in that entry's 'check' field. A
required check with no citation of its own, or one whose citation is a paraphrase instead of a
command's output, invalidates the verdict. Name the check that settled it in 'decisive_check'; it
must be one you cited.

- **`fix_diff`** --- read the fix diff for the record's file. Cite the hunk that carries the repair.
- **`fix_shape`** --- read the diff stat. Does the fix add a test, or rewrite an existing test's
 assertions? Does it touch a declared support surface? Does it leave equivalent call sites untouched?
 Cite the stat line or the test hunk. This check asks what the author treated as required; it never
 says what is at the snapshot.
- **`snapshot_file`** --- read the record's file at the snapshot around the pinned lines, and wider if the
 range looks like a hull. Cite a numbered line that bears on the claim.
- **`temporal_ancestry`** --- identify the commit that introduced the code or the precondition the fix
 repairs, then run 'git merge-base --is-ancestor' on it against the snapshot. Cite the commit (as
'introducing_commit') and the answer (as 'ancestry'), and repeat both in the top-level
'introducing_commit' and 'ancestry_answer' fields. If no such commit exists because the code was
always there, say so and cite the pre-snapshot 'git log -S' that shows it.
- **`symbol_sites`** --- 'git grep -n -w' at the snapshot every identifier that is load-bearing for the
 described defect. Cite 'path:line' and say whether the hit is a definition, a use, or a comment. A
 name that returns nothing is the strongest evidence of absence there is. Names the fix itself
 introduces are expected to be absent and prove nothing.
- **`location`** --- does the pinned file and line range hold the defect the description names? When they
 do not, find where it is and measure the tie: the function, method or class the pinned lines belong
 to ('git show HEAD:<path>' around both sites), and the line distance to the nearest pinned line or
 span. Cite the pinned lines that hold it, or the true site with its enclosing unit and distance, or
 the 'git grep' that finds it nowhere. Put the true site in 'defect_site' whenever it is outside the
 pinned lines.
- **`description`** --- does the description match the code at the location? Cite the line that bears it
 out, or the line that contradicts it.

The five grounds

- **`none`** --- the record is right: the described defect is at the snapshot, at the pinned lines or
 within reach of them (the ties 'wrong_location' lists), and a realizable input or call path that
 exists at the snapshot makes it crash or produce a wrong result. Answer 'snapshot_misbehavior' with
 that input and that result. When the pinned lines do not hold the defect, name the true site in
'defect_site'.
- **`temporal`** --- the defective code, or the precondition that makes it trigger, arrived after the
 snapshot. 'drop_ground' is 'precondition_postdates' (established by an 'ancestry' citation answering
'NOT-ANCESTOR', or a 'symbol_site' citation showing the load-bearing name absent repo-wide at
'HEAD') or 'code_absent' (the code the fix rewrites is not at the snapshot: a different
implementation, the check already present, the code missing --- a 'symbol_site' or 'snapshot_line'
citation). An 'ancestry_answer' of 'ANCESTOR' removes 'precondition_postdates' outright.
- **`not_defect`** --- the snapshot behaviour was not a bug. 'drop_ground' is 'deliberate_rejection' (the
 snapshot rejects the input on purpose through validation you cite with a 'snapshot_line', and the
 fix relaxes it; an 'unintentional' crash on malformed input is a robustness defect, not this) or
'capability_absent' (the fix adds a capability, a compatibility target or a support surface the
 snapshot never declared, and its absence broke nothing the snapshot promised --- cite the declared
 surface: its tests, docs, build or runtime configuration, or the equivalent call sites the fix left
 alone). A typing-only change with no realizable wrong result and no compile failure on the
 snapshot's own declared target is 'capability_absent', citing that target.
- **`wrong_location`** --- a real defect exists at the snapshot, but the record's pointer would not lead a
 reader or a matcher to it. The pin is located, and the answer is 'none', when the defect is inside
 the pinned lines or spans, or inside the same function, method or class as the pinned lines; a pin
 that sits in no such unit (imports, module-level code) is located when the defect is within 10 lines
 of a pinned line or span in the same file. Nothing else locates a pin: not a call site, not a
 caller, not a sibling occurrence of the same defect, not a line the description names.
'wrong_location' remains when the defect is in another file, or in the pinned file outside the
 pinned unit. Cite the 'symbol_site' or 'snapshot_line' where it actually is and the pinned lines
 that do not hold it, set 'defect_site', and say which tie fails.
- **`wrong_description`** --- the harm the record states, the crash or the wrong result, is contradicted
 at the snapshot: the pinned code cannot produce it on any input, or the description names a
 different defect than the one at the location. Cite the 'snapshot_line' that contradicts it; an
'execution' that refutes the claimed behaviour is the strongest form. A wrong mechanism sentence, a
 wrong blast-radius or severity sentence, a wrong line number, an alias name, an illustrative example
 that does not trigger, or an inaccurate detail is not this ground when the title, the pinned code
 and the suggested fix identify the same real defect: note the inaccuracy in 'reasoning' and answer
'none'.

```

When more than one ground applies, take the first in this order: `temporal`, `not\_defect`, `wrong\_location`, `wrong\_description`, and name the other in `runner\_up\_ground`.

**## The burden of proof**

A ground must be **established** by a citation of an accepted kind, stated as a fact about the snapshot code. How the commit or its author framed the change is never a ground. There is deliberately no ground for "this changes no observable behaviour": that claim rests on judging two code paths equivalent, which no command settles. If the change looks like hygiene and none of the five grounds fits, the answer is `none` with a low confidence and `snapshot\_misbehavior` saying what you could not establish.

The asymmetry runs the other way too. You are the prosecutor: a `none` you did not try to overturn is a failed check. Before answering `none`, you must have run the temporal test, searched the load-bearing names, read the pinned lines, and named the realizable input.

**## Standing rules**

**\*\*The description is a claim, not a finding.\*\*** It was written from the fix commit, so it describes the record as a defect before anyone judged whether it was one, and it carries the fixer's framing. Verify that the defect it describes is the defect at the pinned lines. An inaccurate sentence around a correctly identified defect is not a ground.

**\*\*The pinned range is a pointer, and sometimes a wrong one.\*\*** When it holds nothing the description names, that is not absence: `git grep` the defect across the whole snapshot. Present and triggerable inside the pinned unit is `none` with `defect\_site` set; outside it is `wrong\_location`; present nowhere is `temporal` with `code\_absent`.

**\*\*The fix diff is not evidence of what is at the snapshot.\*\*** Its context lines routinely contain parameters, options, branches and helpers the snapshot lacks. Code you have seen only in the fix diff is post-snapshot code until you place it at the snapshot with `git grep` or `git show HEAD:<path>`.

**\*\*The fix diff is evidence of what the project treated as required.\*\*** What the author changed, left alone, and which tests had to change bear on whether the snapshot behaviour was *\*wrong\**, never on whether it was *\*there\**. That is the `fix\_shape` check.

**\*\*A real crash or wrong result stays `none` however the change was packaged.\*\*** A typing sweep, a "gracefully handle", a release merge, a `feat:` or `ENH:` framing demotes nothing and promotes nothing. The question is about the snapshot code.

**\*\*Absence must be proven repo-wide, never inferred from the pinned range.\*\*** Shifted line numbers, renamed identifiers and reorganised surroundings are not absence; a variant spelling of the same defect is the same defect.

**\*\*A test in the snapshot tree is part of the snapshot's declared surface.\*\*** A snapshot test that asserts the behaviour the fix changes establishes `capability\_absent` or `deliberate\_rejection`; a fixture committed at the snapshot that the snapshot code mishandles places a realizable input there, and that is `none`.

**## Examples (synthetic --- the shas, paths and names below belong to no real repository)**

**\*\*Example 1\*\*** --- a record claims an off-by-one in per-chunk quota accounting; the quota does not exist at the snapshot.

```

---json
{"ground": "temporal", "drop_ground": "precondition_postdates",
"citations": [
 {"check": "fix_diff", "kind": "fix_diff", "locator": "git diff 7c3f19ab^ 7c3f19ab --
 pkg/archive/chunker.py", "quote": "- if used > chunk_quota:\n+ if used >= chunk_quota:"},
 {"check": "fix_shape", "kind": "fix_diff", "locator": "git diff --stat 7c3f19ab^ 7c3f19ab", "quote":
 " pkg/archive/chunker.py | 2 +- \n tests/test_chunker.py | 41 ++++++"},
 {"check": "snapshot_file", "kind": "snapshot_line", "locator": "pkg/archive/chunker.py:88", "quote":
 " while remaining:"},
 {"check": "symbol_sites", "kind": "symbol_site", "locator": "git grep -n -w chunk_quota HEAD",
 "quote": "(no output)"},
 {"check": "temporal_ancestry", "kind": "introducing_commit", "locator": "git log -S 'chunk_quota'
 --format='%h %ad' --date=short HEAD..7c3f19ab -- pkg/archive/chunker.py", "quote": "e28d4f60
 2025-03-02"},
 {"check": "temporal_ancestry", "kind": "ancestry", "locator": "git merge-base --is-ancestor e28d4f60
 HEAD && echo ANCESTOR || echo NOT-ANCESTOR", "quote": "NOT-ANCESTOR"},
 {"check": "location", "kind": "snapshot_line", "locator": "pkg/archive/chunker.py:85-92", "quote": "
 while remaining:\n chunk = remaining[size:]"},
 {"check": "description", "kind": "snapshot_line", "locator": "pkg/archive/chunker.py:85-92", "quote":
 "(no quota comparison in the pinned range or the file)"}],
"decisive_check": "temporal_ancestry", "introducing_commit": "e28d4f60", "ancestry_answer":
 "NOT-ANCESTOR",
"snapshot_misbehavior": "None. The quota the comparison governs does not exist at the snapshot --- the
 name has no occurrence in the tree --- so no input reaches it.",
"decisive_evidence": "e28d4f60, which introduced the quota accounting the fix repairs, is not an
 ancestor of the snapshot",
"defect_site": null, "runner_up_ground": "wrong_description", "confidence": "high",
"reasoning": "The repaired comparison belongs to quota accounting added after the snapshot, and the
 snapshot tree has no occurrence of the name, so the described defect had no way to trigger there."}

```

```

Example 2 --- a record claims a loader returns an exception object instead of raising it; the pinned
range is the head of the function, the defect is nine lines further down inside it.
---json
{"ground": "none", "drop_ground": null,
 "citations": [
 {"check": "fix_diff", "kind": "fix_diff", "locator": "git diff 93b1c07e^ 93b1c07e --
 lib/manifest/loader.py", "quote": "- return ManifestError(path)\n+ raise
 ManifestError(path)"},
 {"check": "fix_shape", "kind": "fix_diff", "locator": "git diff --stat 93b1c07e^ 93b1c07e", "quote":
 " lib/manifest/loader.py | 2 +-"},
 {"check": "snapshot_file", "kind": "snapshot_line", "locator": "lib/manifest/loader.py:751", "quote":
 " return ManifestError(path)"},
 {"check": "symbol_sites", "kind": "symbol_site", "locator": "git grep -n -w load_manifest HEAD --
 lib/manifest/loader.py", "quote": "742:def load_manifest(self, path):"},
 {"check": "temporal_ancestry", "kind": "ancestry", "locator": "git merge-base --is-ancestor a4f28d15
 HEAD && echo ANCESTOR || echo NOT-ANCESTOR", "quote": "ANCESTOR"},
 {"check": "location", "kind": "snapshot_line", "locator": "lib/manifest/loader.py:742-751", "quote":
 "def load_manifest(self, path):\n ...\n return ManifestError(path)"},
 {"check": "description", "kind": "execution", "locator": "python -c \"import lib.manifest.loader as
 m; print(type(m.load_manifest(None, 'truncated.mf')))\n\"", "quote": "<class
 'lib.manifest.loader.ManifestError'>"}],
 "decisive_check": "description", "introducing_commit": "a4f28d15", "ancestry_answer": "ANCESTOR",
 "snapshot_misbehavior": "Loading a truncated manifest returns the error object instead of raising it,
 so the caller carries on with a half-loaded manifest --- at loader.py:751, nine lines below the pinned
 742-748.",
 "decisive_evidence": "the execution shows the returned-not-raised error at lib/manifest/loader.py:751
 inside load_manifest, whose head is the pinned range 742-748",
 "defect_site": "lib/manifest/loader.py:751", "runner_up_ground": "wrong_location", "confidence":
 "high",
 "reasoning": "The defect the description names is real and triggerable at the snapshot; the pin is
 inside load_manifest, nine lines above the defective statement, so a finding written at 751 would
 match this record and the record stands with the true site named."}

Example 3 --- the same record with the pinned range on the file's imports; the defect is 700 lines
down, in a function the pinned lines are not part of.
---json
{"ground": "wrong_location", "drop_ground": null,
 "citations": [
 {"check": "fix_diff", "kind": "fix_diff", "locator": "git diff 93b1c07e^ 93b1c07e --
 lib/manifest/loader.py", "quote": "- return ManifestError(path)\n+ raise
 ManifestError(path)"},
 {"check": "fix_shape", "kind": "fix_diff", "locator": "git diff --stat 93b1c07e^ 93b1c07e", "quote":
 " lib/manifest/loader.py | 2 +-"},
 {"check": "snapshot_file", "kind": "snapshot_line", "locator": "lib/manifest/loader.py:751", "quote":
 " return ManifestError(path)"},
 {"check": "symbol_sites", "kind": "symbol_site", "locator": "git grep -n -w load_manifest HEAD --
 lib/manifest/loader.py", "quote": "742:def load_manifest(self, path):"},
 {"check": "temporal_ancestry", "kind": "ancestry", "locator": "git merge-base --is-ancestor a4f28d15
 HEAD && echo ANCESTOR || echo NOT-ANCESTOR", "quote": "ANCESTOR"},
 {"check": "location", "kind": "snapshot_line", "locator": "lib/manifest/loader.py:1-14", "quote":
 "import os\nimport json"},
 {"check": "description", "kind": "execution", "locator": "python -c \"import lib.manifest.loader as
 m; print(type(m.load_manifest(None, 'truncated.mf')))\n\"", "quote": "<class
 'lib.manifest.loader.ManifestError'>"}],
 "decisive_check": "location", "introducing_commit": "a4f28d15", "ancestry_answer": "ANCESTOR",
 "snapshot_misbehavior": "Loading a truncated manifest returns the error object instead of raising it,
 so the caller carries on with a half-loaded manifest --- at loader.py:751, not in the pinned lines
 1-14.",
 "decisive_evidence": "the pinned range 1-14 holds imports; the returned-not-raised error is at
 lib/manifest/loader.py:751 inside load_manifest, defined at 742",
 "defect_site": "lib/manifest/loader.py:751", "runner_up_ground": "none", "confidence": "high",
 "reasoning": "The defect is real, but the pin sits in no function and the defect is 737 lines away, far
 outside the 10-line allowance for a pin outside any unit; a finding at 751 would be scored against
 the wrong place."}

Now run the required checks, then emit the JSON object. Do not write any text before the opening `{`. Do
not write any text after the closing `}`. Do not wrap the JSON in a code fence.

```

## User

Record id: *record id*  
Repository: *repository*  
Working directory: a checkout pinned at the snapshot; HEAD is *snapshot commit*.  
Fix commit(s):  
*one line per fix commit*

Pinned location: *snapshot file:first pinned line-last pinned line*

```

Pinned spans (snapshot coordinates):
one line per pinned span, in snapshot coordinates

Title: record title

Description:
record description

Suggested fix (part of the record, not evidence):
the record's suggested fix

```

## F.4 HISTORICAL BUG MATCHING

### F.4.1 MATCHER JUDGE

**Gemini 3.5 Flash** Matcher judge. It decides whether a finding and a reference bug describe the same defect, and is the benchmark's scoring function: recall and precision are counted from its verdicts. The merge of Step 6 uses the stricter variant of Appendix F.2.5.

#### Prompt

```

You are reviewing two automated bug findings to decide if they are duplicates.

Two bugs are duplicates if:
- A single code fix would resolve both, OR
- One bug is a subset of the other (fixing the larger bug automatically fixes the smaller one).

=== BUG A ===
ID: id of A
Title: title of A
File: file of A: first line of A-last line of A
Description:
description of A

Code snippet:
```
code snippet of A
```

=== BUG B ===
ID: id of B
Title: title of B
File: file of B: first line of B-last line of B
Description:
description of B

Code snippet:
```
code snippet of B
```

First, briefly reason through the evidence: compare the files, line ranges, descriptions, and code
snippets. Then output your conclusion as a single fenced JSON block matching the JSON Schema
appended below; its field descriptions are part of the output contract.

```

## F.5 THE AUDIT HARNESS

### F.5.1 REPOSITORY CONTEXT DOCUMENT

**Claude Opus 5** Exploration prompt. One run per repository writes the repository context document that every audit pass of Appendix F.5.2 is given. It is mounted as CLAUDE.md into a container layered on the snapshot image, so the agent reads the repository rather than being handed it.

#### System

```

AGENTS.md --- Repository Exploration Pass

Task

Produce a structured context report for this repository. The report will be injected verbatim into the
system prompts of downstream per-file bug-finding agents and the validation agents that adjudicate
their findings.

This is a one-time exploration pass --- not a bug-finding pass. Do not report bugs. Map structure,

```

purpose, architecture, conventions, and scope.

Downstream agents use this file for exactly two decisions:

1. **G1 --- Reachability**: Is the affected function part of the public API surface, or does any internal caller pass the problematic input?
2. **G2 --- Expected Behavior**: Is the input within the project's supported scope, or --- if the input is in scope --- is the observed behavior documented as intentional or as a deliberate refusal? Judges further categorize G2 rejections as `'out-of-scope'`, `'intentional'`, or `'unsupported-feature'`.

Bug finders additionally need cross-module context (abstractions, contracts, pipeline shape) that they cannot reconstruct from a single file.

**Every line in this file is injected into the context of every downstream agent on every pass --- spend lines only on what changes verdicts or unblocks single-file reasoning.**

**## Exploration Workflow**

You have shell access. Use it freely.

**### Phase 1 --- Project Identity**

Read `README`, `pyproject.toml` / `setup.py` / `package.json` to determine: what the project does (one paragraph), primary language and runtime, key dependencies, install/run commands. Skim `CHANGELOG`, `ARCHITECTURE.md`, `CONTRIBUTING.md`, `docs/` for stated design decisions and non-goals.

**### Phase 2 --- Architecture Map**

Map the directory structure by listing the repo's source files (adjust the pattern to the project's language). For example:

```

...
Python
find . -not -path './.git/*' -not -path '*/__pycache__/*' -not -path '*/tests/*' -not -path '*/test/*'
-not -name 'test_*.py' -not -name 'conftest.py' -name '*.py' | sort | head -300
TypeScript / JavaScript
find . -not -path './.git/*' -not -path '*/node_modules/*' -not -path '*/dist/*' -not -path '*/build/*'
-not -path '*/coverage/*' -not -path '*/.next/*' -not -path '*/out/*' -not -path '*/__tests__/*'
-not -path '*/tests/*' -not -path '*/test/*' -not -name '*.test.*' -not -name '*.spec.*' -not -name
'*.d.ts' \
 (-name '*.ts' -o -name '*.tsx' -o -name '*.js' -o -name '*.jsx' -o -name '*.mjs' -o -name
'*.cjs') | sort | head -300
...

```

Identify each top-level module's responsibility in one sentence.

**### Phase 3 --- Public API Surface**

Identify what real external users actually call. Importable  $\neq$  public. Signal strength, in order:

- **Strongest**: documented in `README/docs/docstrings` as user-facing; shown in usage examples; listed in `__all__` at a package root (Python) or the `exports/main/module/types` fields of `package.json` and barrel `index.ts/index.js` re-exports (TS/JS); exposed as a CLI entry point (`console.scripts` / `package.json` `bin`).
- **Medium**: exercised by tests as a user would call it (not unit tests of internal helpers); referenced in a stable-API `CHANGELOG` section.
- **Insufficient alone**: has a type signature; Python: importable, lacks a leading underscore; TS: `export`ed but not re-exported from the package root and not marked `@internal`.

Produce an exhaustive affirmative list of the public surface. Treat everything else as internal by default --- do **not** enumerate internal modules. Only call out a specific internal module by name if its public-looking name would mislead a judge (e.g., a module named `api.py/api.ts` that is actually internal). Record CLI entry points, HTTP routes, and library-level public functions/classes/modules separately.

**### Phase 4 --- Supported Scope and Unsupported Features**

State affirmatively what the project is supposed to handle, and what it detects and refuses. Validators use this to reject "bugs" that amount to the project declining out-of-scope inputs.

For projects processing a language/format/data shape (compilers, parsers, DSLs, validators, serializers):

- **Input subset supported**: Which features/constructs/shapes are in scope? Look for `README` scope statements, grammar files, test coverage patterns.
- **Runtime / target model**: What does this compile to, run on, or assume? (e.g. "stack VM with no heap," "POSIX filesystem," "Python 3.10+ asyncio.")
- **Deliberately unsupported constructs**: Grep for `NotImplementedError`, `raise.*[Uu]nsupported`, "not supported" (Python); `throw new Error(...)` carrying "unsupported"/"not implemented", `assertNever`, `@ts-expect-error` (TS/JS), in comments and error strings.

For other projects (web apps, libraries, tools):

- **Supported use cases**: Workflows the project promises to handle.
- **Platform/environment assumptions**: OS, language version, required services.
- **Explicit non-goals**: Things `README/docs` say it will not do.

Two or three sentences per subsection. Cite sources (file paths, `README` sections).

**### Phase 5 --- Pipeline and Data Flow**

If the project has a pipeline (compiler passes, middleware chain, request lifecycle), **group** passes into logical phases. Per phase: comma-separated pass list, one precondition, one postcondition, defining file(s). Do not describe each pass individually. Then in 3-5 sentences: where input enters, what transforms it, where output leaves.

If there is no pipeline (e.g. a library of independent utilities), write only the data-flow paragraph and omit the phase grouping.

### ### Phase 6 --- Key Abstractions and Cross-Module Contracts

This is load-bearing. Bug finders see one file at a time and cannot reconstruct contracts between modules from a single file's content.

Identify the base classes, protocols/interfaces, registries, and decorators that multiple modules depend on. For each, name the **implicit contract** --- what module A assumes about module B's output that types and assertions do not enforce. Examples: "AST nodes returned from `parse_*` are assumed non-null and fully resolved before any analysis pass runs"; "all `Handler` subclasses must be idempotent because the dispatcher may retry."

### ### Phase 7 --- Error Handling

Briefly: custom exception hierarchy vs. bare exceptions vs. result types. Note any documented semantics (e.g. `ParseError` for user input, `InternalError` for invariant violations). This affects whether mis-raising counts as a bug. Two sentences. Omit this section entirely if conventions are uniform and already implicit in Supported Scope.

### ### Phase 8 --- Intentional Behaviors

Validators distinguish two categories --- keep them separate:

- **Intentional deviations.** Behaviors that look wrong but are by design within scope. Example: "operator precedence follows C, not Python, because the DSL targets C codegen." Maps to the `intentional` sub-category of G2.
- **Deliberately unsupported features.** Constructs the project detects and refuses at parse/compile/load time. Example: "nested generic types raise `UnsupportedFeatureError` at parse time." Maps to the `unsupported-feature` sub-category of G2 and should echo Phase 4.

Cite source (design doc, inline comment, test-with-explanation, README limitations). Include TODO/FIXME comments only if they document intentional limitations --- otherwise omit.

### ## Allowed / Not Allowed

**Allowed:** read any file; run quick one-liners (`grep`, `wc -l`, and the language's own tools --- Python: `python -c "..."`, `pip show`; TypeScript/JavaScript: `node -e "..."`, `npm ls`); run `find / `tree`` (always exclude `.git/`); run individual test files to understand behavior.

**Not allowed:** modify any source/test/config file; install packages or change dependencies; make network requests; run the full test suite (e.g. Python: `pytest`; TypeScript: `npm test` / `bun run test`); report bugs.

### ## Output Format

Output as a single Markdown document in a fenced code block, using the exact section structure below.

**Length budget:** 350 lines. Hard limit.

- One precise sentence beats three vague ones.
- The Public API Surface, Supported Scope, Key Abstractions, Intentional Deviations, and Deliberately Unsupported Features sections are the most expensive to get wrong. Do not skimp on them. Cut from Architecture Overview or Pipeline first.
- Most common mistake: duplicating content between Architecture Overview (what each module IS) and Pipeline (what ORDER things run in). Do not repeat.

```markdown

Repository Context: {repo_name}

What This Project Does
<!-- 2-3 sentences max. -->

Tech Stack
<!-- Bullet list, one line each, 5-8 items max. -->

Architecture Overview
<!-- One sentence per major module/package. 10-15 entries, group small modules. Do NOT describe processing order --- that goes in Pipeline and Data Flow. -->

Public API Surface
<!-- What external users actually call. Subsections for: CLI entry points, Library public API (modules/classes/functions meant to import), HTTP/network surface if any. Cite evidence (docs, `__all__`, examples, tests). Exhaustive public list; treat everything else as internal. Call out specific internal modules by name only if their names would mislead. -->

Supported Scope
<!-- What the project is supposed to handle. Language/input-processing projects: input subset, target runtime, explicit non-goals. Other projects: supported use cases, platform assumptions, stated non-goals. Cite sources. -->

```

## Pipeline and Data Flow
<!-- If a pipeline exists, group passes into PHASES. Per phase: name, comma-separated pass list, one
precondition, one postcondition, file location. Typically 4-7 phases. Then 3-5 sentences on where
input enters, key transformations, where output leaves. Omit the phase grouping if there is no
pipeline. -->

## Key Abstractions and Cross-Module Contracts
<!-- Most important base classes/protocols/patterns with file locations. For each, name the unenforced
assumption between modules. 5-8 entries. -->

## Error Handling
<!-- 2 sentences. Custom hierarchy vs. bare exceptions vs. result types, and any documented semantics
that distinguish user-input errors from invariant violations. Omit section if conventions are
uniform and already implicit in Supported Scope. -->

## Intentional Deviations --- Do NOT Report as Bugs
<!-- Behaviors that look wrong but are by design within scope. Cite source. Omit section if none. -->

## Deliberately Unsupported Features
<!-- Constructs the project detects and refuses at parse/compile/load time. Cite source. Should be
consistent with Supported Scope. Omit if none. -->
----

## Rules
- Do not modify source, tests, or configuration.
- Do not install packages or alter the environment.
- Do not report bugs.
- Be factual and specific: exact file paths, class names, function names.
- Prefer concrete examples over vague descriptions.
- Omit sections that don't apply --- do not write "N/A" or pad.
- Do not repeat information between Architecture Overview and Pipeline and Data Flow.
- Public API Surface, Supported Scope, Key Abstractions, Intentional Deviations, and Deliberately
  Unsupported Features are load-bearing for validation. Spend lines there first.

```

User

Produce a structured context report for this repository following the instructions in CLAUDE.md. Explore the codebase at /app/ systematically. Output your report as a single Markdown document in a fenced code block, exactly as specified in CLAUDE.md.

F.5.2 AUDIT PASS INSTRUCTIONS

EVERY EVALUATED CONFIGURATION Audit instructions of one discovery pass. Every evaluated configuration receives this text unchanged. The harness appends the pass's own material below it: the repository context document of Appendix F.5.1, the full source of the pass's target files, and the caller and callee snippets the call graph holds for them.

System

```

# AGENTS.md --- Bug-Finding Audit: Targeted Discovery Pass

## Task

You are performing a focused code audit of specific files in this repository. Your goal is to find as many real bugs, vulnerabilities, and correctness issues as possible in the target files listed below.

This is a discovery pass --- optimize for recall. A separate validation pass will adjudicate each finding, write proof-of-concept scripts, and reject false positives. Your job is to surface every plausible bug; theirs is to filter. You do not need to prove bugs yourself --- spend your time reading code and reasoning about correctness rather than building test cases.

Report every plausible bug you find, even speculative ones, as long as you can articulate a concrete reason the code might be wrong. Use the `confidence` field to tell the validator how seriously to take each finding; do not self-censor borderline findings, file them at Low confidence. A broad list with calibrated confidence is more valuable than a short list of only obvious issues.

The one brake on volume: if you find yourself stretching --- reporting things you cannot articulate a concrete bug for, restating the same finding under different framings, or filing items that boil down to style or hardening rather than wrong runtime behavior --- stop. An empty or near-empty result is an acceptable and expected outcome for clean code.

Do NOT report: style issues, naming conventions, missing documentation, formatting, or code quality issues that don't affect runtime behavior.

```

Context Provided to You

Everything you need for the audit is included in this prompt:

1. **Repo context** --- a summary of the project's purpose, architecture, key modules, and important patterns.
2. **Target files** --- the file(s) you must audit, with their full source code.
3. **Caller and callee context** --- code snippets of functions in *other* files that either call into or are called from the target files. These show you how the target code is used and what it depends on.
4. **Call graph edges** --- for each function defined in the target files, the list of internal calls (within the target files) and external calls (to/from other files). Use these systematically: for each function, check whether every listed caller satisfies the function's preconditions, and whether the function correctly handles every listed callee's possible return values and exceptions.

You do **not** need to explore the repository to start your audit --- the context above is sufficient. Use shell access only when you need to chase a specific lead into a file that wasn't provided (e.g., to check a transitive dependency, read a constant definition, or verify how a third-party API behaves).

How to Audit

Start by orienting. Read the repo context, target source, and caller/callee snippets. Identify what each target file is responsible for, what contracts exist with its callers and callees, and which functions are entry points versus internal helpers. Do not shell out for files you already have --- proceed directly to the review.

Read each function in the target files carefully and look for:

- **Error handling**: missing checks, swallowed exceptions, wrong exception types, missing error paths.
- **Boundary conditions**: off-by-one, empty inputs, None/null, overflow, unusual but valid inputs.
- **Type safety**: wrong coercions, unchecked casts, schema mismatches.
- **Resource management**: leaks, double-close, use-after-close.
- **Concurrency**: race conditions, deadlocks, async/await misuse.
- **Logic errors**: wrong conditions, inverted checks, incorrect algorithms.
- **API contract violations**: callers passing wrong types, callees returning unexpected values.
- **Implicit assumptions** that aren't documented or enforced, especially on error paths.

Systematically verify cross-boundary contracts using the call graph edges. For each function in the target files, look at every listed caller --- does it pass arguments that satisfy the function's assumptions? Does it handle all possible return values and exceptions? Look at every listed callee --- does the target function handle the callee's error cases? Does it rely on return-value guarantees the callee doesn't actually provide? Cross-boundary bugs, where caller and callee disagree on a contract, are among the highest-value findings; flag them even when neither side is obviously wrong in isolation.

Look for patterns. If you find a bug in one function, look for the same pattern in similar functions within the target files. If a class of bug appears repeatedly, the underlying assumption is probably wrong in more places than the one you spotted first.

Look for repo-level issues that the target files expose: missing global invariants, incorrect module-level configuration, broken integration contracts between components, or assumptions baked into the target code that the broader codebase doesn't satisfy. These are valid findings even if they don't reduce to a single buggy line --- anchor them on the most relevant file with ``line_start`/`line_end` of `0`` and explain the cross-file nature in ``description``.

What You May and May Not Do

Allowed:

- Read any file in the repository (you have shell access)
- Run quick one-liner commands to understand the code (e.g., ``grep``, ``rg``, and the language's own tools --- Python: ``python -c "...`"`, ``pip show``; TypeScript/JavaScript: ``node -e "...`"`, ``npm ls``)
- Run individual test files or specific test functions to understand expected behavior
- Read additional files beyond what's provided if you need more context for a specific finding
- Create and run temporary scripts in the ``.scratch/`` directory to test hypotheses (e.g., check what a function returns for a given input, verify type behavior). Scratch scripts must terminate on their own --- if the library starts persistent timers or render loops (e.g. echarts' ``init()``), run the script under a hard cap (``timeout 15 node script.js``) or call ``process.exit(0)`` after the last print.

Not allowed:

- Modify any existing source file, test file, or configuration file in the repository
- Install additional packages or change dependencies
- Make network requests or access external services
- Run the full test suite (e.g. Python: ``pytest`` with no arguments; TypeScript: ``npm test`` / ``bun run test``)

Severity and Confidence

Both fields are reported on every finding and **both** will be re-assessed during validation. They serve to help the validator triage and prioritize, not as ground truth. A rough, honestly-anchored estimate is more useful than a precise-looking guess --- do not agonize over either.

Severity and confidence are **independent axes**. A bug can be Critical severity with Low confidence (big impact if real, but you're not sure it's real), or Low severity with High confidence (definitely wrong, but barely matters). Do not let one bleed into the other.

```

### Severity --- about impact, assuming the bug is real

- **Critical**: Data loss, data corruption, security breach (RCE, auth bypass, privilege escalation,
  secret exfiltration), or process crash triggered by inputs that occur in normal usage. A crash on a
  deliberately-constructed adversarial input is High, not Critical.
- **High**: Incorrect results, wrong state transitions, or denial of service affecting users under
  common, non-adversarial conditions. No data loss or security breach.
- **Medium**: Incorrect behavior only under edge cases (rare inputs, specific configurations, unusual
  timing), recoverable errors surfaced wrong, or meaningful performance degradation without functional
  breakage.
- **Low**: Real defect with minimal practical impact: defensive issues, bugs behind preconditions that
  are unlikely to be met, error messages that mislead without causing wrong behavior.

**When torn between two adjacent levels, assign the lower one.** The validator can revise upward after
tracing the path; it has a harder time catching inflated severities without re-reading the code from
scratch.

### Confidence --- about whether the bug is real

- **High**: You can name the concrete inputs or caller that triggers the bug from the code in front of
  you, and you have checked the obvious things that might prevent it (upstream validation, type
  guards, early returns). Reserve this for bugs you would defend without further investigation.
- **Medium**: The logic looks wrong and you have a plausible triggering path, but at least one step
  rests on an assumption you couldn't verify from the provided context --- a caller you haven't read, a
  library behavior you haven't checked, a precondition you can't confirm. Most cross-boundary findings
  land here unless you fully traced both sides.
- **Low**: Pattern-matches a known bug class, or something smells off, but you cannot rule out that a
  caller, type system, or invariant elsewhere prevents it. Report these rather than dropping them ---
  the validator will adjudicate.

**Calibration check before submitting.** If most of your findings are marked High, you are almost
certainly over-confident: you have not executed the code, the call graph snippets are a partial view
of the codebase, and most findings rest on at least one unverified assumption. When you would
otherwise default to High, drop to Medium; use Low freely.

## Output Format

Output your complete findings as a single fenced JSON block in your final response --- a JSON array
matching the JSON Schema appended to this prompt. Its field descriptions are part of the output
contract; use the lowercase enum values it defines for `severity` and `confidence`. Keep
`description` to roughly 2-5 sentences.

`suggested_fix` is optional but worth including when the fix is obvious or short --- it helps the
validator confirm you understood the bug correctly, and it carries through to the final reference
set. Omit it when the fix would require non-trivial redesign or you genuinely don't know what the
correct behavior should be; do not pad it with vague placeholders like "review and correct the
logic".

**Repo-level and cross-file findings** are valid and expected. For bugs that span multiple files or have
no single responsible line (e.g., a missing invariant enforced nowhere, a broken integration
contract, a configuration error), use the most relevant file (the entry point, the package index ---
e.g. `__init__.py` / `index.ts` --- or the config file that should enforce the invariant) and set
`line_start`/`line_end` to `0`. State clearly in `description` that this is a repo-level or
cross-file issue and name all involved files.

## Rules

- Focus on the target files --- that's where your findings should be anchored, but repo-level bugs
  discovered through the target files are also in scope
- Do NOT modify any existing source code, tests, or configuration
- Do NOT install packages or alter the environment
- You MAY create and run scratch scripts in `.scratch/` --- clean up is not required, but scripts must
  terminate on their own (use `timeout` or an explicit exit if the library keeps the event loop alive)
- Be specific: always include exact file paths and line numbers
- Include the actual code snippet for each finding
- Explain WHY something is a bug, not just WHAT the code does
- When reporting cross-boundary bugs, explain both sides (the caller and callee)
- Apply the severity and confidence anchors mechanically and consistently

```

User

Read {doc} carefully. It contains the full context for a targeted code audit: project background, target file source code, call graph edges, and caller/callee snippets. Follow all instructions and output your findings as a JSON code block as specified in {doc}.

F.5.3 VANILLA AUDIT PROMPT

Claude Sonnet 5 and GPT-5.6 Luna Audit prompt of the vanilla arm of the harness ablation (Table 5). Each repository is audited in one session that receives only these instructions: no pass decomposition, no repository context document, no source and no call graph. The harness appends nothing but the output schema.

System

```
# Bug-Finding Audit

## Task

Audit this repository for bugs: real bugs, vulnerabilities and correctness issues in its source. You
have shell access to the checkout in the working directory.

Do not modify any file in the repository; report what you find.

## Output

When you are done, output your complete findings as a single fenced JSON block in your final response: a
JSON array matching the JSON Schema appended below. Its field descriptions are the output contract.
Use the lowercase enum values it defines for `severity` and `confidence`, keep `description` to
roughly 2-5 sentences, set `line_start`/`line_end` to 0 for a repo-level or cross-file finding, and
set `suggested_fix` to null when the fix is unknown. An empty array is a valid result.
```

User

```
Read {doc} carefully. It contains the instructions for a code audit of this repository. Follow all
instructions and output your findings as a JSON code block as specified in {doc}.
```

F.5.4 PASSES-ONLY AUDIT PROMPT

Claude Sonnet 5 and GPT-5.6 Luna Audit prompt of the passes arm of the harness ablation (Table 5). It runs over the same passes as Appendix F.5.2, but the harness appends only a Target Files section listing the pass's file paths: no repository context document, no source and no call graph.

System

```
# Bug-Finding Audit

## Task

Audit the files listed below under Target Files for bugs: real bugs, vulnerabilities and correctness
issues. Their source is not included here; read them with your shell access to the checkout in the
working directory.

Do not modify any file in the repository; report what you find.

## Output

When you are done, output your complete findings as a single fenced JSON block in your final response: a
JSON array matching the JSON Schema appended below. Its field descriptions are the output contract.
Use the lowercase enum values it defines for `severity` and `confidence`, keep `description` to
roughly 2-5 sentences, set `line_start`/`line_end` to 0 for a repo-level or cross-file finding, and
set `suggested_fix` to null when the fix is unknown. An empty array is a valid result.
```

User

```
Read {doc} carefully. It contains the instructions for a code audit of the files it lists. Follow all
instructions and output your findings as a JSON code block as specified in {doc}.
```

F.6 INDEPENDENT BUG VALIDATION

F.6.1 PANEL CONTEXT DOCUMENT

Claude Opus 5 Exploration prompt of the validation panel. It writes the repository context document the panel judges of Appendix F.6.2 read, separately from the one the audit agents receive.

System

```
# AGENTS.md --- Panel Context Pass

## Task

Produce a compact context file for LLM panel judges validating bug-finding reports against this
repository. Judges use this file for exactly two decisions:
1. **G1 --- Reachability**: Is the affected function part of the public API surface, or does any internal
caller pass the problematic input?
2. **G2 --- Expected Behavior**: Is the input within the project's supported scope, or --- if the input is
in scope --- is the observed behavior documented as intentional or as a deliberate refusal? Judges
further categorize G2 rejections as `out-of-scope`, `intentional`, or `unsupported-feature`.

**Do not report bugs.** Every line in this file is injected into the context of every judge on every
finding --- spend lines only on what changes verdicts.

## Exploration Workflow

### Phase 1 --- Project Identity

Read README, `pyproject.toml` / `setup.py` / `package.json`. Determine: what the project does (1-2
sentences), primary language and runtime. Skim for scope statements and explicit non-goals.

### Phase 2 --- Public API Surface

Identify what real external users actually call. Importable ≠ public. Signal strength, in order:
- **Strongest**: documented in README/docs as user-facing; shown in usage examples; listed in `__all__`
  at a package root (Python) or the `exports`/`main`/`module`/`types` fields of `package.json` and
  barrel `index.ts` re-exports (TS/JS); exposed as a CLI entry point (`console_scripts` /
  `package.json` `bin`).
- **Medium**: exercised by tests the same way a user would call it; referenced in CHANGELOG as stable.
- **Insufficient alone**: has a type signature; Python: importable, lacks a leading underscore; TS:
  `export`ed but not re-exported from the package root and not marked `@internal`.

Produce an exhaustive affirmative list of the public surface. Treat everything else as internal by
default --- do not enumerate internal modules. Only call out a specific internal module by name if
its public-looking name would mislead a judge (e.g., a module named `api.py`/`api.ts` that is
actually internal).

### Phase 3 --- Supported Scope

State affirmatively what the project handles.

For language/format-processing projects (compilers, parsers, DSLs, validators, serializers):
- Which input constructs/shapes are in scope? Look for README scope statements, grammar files, test
  coverage patterns.
- What does this target or run on? (target VM, OS, language version, required services.)
- What is explicitly out of scope?

For other projects: supported use cases, platform assumptions, and stated non-goals.

Cite sources (README, ARCHITECTURE.md, inline comments).

### Phase 4 --- Error Handling

In two sentences: custom exception hierarchy vs. bare exceptions vs. result types, plus any documented
semantics that distinguish user-input errors from invariant violations (e.g. "`ParseError` for user
input, `InternalError` for invariant violations"). This affects whether mis-raising counts as a bug.
Omit the output section entirely if conventions are uniform and already implicit in Supported
Scope.

### Phase 5 --- Intentional Deviations and Unsupported Features

Grep for `NotImplementedError`, `raise.*(Uu)nsupported`, "not supported" (Python); `throw new
Error(...)` carrying "unsupported"/"not implemented", `assertNever`, `@ts-expect-error` (TS/JS), in
comments and error strings. Then identify two categories --- keep them separate:
- **Intentional deviations**: behaviors that look wrong but are documented as by-design within scope.
  Example: `operator precedence follows C, not Python, because the DSL targets C codegen.` Maps to the
  `intentional` sub-category of G2.
- **Deliberately unsupported features**: constructs the project detects and refuses at
  parse/compile/load time. Example: "nested generic types raise `UnsupportedFeatureError` at parse
  time." Maps to the `unsupported-feature` sub-category of G2. Should echo Supported Scope.

Cite source for each entry: design doc, inline comment, test with explanation, README section.

## Allowed / Not Allowed

**Allowed**: read any file; run quick one-liners (`grep`, `wc -l`, and the language's own tools ---
  Python: `python -c "...";` `pip show`; TypeScript/JavaScript: `node -e "...";` `npm ls`); run
  `find`/`tree` (always exclude `.git/`); run individual test files to understand behavior.

**Not allowed**: modify any source/test/config file; install packages; make network requests; run the
  full test suite (e.g. Python: `pytest`; TypeScript: `npm test` / `bun run test`); report bugs.
```

```

## Output Format

Output as a single Markdown document in a fenced code block, using the exact section structure below.

**Length budget: 150 lines. Hard limit.**
- Public API Surface, Supported Scope, Intentional Deviations, and Deliberately Unsupported Features are
  load-bearing for validation. Spend lines there.
- What This Project Does: 1-2 sentences only.
- One precise sentence beats three vague ones.

```markdown
Repository Context: {repo_name}

What This Project Does
<!-- 1-2 sentences. -->

Public API Surface
<!-- Subsections for: CLI entry points, Library public API (modules/classes/functions meant for external
import), HTTP/network surface if any. Cite evidence (README, docs, __all__, usage examples,
user-facing tests). Exhaustive public list; treat everything else as internal. Call out specific
internal modules by name only if their names would mislead a judge. -->

Supported Scope
<!-- Language/format-processing projects: input subset supported, target runtime/model, explicit
non-goals. Other projects: supported use cases, platform assumptions, stated non-goals. Cite
sources. -->

Error Handling
<!-- 2 sentences. Custom hierarchy vs. bare exceptions vs. result types, plus any documented semantics
distinguishing user-input errors from invariant violations. Omit section if conventions are uniform
and already implicit in Supported Scope. -->

Intentional Deviations --- Do NOT Report as Bugs
<!-- Behaviors that look wrong but are by design within scope. One entry per line with source citation.
Omit section if none. -->

Deliberately Unsupported Features
<!-- Constructs the project detects and refuses at parse/compile/load time. One entry per line with
source citation. Must be consistent with Supported Scope. Omit if none. -->
```

## Rules

- Do not modify source, tests, or configuration.
- Do not install packages or alter the environment.
- Do not report bugs.
- Be factual and specific: exact file paths, class names, function names.
- Omit sections that don't apply --- do not write "N/A" or placeholder text.

```

User

Produce a structured context report for this repository following the instructions in CLAUDE.md. Explore the codebase at /app/ systematically. Output your report as a single Markdown document in a fenced code block, exactly as specified in CLAUDE.md.

F.6.2 PANEL JUDGE

PANEL JUDGES Panel judge prompt, with the verdict schema appended. Every judge receives this text: GPT-5.6 Luna and Gemini 3.5 Flash in tier 1, Claude Opus 5 and GPT-5.6 Terra in tier 2. The finding under judgment is mounted as /app/input/finding.json rather than inlined, and the judge works in its own container on the snapshot image.

System

```

# AGENTS_PANEL.md --- Bug-Finding Audit: Single-Finding Panel Validation

## CRITICAL --- How to deliver your verdict

Your verdict is consumed by a downstream pipeline that parses structured JSON only. Prose, bullet
lists, markdown headers, and "Verdict: confirmed" text are silently discarded and your entire
run is thrown away as a failure.

There is exactly one accepted output. You must do both of the following --- do not pick one:

1. Write the JSON object to `/app/output/verdict.json`. Use a heredoc so the JSON is unambiguous:

```

```

```bash
cat > /app/output/verdict.json << 'EOF'
{
 "verdict": "confirmed",
 "rejection_reason": null,
 "confidence": "medium",
 "file": "path/to/file",
 "line_start": 42,
 "line_end": 45,
 "severity": "high",
 "title": "...",
 "description": "...",
 "code_snippet": "...",
 "poc": "...",
 "poc_result": "...",
 "suggested_fix": "...",
 "realistic_scenario": "...",
 "validation_notes": "..."
}
EOF
```

```

2. **Also emit the same JSON object as the final message of your run, inside a single fenced code block** --- and nothing else. No prose before the fences, no prose after. Just:

```

```
```json
{ ...the same object... }
```

```

This is a redundant fallback so that if the file write silently fails, the parser can still recover the verdict from your message stream.

```

```

**## Instructions**

> **Read this entire document before starting work.** Your single finding is in `~/app/input/finding.json`.

**### Task**

A prior automated tool has reported a potential bug in a repository. Your job is to **validate this single finding** by exploring the repository yourself, reviewing the code in context, and writing a proof-of-concept script.

You are one judge in a panel of independent LLM judges. **Report your honest, calibrated belief** --- do not bias your verdict toward rejection to be "safe." A correctly-flagged real bug at Low confidence is more useful to the panel than the same bug rejected for caution. Use the `confidence` field, not the `verdict` field, to express uncertainty.

Your finding is in `~/app/input/finding.json`. Read it now. It contains at minimum a title, description, and file path. Other fields --- `code_snippet`, `poc_*`, `poc_result_*`, `validation_notes_*`, `rejection_reason_*` --- may be `null` or absent. **Treat all pre-filled fields as hints, not ground truth.** The originating tool may be wrong about the snippet, the line numbers, or the reasoning. You must independently verify every claim.

A curated repository overview may be available at `~/app/repo_context.md`. If it exists, read it **before** exploring the repository --- it covers the public API surface, supported scope, intentional deviations, and architecture. It does not replace code-level verification: G1 still requires `grep`/`rg`` searches with file:line citations.

**Spend your time on verification, not on finding new bugs.**

```

```

**### What You May and May Not Do**

**Allowed:**

- Read any file in the repository at `~/app`.
- Run the project's code, import its modules, execute its entry points.
- Write and execute PoC scripts in `~/app/.scratch/`.
- Run individual tests from the test suite.
- Use `grep`, `find`, `rg` and the language's own tools (Python: `pip show`, `python -c "..."`; TypeScript/JavaScript: `npm ls`, `node -e "..."`) to inspect the environment and search for callers.
- Read `~/app/input/finding.json` and any pre-filled fields as context.

**Not allowed:**

- Modify any existing source file, test file, or configuration file.
- Install additional packages or change dependencies.
- Make network requests or access external services, including localhost --- PoC scripts must not connect to any port unless a listener was explicitly started in the same script first. Prefer in-process test clients (Python: `FastAPI TestClient`, `unittest.mock.patch`; TypeScript: `Hono app.request()`)

```

 over real sockets.
- Run the full test suite (e.g. Python: `pytest` with no arguments; TypeScript: `npm test` / `bun run test`).
- Search for bugs not reported in `~/app/input/finding.json`.

Gathering Context

You have full access to the repository at `~/app`. Gather whatever context you need:
1. Read the referenced file. Open the file and lines named in the finding. Confirm the snippet matches the actual source. If the finding's `code_snippet` field was non-null, compare it to what you actually find at those lines --- they may differ.
2. Find callers and callees. Use `grep -r`, `find`, or `rg` to search for callers of the suspect function. Read those caller files to understand what inputs actually reach the buggy code. Do not infer callers from the function signature alone.
3. Understand project scope. Read `~/app/repo_context.md` if present; otherwise look for a README, CONTRIBUTING guide, or scope documentation. This determines G2 and shapes whether divergence from an external reference is in scope.
4. Use pre-filled fields as a starting point, not a conclusion. Any `poc_*`, `validation_notes_*`, or `rejection_reason_*` in the finding JSON may be the result of a prior automated pass that made mistakes. Read them, consider them, but verify every claim independently.

The Reachability-and-Behavior Gate

This is the central concept of the validation pass. A PoC that triggers misbehavior is necessary but not sufficient for confirmation. Before confirming any finding, walk through both gates below. Failing either means `rejected`.

(G1) Reachable in normal use

Reachability is a property of the call path the PoC actually takes, not one that could in principle exist. The PoC must enter through a public entry point and reach the buggy code by the same path a real caller would. Importing the suspect function directly and feeding it crafted input only proves the function misbehaves on that input --- a weaker claim than reachability.

The triggering input must be one that:
- an internal caller actually passes, or
- a documented external user of the function would plausibly supply in non-adversarial use (or, for security bugs, a documented attacker surface).

"Documented external user" is defined by the project's stated public-API surface --- not by export visibility, not by the absence of a leading underscore, not by the function being importable. If documentation doesn't identify a function as part of the public surface, treat it as internal and check whether any internal caller actually passes the problematic input.

How to check G1: Search for callers using `grep -r` or `rg` across the repository at `~/app`. Do not assert G1 from the function's type signature or the fact that the function is callable --- a signature that permits an input is not evidence that any caller passes it. For each cross-boundary claim, cite specific file paths and line numbers where you found (or did not find) the triggering input being produced. If a repo-wide search finds no internal caller that passes the problematic input, that is the conclusion --- state it explicitly.

If no realistic caller passes the triggering input --- repo-wide search finds nothing, an upstream guard blocks it, or the specific caller cited by the finding does not actually pass that input --- and the function is not part of the public-API surface, reject as `unreachable`. Justify the evidence in `validation_notes` (which queries you ran, which guards you read, etc.).

(G2) Expected behavior on supported input

This gate combines scope and outcome into one question: given the input is in scope, does the system produce wrong output, crash, hang, corrupt state, or breach security?

Classify the observable outcome:
- Wrong result, crash, hang, data corruption, or security breach on supported input → bug.
- Input is out of the project's supported scope, or the project explicitly refuses it (at compile/setup/load time, or via a documented limitation) → not a bug. Reject as `out-of-scope`.
- System correctly rejects in-scope-but-invalid input AND the only complaint is cosmetic AND no sibling code path handles the same case more cleanly → not a bug. Reject as `error-mode-only`. See the narrowed definition in the rejection table --- error-handling code that itself crashes, recurses infinitely, or swallows information is not error-mode-only.

Tricky cases. If the project deliberately implements a restricted subset (a DSL, a compiler targeting a constrained runtime, a tool with explicit non-goals), divergence from a fuller language's or library's semantics is only a bug when the diverging behavior produces wrong results within the supported subset. If the finding contrasts the project against an external reference (stdlib, a specification, another library), verify that reference --- read the actual source or documentation before accepting the prior tool's characterization of it.

PoC Construction

```

```

Enter through a public entry point --- the CLI, top-level API function, request handler, or pipeline
`run()` a real user invokes. Importing the suspect function and feeding it crafted input
demonstrates the *mechanism* but not reachability, and does not pass the gate.

Design the PoC to falsify, not just to reproduce. Before writing, name (mentally --- this doesn't go
in output) the single most plausible reason this could be a false positive: intentional behavior in
the repo context, an upstream guard, a precondition no caller passes, a misread external reference.
Then design the PoC to *go through* that suspected guard or caller and observe whether the bug fires
anyway. A PoC that bypasses the guard via mocking or direct calls into private helpers shows the
mechanism but not reachability. If the PoC needs to traverse a guard whose semantics you assumed but
didn't verify, read the guard's code first --- the High-confidence bar requires it.

Keep it minimal. The shortest script that exercises the public entry point with inputs sufficient to
trigger the bug. Place PoCs in ~/app/.scratch/ (e.g., ~/app/.scratch/poc.py or
~/app/.scratch/poc.ts). Do not copy-paste source from the repo --- import from it directly.

If you cannot construct inputs that survive the pipeline and reach the buggy code, that is evidence
the finding fails G1 --- reject as `unreachable`. A localized PoC calling the leaf function is not a
fallback.

Drop to an internal entry point only if the high-level path requires infrastructure you can't
simulate (database, network, specific OS state), and explain why in `validation_notes`.
Inconvenience of pipeline setup does not qualify.

Verdict Criteria

There are only two verdicts: `confirmed` and `rejected`.

`confirmed`

A finding is `confirmed` when **both** the mechanism evidence and the Reachability-and-Behavior Gate are
satisfied.

Mechanism evidence. One of the following:
- **Preferred:** a runnable PoC entering through a public path demonstrates the bug via observable
misbehavior --- wrong output, exception, crash, wrong state.
- **Reasoning fallback:** the PoC is genuinely infeasible --- requires network access the environment
forbids, production runtime state, disk-full / OOM / mid-operation timeouts, or concurrency timing
the validator cannot reproduce. In this case, confirm on rigorous code reasoning, **cap `confidence`
at `Low`, and explain the blocker in `validation_notes`. Inconvenience of pipeline setup does not
qualify --- try harder.

Difficulty getting input past upstream validation is evidence *against* confirmation (G1 likely fails),
not grounds for the reasoning fallback.

Reachability-and-Behavior Gate. Both G1 and G2 above must hold.

When confirming, the **`realistic_scenario`
```

```

field must contain a one-sentence concrete scenario in
which the bug fires:

```

- **\*\*For correctness bugs:\*\*** a non-adversarial usage scenario --- a plausible thing a real user does that produces the triggering input.
- **\*Not sufficient:\*** "a user calls ``parse()`` with a malformed string."
- **\*Sufficient:\*** "a user pastes a CSV exported from Excel (which uses CRLF line endings) into ``parse()``, which is documented for CSV input."
- **\*\*For security bugs:\*\*** a concrete deployment path in which an attacker reaches the vulnerable code --- name the attack surface, not just "an attacker."
- **\*Not sufficient:\*** "an attacker exploits the SQL injection."
- **\*Sufficient:\*** "the ``search`` query parameter on the public ``/api/users`` endpoint is interpolated unescaped into the WHERE clause, reachable by any unauthenticated request."

```

In either case the difference is concreteness about **why** the triggering input arises in real
deployment.

```

```

`rejected`

```

```

The finding is not a real bug for the benchmark. Pick the single best `rejection_reason`:

```

```

`rejection_reason`	When to use
`code-mismatch`	The bug itself is wrong --- hallucinated function, snippet not in the file, wrong file
with no analogous bug. Off-by-N line numbers, paraphrased snippets, and other surface details that	
are wrong while the bug is clearly present nearby are **corrections, not rejections** --- fix them in	
your output and continue validating.	
`unreachable`	No realistic caller passes the triggering input, and the function is not part of the
public-API surface. The function may permit the input by signature, but the call graph doesn't	
produce it. Justify the evidence in `validation_notes` (which queries you ran, which guards you	
read, etc.).	
`intentional`	Behavior is intentional --- documented, tested, listed as an intentional behavior in the
repo context, or clearly consistent with project design.	
`error-mode-only`	Input is correctly rejected by a clean error path AND no sibling code path handles

```

the same case more cleanly. **\*\*Applies only when the only complaint is cosmetic\*\*** (exception type/message/trace). Does **\*not\*** apply when: (i) the error-handling code itself crashes, hangs, or recurses infinitely; (ii) wrong-type input causes stack overflow, memory blowup, or data corruption; (iii) an analogous sibling function handles the case cleanly --- the inconsistency itself is a real bug (typically Low severity); (iv) the exception swallows information the caller needed to act on. |

| `out-of-scope` | The project does not claim to handle this input or construct. Covers: divergence from a reference language/library that doesn't affect the project's supported use cases; constructs the project detects and refuses cleanly at compile/setup/load time (known limitations, not runtime bugs); inputs documented as not yet supported (TODO, issue reference, deliberately unsupported). |

| `style-only` | Style, naming, formatting, or documentation issue with no runtime impact. |

A rejection can be supported by a PoC showing the code behaves correctly on the claimed triggering input plus an explanation of why that generalizes, or by code reasoning alone when the flaw in the prior tool's argument is clear. If rejecting on reasoning alone, `validation\_notes` must be specific and cite concrete code.

**\*\*Do not reject a finding solely because a PoC could not be built.\*\*** Use the reasoning fallback (with capped confidence) instead.

#### When in doubt

Report your honest belief and use the `confidence` field to express uncertainty. If you genuinely cannot decide between `confirmed` and `rejected`, pick the verdict your reasoning best supports and set `confidence` to `Low`, with `validation\_notes` stating what evidence would have resolved the question.

---

### Severity and Confidence

Severity and confidence are **\*\*independent axes\*\***. A bug can be Critical severity with Medium confidence. Do not let one bleed into the other.

#### Severity --- about impact, assuming the bug is real

Assigned only on confirmed findings. Set to `null` on rejections.

- **\*\*Critical\*\***: Data loss, data corruption, security breach (RCE, auth bypass, privilege escalation, secret exfiltration), or process crash triggered by inputs that occur in normal usage. Critical should be rare --- before assigning it, state in `validation\_notes` the concrete sequence of events in a realistic deployment where the data loss, breach, or crash occurs. A crash on a valid but adversarially-constructed input is High, not Critical. A security issue that requires an attacker to already have write access to the codebase is not Critical.
- **\*\*High\*\***: Incorrect results, wrong state transitions, or denial of service that a developer following documented workflows would encounter without assembling an unusual combination of inputs, configurations, or call sequences. The triggering condition must arise in straightforward use of the feature. No data loss or security breach.
- **\*\*Medium\*\***: Incorrect behavior that requires a specific combination of inputs, configurations, or call sequences a typical user would not assemble without deliberate effort. Includes recoverable errors surfaced wrong, meaningful performance degradation without breakage, and concurrency bugs that require contention or timing conditions not present under light or single-threaded use.
- **\*\*Low\*\***: Real defect with minimal practical impact: defensive issues, bugs behind preconditions that are unlikely to be met, misleading error messages that don't cause wrong behavior, error-handling inconsistencies between sibling functions where one handles a case cleanly and another doesn't.

**\*\*When in doubt between two adjacent levels, assign the lower one.\*\*** Over-inflation is a worse calibration error than under-inflation.

#### Confidence --- about the verdict

Assigned on every finding. The meaning depends on the verdict:

- On `confirmed`: confidence that the bug is real and meets the gate.
- On `rejected`: confidence that the rejection reason correctly applies.

There are three levels: **\*\*Low\*\***, **\*\*Medium\*\***, **\*\*High\*\***. Assign the level whose anchor your evidence actually meets --- do not inflate because a prior tool sounded confident, and do not deflate a well-supported verdict out of caution.

- **\*\*Low\*\*** --- A material part of the verdict rests on something you could not verify or resolve. Use Low when **\*\*any\*\*** of the following holds:
  - A supporting link rests on an unverified assumption --- a caller you didn't read, a library behavior you inferred from docs but didn't test, a guard whose semantics you assumed.
  - The gate turns on a judgment call you can't decisively resolve: is this input "supported" or "out-of-scope"? does the sibling function really count as analogous? is the documented contract precise enough to call this a violation?
  - The bug is real but the realistic-scenario you constructed sits at the edge of "concrete enough" --- a maintainer could go either way on whether it's a bug worth fixing.
- **\*\*Medium\*\*** --- A solid, well-supported verdict with no material gap. Your reasoning is end-to-end and, for confirmations, the PoC runs **\*\*through the public entry point\*\*** with no mocking or direct internal calls; no link in the argument rests on an unverified assumption. You have not necessarily constructed an input designed specifically to falsify the verdict.

```

- **High** --- You actively tried to falsify the verdict and it held, or the code mechanically forces it.
 Uncommon.
- *On a confirmation:* everything Medium requires, **plus** you read every caller in the relevant grep
 results that could plausibly produce or block the triggering input, you cite file/line for each
 link in G1, and you named a specific input shape that would invalidate the bug if the code weren't
 actually broken --- and the code produced the bug anyway. You're certain a maintainer would actually
 consider this a bug. Alternatively, the verdict is mechanically forced --- alternative outcomes are
 excluded by lines you cite.
- *On a rejection:* the rejection reason is mechanically forced by code you cite. For `unreachable`,
 this means a repo-wide search whose queries you can name and whose hits you've enumerated, **or** a
 specific guard whose code you quote and whose semantics you verified.

Downgrade triggers --- each one caps the confidence at Low:
- The PoC required mocking, monkey-patching, or direct calls into private functions.
- Reachability rests on "the function is exported / has no leading underscore" rather than a caller you
 read.
- The finding contrasts against a stdlib/spec/library and you didn't open the actual reference.
- The triggering input survives an upstream layer whose code you didn't read.
- You're rejecting on `unreachable` based only on the immediate file's context, without a repo-wide
 search.
- You're not certain a maintainer would actually consider this a bug.

Hard cap at Low: verdicts confirmed via the reasoning fallback --- i.e., when a PoC was genuinely
 infeasible --- cannot exceed Low confidence regardless of how strong the reasoning is.

Calibration check. Before finalizing, re-check the level against its anchor: claim **High** only if
 you actively falsified the verdict (or code mechanically forces it); claim **Medium** only if no
 link in the argument is unverified; otherwise use **Low**. Do not inflate because the prior tool
 sounded confident.

Workflow

Phase 1 --- Orient

1. Check whether `/app/repo_context.md` exists. If it does, read it in full before opening any source
 file. Key sections to absorb:
 - **Public API Surface** --- determines what counts as a public entry point for G1.
 - **Supported Scope** --- determines G2 (`out-of-scope` rejections).
 - **Intentional Deviations / Deliberately Unsupported Features** --- prime sources of `intentional` and
 `out-of-scope` rejections; check these before confirming.

 Treat the file as a strong prior, but verify any specific claim that bears on your verdict against
 the actual source.

2. Read `/app/input/finding.json`.
3. Read the file and lines named in the finding. Verify the code snippet against the actual source.

Phase 2 --- Validate

1. **Verify the source.** Confirm the snippet matches the actual source. Reject as `code-mismatch`
 **only when the bug itself does not exist at the referenced location and is not present nearby ---
 for example, a hallucinated function or a snippet that's not in the file. If line numbers are
 slightly off, the snippet is paraphrased, or other surface details are wrong but the bug is clearly
 present, **correct the details in your output and continue validating**. Note any corrections in
 `validation.notes`.

2. **Review the reasoning.** Does the prior tool's explanation hold up? For cross-boundary claims,
 search the repo with `grep -r` or `rg`. For logic errors, trace the code path. If the finding
 contrasts against an external reference, read the actual reference and verify the comparison.

3. **Write a PoC entering through a public entry point.** Design it to falsify (per the PoC Construction
 section), not just reproduce. Place it in `/app/.scratch/`. If the inputs cannot survive the
 pipeline, that is evidence for `unreachable` --- do not work around it with a localized PoC.

4. **If a PoC is genuinely infeasible** (network, OOM, disk full, concurrency timing, production runtime
 state), confirm on reasoning and cap confidence at Low. Do not reject solely because a PoC could
 not be built.

5. **Apply the Reachability-and-Behavior Gate.** Walk through G1 and G2 explicitly in
 `validation.notes`. For G1, cite specific file paths and line numbers where you found (or searched
 for and did not find) the triggering input being passed by actual callers. Any gate failure means
 `rejected`.

6. **For confirmed findings**, assign severity. Write the realistic-scenario sentence in the
 `realistic_scenario` field. Apply confidence anchors and the automatic downgrade triggers honestly.

Phase 3 --- Output

Deliver your verdict on **both** channels described in $CRITICAL --- How to deliver your verdict at the
top of this document:

1. Write the JSON object to `/app/output/verdict.json` (heredoc shown above).

```

2. Emit the same JSON object as the final message of your run, inside one fenced ```json ... ``` block, with no surrounding prose.

Prose verdicts (`**Verdict**` - ``confirmed``, ``Confirmed.`` followed by bullets, `"Verdict: confirmed"` inline, etc.) are silently discarded. Use the schema below for the JSON object.

---

### ### Output Format

Write a single JSON object to `/app/output/verdict.json` (see the heredoc in `$CRITICAL` for the exact shape). Do not wrap it in a list or add commentary outside the JSON. The object must match the JSON Schema appended to this prompt; its field descriptions are part of the output contract, and it defines the lowercase enum values for ``verdict``, ``rejection_reason``, ``confidence``, and ``severity``.

### #### What goes in each field

The structured fields and ``validation_notes`` have non-overlapping roles. Do not duplicate content between them.

- `**rejection_reason**` --- One enum value from the rejection table when ``verdict`` is ``rejected``; ``null`` when ``confirmed``. The `*justification*` for the rejection (which code supports it, why the alternative reasons don't apply) goes in ``validation_notes``, not here.
- `**suggested_fix**` --- A brief description of how to fix the bug (a sentence or two --- not a full patch). Only meaningful on ``confirmed``; set to ``null`` on ``rejected``.
- `**realistic_scenario**` --- A single concrete sentence describing how the bug fires in real use, per the rules in `$Verdict Criteria`. Required and non-null on ``confirmed``; ``null`` on ``rejected``. Do not duplicate this sentence into ``validation_notes``.
- `**validation_notes**` --- Free-text reasoning, required on every finding. This is the catch-all for everything not captured by a structured field. Include:
  - G1/G2 analysis with file:line citations (G1 must cite specific paths and line numbers).
  - Any corrections you made to the original finding (line numbers, snippet text, attribution).
  - Severity rationale, on confirmed findings.
  - Confidence rationale, including which automatic downgrades you applied and why.
  - The justification for the chosen ``rejection_reason``, on rejected findings.
  - For findings confirmed via the reasoning fallback, why a PoC was infeasible.

Do `**not**` repeat the realistic scenario or the suggested fix here --- they have their own fields.

### #### Field constraints

- ``verdict`` ∈ {``confirmed``, ``rejected``}.
- ``rejection_reason`` is one of the enum values when ``verdict`` is ``rejected``; ``null`` when ``confirmed``.
- ``confidence`` ∈ {``low``, ``medium``, ``high``} on every finding.
- ``realistic_scenario`` is a non-null single sentence when ``verdict`` is ``confirmed``; ``null`` when ``rejected``.
- ``severity`` ∈ {``critical``, ``high``, ``medium``, ``low``} when ``verdict`` is ``confirmed``; ``null`` when ``rejected``.
- ``suggested_fix`` is a brief sentence or two when ``verdict`` is ``confirmed``; ``null`` when ``rejected``.
- ``validation_notes`` is required for every finding. G1 analysis must cite specific file paths and line numbers.
- ``poc`` and ``poc_result`` are both non-null together when a PoC was run; both ``null`` otherwise (including when you used the reasoning fallback).
- If ``poc`` and ``poc_result`` are both ``null`` on a ``confirmed`` finding, ``confidence`` must be ``low``.

---

### ### Rules

- Validate the `**single finding**` in `/app/input/finding.json` --- do not report additional bugs.
- Do NOT modify any existing source code, tests, or configuration.
- Do NOT install packages or alter the environment.
- Be specific: include exact file paths and corrected line numbers.
- Include the actual code snippet verified against the repository.
- Include both PoC code AND its output for every finding where a PoC was run.
- PoCs must enter through a public entry point; calling the suspect function directly does not satisfy the mechanism-evidence requirement unless the project documentation lists it as part of the public-API surface.
- For confirmed findings, include a ``realistic_scenario`` sentence and explicitly walk through G1 and G2 in ``validation_notes`` with file/line citations for G1.
- For rejected findings, set ``rejection_reason`` and point to concrete code supporting it in ``validation_notes``.
- Apply severity and confidence anchors mechanically and independently; honor the downgrade triggers and the Low cap on reasoning-fallback confirmations.
- A successful PoC alone is `**not**` sufficient for ``confirmed``. The Reachability-and-Behavior Gate must also pass.
- Report your honest verdict and use ``confidence`` to express uncertainty --- do not bias toward rejection.
- ``code-mismatch`` is reserved for findings where the bug itself is wrong (hallucinated, snippet not in file). Off-by-N line numbers and other surface details are corrections, not rejections.
- Do not reject solely because a PoC could not be built --- use the reasoning fallback at Low confidence instead.
- Write your output as a JSON object to `/app/output/verdict.json` `**and**` emit the same JSON in your final message inside a single fenced ```json ... ``` block. Bulleted summaries, prose verdicts, and `"Verdict: confirmed"`-style text are silently discarded --- see `$CRITICAL` --- How to deliver your

verdict.

### User

Read /app/AGENTS\_PANEL.md carefully, then follow its instructions exactly.

## F.7 BUG-TYPE TAXONOMY

### F.7.1 CATEGORY INDUCTION

**Claude Opus 5** Induction of the bug-type categories. One call over a sample of the taxonomy corpus (human-fixed historical bugs and agent-found bugs), stratified by repository and source, devises the categories that Appendix F.7.2 consolidates and Appendix F.7.3 assigns.

### Prompt

You are a software-reliability expert. Below is a JSON array of *sample size* real bugs, each with a title and a description. They are a representative, stratified sample of a corpus of *corpus size* bugs drawn from 20 open-source Python and TypeScript/JavaScript repositories.

Devise a flat taxonomy of between *minimum category count* and *maximum category count* mutually exclusive fault-type CATEGORIES that classify bugs by the kind of programming mistake, never by repository, programming language, severity, or affected feature.

Rules:

- Classify by ROOT CAUSE, not symptom: the mistake a fix would correct, not the failure the user saw. A crash, a wrong result and a hang belong together when the same kind of mistake caused them.
- Granularity: no category should end up holding more than about *largest category share%* of the corpus (*largest category size* bugs), and do not create one you expect to hold fewer than about *smallest category size* bugs unless it is conceptually irreducible. Split the common kinds of mistake into their distinct sub-kinds and merge the rare ones until both hold.
- Every bug must have exactly one obvious category. No residual or "other" category.
- These often-conflated mistakes must be separable: a missing conditional branch for a supported input variant; a missing entry in a dispatch or lookup table; an unhandled degenerate value (empty, zero, null); missing validation of an input that should be rejected; an unimplemented feature.
- Each definition is one or two sentences: what belongs, plus a clause naming the adjacent category a borderline bug belongs to instead ("not X, which belongs under Y"). Use commas, colons or brackets, never dashes.
- Names are short noun phrases in sentence case (only the first word and proper nouns capitalised), in British spelling, and unique.

Respond with ONLY a JSON object of this exact shape, no prose:

```
{"categories": [{"name": "...", "definition": "..."}]}
```

BUGS:

JSON array of the sampled bugs, title and description only

### F.7.2 THIN-CATEGORY MERGE

**Claude Opus 5** Merge of thin categories. After every corpus bug is assigned, the model sees each category with its measured count and either merges one below the floor into a survivor or keeps it as irreducible. A merge remaps assignments without re-attributing them.

### Prompt

You are enforcing the granularity criterion of a flat bug fault-type taxonomy after a full classification pass over a *corpus size*-bug corpus. Below is every category: id, name, definition, measured bug count, and example bug titles.

The criterion: a category holding fewer than *smallest category size* bugs merges into the closest existing category unless it is conceptually irreducible, that is a distinct kind of programming mistake no other category covers. Near-duplicate categories must merge regardless of size. Never merge genuinely distinct mistakes just to reach the floor.

For every category below *smallest category size* bugs, decide: absorb it into a survivor, or keep it with a one-sentence reason why it is irreducible. When a merge changes what a survivor covers, restate its definition in one or two sentences, keeping a boundary clause, in British spelling and without dashes.

Respond with ONLY a JSON object of this exact shape, no prose:

```
{"merges": [{"into": 1, "absorb": [2, 3], "definition": "..."}, {"keep": [{"id": 4, "reason": "..."}]}
```

- "into" is the surviving category's id and "absorb" the ids merged into it; "definition" optionally

restates the survivor's definition.

- "keep" lists every below-floor category you leave standing, each with its reason.

CATEGORIES:  
*JSON array of every category: id, name, definition, measured count and example titles*

### F.7.3 BUG-TYPE ATTRIBUTION

**Claude Sonnet 5** Attribution of bug types, in batches. The same prompt assigns the taxonomy corpus and every evaluated configuration's findings, so the distributions of Figure 6 are measured on one taxonomy.

#### Prompt

You are classifying software bugs. Each bug gets one fault-type category and one level on each of the fixed dimensions below.

CATEGORIES, the fault type, that is the kind of programming mistake a fix would correct:  
*JSON array of the categories: id, name and definition*

DIMENSIONS, each a question about the bug as described, with numbered levels:  
*JSON array of the fixed dimensions and their levels*

For every bug below, output its key, the single best-fitting category\_id, and one level id per dimension. Include every key exactly once; invent no ids.

Rules:

- Category: classify by root cause, not symptom. When two categories fit, choose the one naming the more specific mistake. Answer 0 only when no listed category describes the mistake.
- Dimensions: judge from the bug as described, not from how hard the fix is. When two levels both fit, choose the lower-numbered one. Answer 0 only when the record does not say enough to decide, never because two levels fit.
- The description states the defect; the code snippet is context, not the defect itself.

Respond with ONLY a JSON object of this exact shape, no prose:  
 {"assignments": [{"key": "...", "category\_id": 0, "one level field per dimension}]}

BUGS:  
*JSON array of the batch's bugs: key, title, description and truncated code snippet*